

MATERIAL LISTS

FOR

HOMES

SHOWN ON

1938 CALENDAR

— CITY —

THE ESTIMATES OF COSTS for all homes shown
on 1938 City Calendars are listed and itemized
on PAGE 3 of this book

INDEX

DESIGN	PAGES	DESIGN	PAGES
JANUARY	4, 5, 6 and 7	JULY	22 and 23
FEBRUARY	8 and 9	AUGUST	24 and 25
MARCH	10 and 11	SEPTEMBER	26 and 27
APRIL	12 and 13	OCTOBER	28, 29, 30 and 31
MAY	14, 15, 16 and 17	NOVEMBER	32 and 33
JUNE	18, 19, 20 and 21	DECEMBER	34 and 35

Floor Plans are Shown
on Pages 36, 37 and 38

KEEP THESE VALUABLE LISTS IN A SAFE PLACE
For Use of The Office Force Only
NATIONAL PLAN SERVICE, INC.
1315 W. Congress Street
Chicago, Illinois

CONFIDENTIAL INFORMATION

IMPORTANT FACTS

The most important fact desired by the prospective builder is the total cost of the home, including all material and all labor.

It is necessary that the prospective builder has this completed building cost to aid him to arrange his finances accordingly, or to aid him to select a home within his means. Hence, to enable the retail lumber dealer to give this valuable and necessary information, complete cost estimates of all designs are shown on page 3.

The estimates herein will enable the dealer to tell almost instantly to the prospective builder the approximate cost of the home, including both the complete costs of materials and labor.

Lumber Dealers selling the Completed Home will wish to establish an accurate price based on local conditions, for each home. Therefore, these estimates of costs and material lists will be of that much additional value for their convenience and guidance.

Each dealer should have his contractor refigure the entire job, specifying the materials prevailing in local territory. Local conditions may permit great reduction in the cost of these houses, depending upon wage rates, cost and quality of materials.

NOTE:

THE FOLLOWING PRICES AND INFORMATION WERE USED IN COMPUTING THE ESTIMATES OF COSTS GIVEN ON PAGE 3.

LUMBER AND ROOFING PRICES

2" Dimension—8 Ft. to 16 Ft. Long....	\$ 55.00 per Thousand Feet
2" Dimension—18 Ft. and Longer, and Timbers	65.00 per Thousand Feet
Sheathing, Boards, Sub-flooring	42.00 per Thousand Feet
Furring, Bridging, Etc.....	50.00 per Thousand Feet
½" Bev. Siding.....	60.00 per Thousand Feet
¾" Bev. Siding.....	120.00 per Thousand Feet
⅝ x ¾" Ceiling.....	50.00 per Thousand Feet
Plain Sawed Flooring.....	75.00 per Thousand Feet
1" Finish	100.00 per Thousand Feet
Wood Shingles, Not Stained (For Roof)	7.00 per Square
24" ½ Wall Shingles.....	13.00 per Square
18" ½ Wall Shingles.....	11.00 per Square
Asphalt Shingles	8.50 per Square

The surface square feet to be insulated is given in the material lists. Owing to the various methods employed, it is included in the estimates of costs under additional.

MILLWORK PRICES

Millwork figured at good manufacturers' average factory prices to the dealer, plus 50%.

Outside Moulding and Millwork figured soft wood.
Inside Trim was figured yellow pine.
All Doors were figured stock designs.
Stair Material was figured yellow pine.
Windows and Sash were figured white pine.

NOTE: The lumber dealer at any time, can refer to the millwork list of any design and figure the millwork according to his own prices.

It is advisable to revise millwork figures as and when price changes occur.

HARDWARE AND BUILDING PAPER

Hardware was figured at present market prices as quoted by retail hardware dealers.

Building paper figured at \$2.50 per roll.

CARPENTER LABOR

Carpenter labor has been figured at the rate of \$1.00 per hour, plus 15 per cent added for the benefit of the contractor or builder.

If desired this rate can be changed to meet any scale of carpenter wage. The hours of carpenter labor for each design are given in the estimates of costs.

MASONRY MATERIALS AND LABOR

Excavating:

Excavations were figured at average rate of 50 cents per cubic yard. Trench work figured at the rate of \$1.25 per cubic yard.

Concrete Foundation and Footings:

Were figured at the rate 52 cents per cubic foot, including the cost of making forms.

Cement Floors:

4" thick with trowelled finish were figured at the rate of 14 cents per square foot.

Cement Steps:

The average size 7" rise 12" run were figured at the rate of 60c per lineal foot.

Brick Work:

Common brick were figured at the rate of \$30.00 per thousand laid in the wall. Face Brick were figured at \$60.00 per thousand laid in the wall.

Fire Clay Brick were figured at \$65.00 per thousand laid in the wall.

Face Brick for fireplaces were figured at \$75.00 per thousand laid in the wall.

Miscellaneous:

Flue Linings, Tile, Dampers, Ash Dumps, Cleanout Doors, and Iron Lintels are included in the estimates when called for in plans and itemized lists.

Plastering:

All interior plastering was figured at the rate of 90 cents per sq. yard. Includes plaster, base, nails, metal corner beads and strips. Cement plaster and stucco at \$1.25 per sq. yard.

NOTE: If masonry materials and labor as estimated herein do not conform to local rates or costs, then refer to the material lists in which all the masonry material is itemized. The concrete and cement work, brickwork, stone, plastering, etc., can be repriced at regular local rates.

SHEET METAL

Sheet metal was figured at present market prices as quoted by sheet metal contractors.

PAINTING

The paint, varnish, etc., were figured at the regular retail selling price, plus the labor for painters at the rate of \$1.00 per hour.

ELECTRIC WIRING

Material and labor were figured at the rate of \$2.50 per outlet. Switches were figured at the rate of \$2.50 per one-way or \$5.00 per two-way. Meter, Service Box and Service Switch total \$7.50.

All wiring was figured according to the rules of the National Board of Underwriters.

ELECTRIC FIXTURES

All electric fixtures were figured on the same basis as the hardware.

PLUMBING, DRAINAGE, SEWERAGE AND FUEL GAS

The following average prices for fixtures were used in this estimate:—Kitchen Sink, \$41.00; Bath Tub, \$68.00; Lavatory, \$16.00; Water Closet, \$18.00; Two Compartment Laundry Tubs with Stand, \$11.00; Coal-Fired Water Heater with 30-Gal. Tank, \$28.00. Plumbing Estimate also includes all materials and labor for sewers and Water Supply figured 20 Ft. in front of building, all Stacks and Sanitary Revents, Overflow Drains and Sewerage. Gas Piping, in most cases was figured for two fuel openings. Labor for installing the above was figured at the rate of \$1.00 per hr.

As local conditions regarding Plumbing, Sewerage, etc., vary, it is advisable to have the local plumbing contractor quote prices.

WARM AIR FURNACES

First-grade furnaces were estimated prices complete with flues, stacks, shoes, registers, fresh air intakes, tools and all equipment.

COOLING SYSTEMS

For these homes a cooling system or air conditioning system has been provided for as an extra item.

This system does not include refrigeration, but is a very effective cooling system designed and equipped with thermostatic control to furnish filtered air the year round.

ESTIMATED COSTS OF CONSTRUCTION

Estimates Based on Scale of Prices Shown on Page 2 and
Per Our Itemized Material List

DESCRIPTION	JAN.	JAN. (ALTERNATE)	FEB.	MAR.	APRIL
LUMBER	\$ 1267 00	\$ 1223 00	\$ 1243 00	\$ 885 00	\$ 895 00
MILLWORK	947 00	1022 00	913 00	625 00	767 00
HARDWARE	141 00	143 00	136 00	98 00	116 00
CARPENTER LABOR	981 00	1039 00	949 00	653 00	789 00
EXCAVATING	98 00	98 00	89 00	75 00	86 00
MASONRY WORK	841 00	816 00	856 00	749 00	1003 00
PLASTERING	583 00	583 00	572 00	330 00	407 00
SHEET METAL	49 00	141 00	79 00	43 00	65 00
PAINTING	264 00	266 00	257 00	186 00	220 00
ELECTRIC WIRING & FIXTURES	200 00	200 00	203 00	128 00	154 00
PLUMBING & SEWAGE	505 00	505 00	460 00	420 00	460 00
WARM AIR HEAT	293 00	293 00	285 00	173 00	211 00
TOTAL COST	\$ 6169 00	\$ 6329 00	\$ 6042 00	\$ 4365 00	\$ 5173 00
ADD-AIR CONDITIONING	160 00	160 00	160 00	160 00	160 00
ADD-VAPOR HEAT	352 00	352 00	342 00	208 00	254 00
ADD-HOT WATER HEAT	528 00	528 00	513 00	311 00	381 00
ADD-INSULATION	170 00	170 00	230 00	138 00	162 00
CARPENTER HOURS	853 HRS.	904 HRS.	825 HRS.	568 HRS.	686 HRS.

DESCRIPTION	MAY	MAY (ALTERNATE)	JUNE	JUNE (ALTERNATE)	JULY	AUG.
LUMBER	\$ 984 00	\$ 1055 00	\$ 1006 00	\$ 901 00	\$ 1232 00	\$ 1297 00
MILLWORK	814 00	728 00	630 00	507 00	1043 00	983 00
HARDWARE	131 00	129 00	119 00	103 00	155 00	134 00
CARPENTER LABOR	678 00	758 00	735 00	614 00	1041 00	998 00
EXCAVATING	69 00	69 00	115 00	115 00	100 00	111 00
MASONRY WORK	908 00	916 00	792 00	788 00	941 00	905 00
PLASTERING	429 00	429 00	357 00	357 00	537 00	492 00
SHEET METAL	82 00	84 00	95 00	160 00	113 00	94 00
PAINTING	195 00	222 00	202 00	185 00	241 00	264 00
ELECTRIC WIRING & FIXTURES	140 00	140 00	135 00	135 00	161 00	184 00
PLUMBING & SEWAGE	460 00	460 00	420 00	420 00	505 00	505 00
WARM AIR HEAT	252 00	252 00	179 00	179 00	315 00	260 00
TOTAL COST	\$ 5142 00	\$ 5242 00	\$ 4785 00	\$ 4464 00	\$ 6384 00	\$ 6227 00
ADD-AIR CONDITIONING	160 00	160 00	160 00	160 00	160 00	160 00
ADD-VAPOR HEAT	302 00	302 00	215 00	215 00	378 00	311 00
ADD-HOT WATER HEAT	454 00	454 00	323 00	323 00	567 00	468 00
ADD-INSULATION	174 00	174 00	153 00	153 00	179 00	153 00
CARPENTER HOURS	588 HRS.	659 HRS.	639 HRS.	533 HRS.	905 HRS.	868 HRS.

DESCRIPTION	SEPT.	OCT.	OCT. (ALTERNATE)	NOV.	DEC.
LUMBER	\$ 1267 00	\$ 1010 00	\$ 1082 00	\$ 1051 00	\$ 1173 00
MILLWORK	761 00	785 00	735 00	771 00	848 00
HARDWARE	148 00	120 00	126 00	121 00	130 00
CARPENTER LABOR	839 00	811 00	856 00	878 00	1031 00
EXCAVATING	139 00	84 00	84 00	97 00	110 00
MASONRY WORK	986 00	819 00	821 00	823 00	1620 00
PLASTERING	461 00	501 00	503 00	441 00	517 00
SHEET METAL	88 00	70 00	70 00	56 00	54 00
PAINTING	245 00	224 00	202 00	202 00	258 00
ELECTRIC WIRING & FIXTURES	188 00	158 00	158 00	161 00	203 00
PLUMBING & SEWAGE	420 00	460 00	460 00	460 00	505 00
WARM AIR HEAT	244 00	225 00	225 00	252 00	307 00
TOTAL COST	\$ 5786 00	\$ 5267 00	\$ 5322 00	\$ 5313 00	\$ 6756 00
ADD-AIR CONDITIONING	160 00	160 00	160 00	160 00	160 00
ADD-VAPOR HEAT	293 00	270 00	270 00	302 00	369 00
ADD-HOT WATER HEAT	440 00	405 00	405 00	454 00	553 00
ADD-INSULATION	213 00	179 00	174 00	179 00	174 00
CARPENTER HOURS	729 HRS.	705 HRS.	745 HRS.	763 HRS.	897 HRS.

MATERIAL LIST FOR THE JANUARY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Inside Finish Lumber			
2 Pc.	2x6-18	Main Building Wall Plates - - - - -	36	4 Pc.	1x12-10	Shelving - - - - -	40
8 Pc.	2x6-14	Main Building Wall Plates - - - - -	112	3 Pc.1-1/4x10-14	Cellar Stair Treads - - - - -		44
6 Pc.	2x6-12	Main Building Wall Plates - - - - -	72	3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
6 Pc.	2x6-10	Main Building Wall Plates - - - - -	60	1 Pc.	2x4-12	Cellar Stair Rails - - - - -	8
4 Pc.	2x10-14	Box Sills - - - - -	93	1 Pc.	1x4-8	Cellar Stair Rails - - - - -	3
Girders and Lintles				1 Pc.	4x4-7	Cellar Stair Post - - - - -	9
1 Pc.	6x8-14	Main Building - - - - -	56	3 Pc.	2x4-14	Clothes Hamper - - - - -	28
1 Pc.	6x8-7	Main Building - - - - -	28	60 Ft.	1x4	Clothes Hamper - - - - -	60
2 Pc.	2x8-12	Porch Roof Beam - - - - -	32				
4 Pc.	2x8-9	Porch Roof Beam - - - - -	48				
4 Pc.	2x8-10	Garage Entrance & Door Beams - - - - -	53				
2 Pc.	2x6-9	Poroh Ceiling Beams - - - - -	18				
Girdsr Posts							
4 Pc.	6x6-7	Main Building - - - - -	84				
Floor Joists, Headers and Trimmers							
27 Pc.	2x10-12	First Floor Main Building - - - - -	540				
28 Pc.	2x10-10	First Floor Main Building - - - - -	467				
1 Pc.	2x4-8	Hearth Floor Supports - - - - -	5				
4 Pc.	1x10-14	Fire Stops - - - - -	47				
27 Pc.	2x10-12	Second Floor Main Building - - - - -	540				
24 Pc.	2x10-10	Second Floor Main Building - - - - -	400				
4 Pc.	2x10-8	Second Floor Main Building - - - - -	53				
Ceiling Joists							
21 Pc.	2x6-20	Main Building - - - - -	420				
8 Pc.	2x6-14	Garage - - - - -	112				
5 Pc.	2x4-12	Porch - - - - -	40				
3 Pc.	2x4-9	Garage Entrance - - - - -	18				
Outside Studs							
112 Pc.	2x4-16	Main Building - - - - -	1195				
24 Pc.	2x4-8	Gables - - - - -	128				
5 Pc.	2x4-8	Porch Gables - - - - -	27				
3 Pc.	2x4-14	Garags Studs - - - - -	28				
4 Pc.	2x4-12	Garage Studs - - - - -	32				
20 Pc.	2x4-9	Garage Studs - - - - -	120				
11 Pc.	2x4-6	Garags Studs - - - - -	44				
Inside Studs							
66 Pc.	2x4-8	First Floor - - - - -	352				
6 Pc.	2x6-8	First Floor - - - - -	48				
96 Pc.	2x4-8	Second Floor - - - - -	512				
5 Pc.	2x6-8	Second Floor - - - - -	40				
2 Pc.	2x4-6	Mantel Trim Blocking - - - - -	8				
Stud and Partition Plates							
25 Pc.	2x4-14	Outside Walls - - - - -	233				
42 Pc.	2x4-12	Inside Partitions - - - - -	336				
3 Pc.	2x6-12	Inside Partitions - - - - -	36				
4 Pc.	2x4-10	Garage Plates - - - - -	27				
3 Pc.	2x4-14	Garage Plates - - - - -	28				
Rafters							
44 Pc.	2x6-14	Main Building - - - - -	616				
9 Pc.	2x6-16	Garage - - - - -	144				
9 Pc.	2x6-9	Garage - - - - -	81				
10 Pc.	1x6-6	Collar Beams - - - - -	30				
12 Pc.	2x4-8	Side Porch - - - - -	64				
1 Pc.	1x8-16	Ridge Board - - - - -	11				
1 Pc.	1x8-12	Ridge Board - - - - -	8				
1 Pc.	1x8-10	Ridge Board - - - - -	7				
1 Pc.	1x6-10	Ridge Board - - - - -	5				
4 Pc.	2x4-14	Fire Stops - - - - -	37				
2 Pc.	2x4-12	Fire Stops - - - - -	16				
2 Pc.	2x4-10	Fire Stops - - - - -	13				
3 Pc.	1x8-12	Garags Entrance Cut to Curve - - - - -	24				
3 Pc.	2x4-10	Extension Rafters Cut - - - - -	20				
Step and Stair Carriages							
2 Pc.	2x10-14	Cellar Stairs - - - - -	47				
2 Pc.	2x10-16	Main Stairs - - - - -	53				
2 Pc.	2x6-16	Stairs Platform Framing - - - - -	32				
Sheathing, Boards, Sub-flooring, Furring, Etc.,							
1100 Ft.	1x4	Roof Sheathing Laid 4-1/2" O.C. - - - - -	1100				
200 Ft.	1x6	Roof Sheathing D&M Over Rooms Only - - - - -	200				
1500 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally - - - - -	1500				
2800 Ft.	1x8	Box Sheathing O.S.Walls Shiplap - - - - -	2800				
200 Ft.	1x6	Ribbons, Backing & Furring - - - - -	200				
5 Pc.	1x2-8	Furring Inside Walls Chimney Breast - - - - -	7				
1150 Lin.Ft.	1x1	Ground (Around Inside Openings) - - - - -	96				
80 Ft.	1x4	Bridging - - - - -	80				
80 Ft.	1x2	Floor Stripping 2nd Floor Only - - - - -	80				
Siding For Outside Walls							
2550 Ft.	3/4x10"	Bev.Siding Laid 8" Exposurs - - - - -	2550				
Flooring and Ceiling							
510 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor - - - - -	510				
175 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - - - -	175				
700 Ft.	3/4x3-1/4	Flooring, Second Floor - - - - -	700				
135 Ft.	5/8x3-1/4	Ceiling Porches 9 Ft.Long - - - - -	135				
40 Ft.	5/8x3-1/4	Ceiling - Garage Entrance - - - - -	40				
Shingles							
13-1/2 Squares	16"	Shingles For Roof Certigrade Red Cedar - - - - -					
		Laid 4-1/2" Exposure - - - - -					
Lath							
50	48"	Exterior, For Furring - - - - -					
Outside Finish Lumber							
100 Ft.	1x6	Facias & Gable Frieze - - - - -	100				
40 Ft.	1x6	Garage Door Jamb & Trim - - - - -	40				
3 Pc.	1x2-10	Garage Door Stop - - - - -	5				
45 Ft.	1x10	Porch Lintle Frieze - - - - -	45				
35 Ft.	1x8	Porch Lintle Frieze - - - - -	35				
20 Ft.	1x4	Porch Lintle Soffit - - - - -	20				
10 Pc.	4x4-7	Porch Posts - - - - -	93				
1 Pc.	6x6-8	Garage & Porch Posts - - - - -	24				
1 Pc.	3x6-8	Garage Pilaster - - - - -	12				
200 Lin.Ft.	1x2	Porch Lattice - - - - -	33				
25 Ft.1x4 to 1x10		Miscellaneous O.S.Finish - - - - -	25				

MATERIAL LIST FOR THE JANUARY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			FINISH HARDWARE		
For Balance - First Floor			4		Cellar Sash Sets
1	2/8x6/8x1-3/4	Rear Door Glz.	1		Garage Sash Set
1	2/8x6/8x1-3/8	Inside Door Panelled	4-1/2 Pr.	4x4	Door Butts
1	2/0x6/8x1-3/8	Inside Door Panelled	12 Pr.	3-1/2x3-1/2	Door Butts
2 Sets	7/8x5-5/8	Door Jambs For 2/8x6/8 & Smaller Doors	2 Pr.	3x3	Casement Sash Butts
1 Set	8/0x8/0x1-3/4	Garage Doors Overhead Type, Glz. Complete with All Hardware & Equipment, See Plan	3 Pr.	2-1/2	Cupboard Door Butts, Narrow
1 Set	8x12x7/8	Chute Door, Jambs & Trim	2 Pr.	3-1/2x3-1/2	Bathroom Door Butts
			1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow
Doors and Jambs For Second Floor			1		Front Door Lock Set
4	2/6x6/6x1-3/8	Inside Door Panelled	1		Rear Door Lock Set
1	2/4x6/6x1-3/8	Inside Door Panelled	12		Inside Door Lock Sets
4	2/0x6/6x1-3/8	Inside Door Panelled	2		Bathroom Door Lock Sets
1	1/0x6/6x1-3/8	Inside Door Panelled	1 Single		French Door Lock Set
6 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 & Smaller Doors	1 Set	1-3/8"	Floor Double Acting Hinge
4 Sets	7/8x3-5/8	Door Jambs For 2/4x6/6 & Smaller Doors	2		Push Plates
1 Set	12x16x7/8	Pipe Door, Jambs & Trim	2 Sets		Casement Sash Fasteners, Single
1 Set	8x12x7/8	Chute Door, Jambs & Trim	16		Sash Locks
			32		Sash Lifts
			4		Sash Lifts, Bathroom
			2		Sash Lock, Bathroom
			3		Cupboard Turns
			1		Cupboard Turn, Med. Case
			14		Metal Base Knobs
			1		Metal Base Knob, Bathroom
			5 Doz.		Coat and Hat Hooks
			11 Sets		Window Blinds Hangers
Interior Finish: Main Rooms, First Floor			Rough Hardware		
1		Sides of Trim For 3/0x6/8 Door	4 Hanks		Sash Cord
3		Sides of Trim For 2/6x6/8 Door	30	1/2x16"	Anchor Bolts With Nuts & Washers
1		Sides of Trim For 2/0x6/8 Door	4 Sets	6"	Post Caps & Bases Including Lag Screws
1		Sides of Trim For 2/0x6/8 Closet Door	1 Pr.	5"	T.Hinges
2		Sides of Trim For 4/0x6/8 C.O.	450 Lbs.		Sash Weights
2		Sides of Trim For 3/6x6/8 C.O.			
2		Sides of Trim For 10x12 - 15 Lt.Windows			
1		Sides of Trim For 8x10 - 12 Lt.Windows			
1 Mullion		Sides of Trim For 8x12 - 12 Lt.Windows			
2		Sides of Trim For 10x12 - 6 Lt.Casement Sash-Base			
115 Lin.Ft.		Base Shoe			
130 Lin.Ft.		Picture Mould			
120 Lin.Ft.		Closet Base			
15 Lin.Ft.		Hook Strips			
10 Lin.Ft.		Thresholds			
1 Pc.	3/6	Thresholds			
1 Pc.	3/0	Thresholds			
Interior Finish: Balance of Rooms - First Floor			BUILDING PAPER		
3		Sides of Trim For 2/8x6/8 Doors	7 Rolls	50#	(500 Ft.) Building Paper
2		Sides of Trim For 2/6x6/8 Doors			
2		Sides of Trim For 2/0x6/8 Doors			
1		Sides of Trim For 20x18 - 2 Lt.Window			
1 Mullion		Sides of Trim For 20x18 - 2 Lt.Window			
4 Lin.Ft.		Window Stool Garage			
4 Lin.Ft.		Sash Stool Garage			
16 Lin.Ft.		Window Stop Garage			
55 Lin.Ft.		Base			
55 Lin.Ft.		Base Shoe			
40 Lin.Ft.		Chair Rail, Kitchen & Toilet			
1 Pc.	3/0	Thresholds			
Interior Finish: Second Floor			SHEET METAL MATERIAL		
8		Sides of Trim For 2/6x6/6 Doors	25 Lin.Ft.	14"	Valley Tin
2		Sides of Trim For 2/4x6/6 Doors	110 Pc.	10x12"	Tin Shingles
4		Sides of Trim For 2/0x6/6 Doors	100 Lin.Ft.	5"	Gutter Eaves Trough
4		Sides of Trim For 2/0x6/6 Closet Doors	2-1/2 Doz.	5"	Hangers
4		Sides of Trim For 8x12 - 12 Lt.Windows	12	5"	End Caps
3		Sides of Trim For 10x12 - 12 Lt.Windows	8	5"x3"	Drop Outlets
2		Sides of Trim For 8x10 - 12 Lt.Windows	110 Lin.Ft.	3"	Conductor Pipe
1		Sides of Trim For 1/0x6/6 Door	16	3"	Elbows
1		Sides of Trim For 1/0x6/6 Closet Door	2-1/2 Doz.	3"	Conductor Pipe, Hooks
200 Lin.Ft.		Base	8	3"	Strainers
260 Lin.Ft.		Base Shoe	18 Lin.Ft.		Chute Lining, See Plan
60 Lin.Ft.		Closet Base			
180 Lin.Ft.		Picture Mould			
28 Lin.Ft.		Chair Rail Bathroom			
50 Lin.Ft.		Hook Strips			
1 Set	24x30"	Scuttle Trim, Door & Jambs			
Main Stair			NAILS		
1		Starting Newel	80 Lbs.	20d	Common Nails
1		Quarter Circle End Tread & Riser	80 Lbs.	16d	Common Nails
10		Treads	30 Lbs.	10d	Common Nails
13		Risers	160 Lbs.	8d	Common Nails
5		Landing Treads	10 Lbs.	6d	Common Nails
8 Lin.Ft.		Rail	5 Lbs.	10d	Casing Nails
10	32"	Balusters	50 Lbs.	8d	Casing Nails
6 Lin.Ft.		Nosing	10 Lbs.	6d	Casing Nails
8 Lin.Ft.		Face Mould	5 Lbs.	10d	Finish Nails
24 Lin.Ft.		Wall String (2 mem.)	15 Lbs.	8d	Finish Nails
8 Lin.Ft.		Face String	5 Lbs.	6d	Finish Nails
1		Wall Rosette	2 Lbs.	4d	Finish Nails
2		Stair Rail Acorn Ends	1 Lb.	7/8"	Finish Brads (16 Gauge)
12 Lin.Ft.		Wall Rail	65 Lbs.	3d	Shingle Nails Hot Dipped Zinc Coated
3		Wall Rail Brackets	60 Lbs.	8d	Coated Nails For Siding
Miscellaneous			2 Lbs.	3d	Fine Lath Nails
70 Lin.Ft.		Stair Cove Moulding	2 Lbs.	20d	Cut Nails For Furring
1 Pc.	3/4x4"	Stair Part.Corner Trim			
1 Pc.	3/4x3"	Stair Part.Corner Trim			
Cabinets			PAINT		
1		Mantel Shelf & Trim See Plan	11 Gals.		Outside Body Paint
1		Medicine Cabinet	3-1/2 Gals.		Outside Trim Paint
2	2/6 x8/0	Kitchen Cabinet, 1 Pr.Panel Doors Above, 1 Pr Panel Doors & 2 Drawers Below, with Hdwe.	1 Gals.		Porch Ceiling Paint
			1 Gals.		Blind or Shutter Paint
			1 Gals.		Sheet Metal Paint (Mineral)
			1 Pint		Mineral Paint - Ornamental Iron
			5 Gals.		Inside Varnish
			6 Gals.		Floor Varnish
			1/2 Gals.		Spar Varnish
			1/2 Gals.		Shellac
			3-1/2 Gals.		Liquid Wood Filler
			3/4 Gals.		Flat White
			1-1/2 Gals.		White Enamel
			2 Gals.		Boiled Linseed Oil
			2 Gals.		Turpentine
			25 Lbs.		Putty

MATERIAL LIST FOR THE JANUARY 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Inside Finish Lumber			
2 Pc.	2x6-18	Main Building Wall Platee	36	4 Pc.	1x12-10	Shelving	40
8 Pc.	2x6-14	Main Building Wall Platee	112	3 Pc.	1-1/4x10-14	Cellar Stair Treads	44
6 Pc.	2x6-12	Main Building Wall Plates	72	3 Pc.	1x8-14	Cellar Stair Risee	28
6 Pc.	2x6-10	Main Building Wall Plates	60	1 Pc.	2x4-12	Cellar Stair Raile	8
4 Pc.	2x10-14	Main Building Wall Plates	93	1 Pc.	1x4-8	Cellar Stair Raile	3
Girders and Lintles				1 Pc.	4x4-7	Cellar Stair Posts	9
1 Pc.	6x8-14	Main Building	56	3 Pc.	2x4-14	Clothes Hamper	28
1 Pc.	6x8-7	Main Building	28	60 Ft.	1x4	Clothes Hamper	60
2 Pc.	2x10-12	Front Porch Roof Beam	40				
4 Pc.	2x10-9	Front Porch Roof Beam	60				
2 Pc.	2x10-10	Garage Entrance Beams	33				
2 Pc.	2x8-10	Garage Door Beams	27				
2 Pc.	2x6-9	Porch Ceiling Beams	18				
Girder Posts							
4 Pc.	6x6-7	Main Building	84				
Floor Joists, Headers and Trimmere							
27 Pc.	2x10-12	First Floor Main Building	540				
28 Pc.	2x10-10	First Floor Main Building	467				
1 Pc.	2x4-8	Hearth Floor Nail Header	5				
4 Pc.	1x10-14	Fire Stops	47				
27 Pc.	2x10-12	Second Floor Main Building	540				
24 Pc.	2x10-10	Second Floor Main Building	400				
4 Pc.	2x10-8	Sascond Floor Main Building	53				
Ceiling Joiste							
20 Pc.	2x6-20	Main Building	400				
20 Pc.	2x6-10	Garage & Entrance	200				
10 Pc.	2x6-10	Porch	100				
Outside Stude							
112 Pc.	2x4-16	Main Building	1195				
50 Pc.	2x4-9	Garage	300				
8 Pc.	2x4-12	Dormer Studs & Blocking	64				
4 Pc.	2x4-14	Fire Stops	37				
2 Pc.	2x4-12	Fire Stops	16				
2 Pc.	2x4-10	Fire Stops	13				
Inside Studs							
66 Pc.	2x4-8	First Floor	352				
6 Pc.	2x6-8	First Floor	48				
96 Pc.	2x4-8	Second Floor	512				
5 Pc.	2x6-8	Second Floor	40				
2 Pc.	2x4-6	Mantel Trim Blocking	8				
Stud and Partition Plates							
25 Pc.	2x4-14	Outside Walls	233				
42 Pc.	2x4-12	Inside Partitions	336				
3 Pc.	2x6-12	Inside Partitions	36				
6 Pc.	2x4-10	Garage	40				
4 Pc.	2x4-12	Garage	32				
Rafters							
48 Pc.	2x6-16	Main Building	768				
4 Pc.	1x6-8	Collar Beams	16				
1 Pc.	1x8-6	Ridge Board	4				
16 Pc.	1x8-10	Dormers (Cut to Curve)	107				
4 Pc.	2x8-20	Hip Rafters	107				
30 Pc.	1x6-10	Garage & Porch Roof Furring	150				
Step and Stair Carriagss							
2 Pc.	2x10-14	Cellar Stairs	47				
2 Pc.	2x10-16	Main Stairs	53				
2 Pc.	2x6-16	Main Stairs Platform Framing	32				
Sheathing, Boards, Sub-flooring, Furring, Etc.,							
625 Ft.	1x4	Roof Sheathing S.2.S.Laid 4-1/2" O.C.	625				
850 Ft.	1x6	Roof Sheathing D&M	850				
1500 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally	1500				
2460 Ft.	1x8	Box Sheathing O.S.Walls Shiplap	2460				
		Laid Diagonally	2460				
200 Ft.	1x6	Ribbons, Backing & Furring	200				
5 Pc.	1x2-8	Furring Inside Walls Chimney Breast	7				
1150 Lin.Ft.	1x1	Ground (Around Inside Openings)	96				
80 Ft.	1x4	Bridging	80				
20 Ft.	1x4	Lookouts	20				
80 Ft.	1x2	Floor Stripping 2nd Floor Only	80				
Siding For Outside Walls							
1850 Ft.	3/4x10"	Bev.Siding Laid 8" Exposure	1850				
400 Ft.	1x12	Siding Boards S.2.S.	400				
Flooring and Ceiling							
510 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor	510				
175 Ft.	3/4x3-1/4	Flooring, Balance First Floor	175				
700 Ft.	3/4x3-1/4	Flooring, Second Floor	700				
135 Ft.	5/8x3-1/4	Ceiling Porches 9 Ft.Long	135				
40 Ft.	5/8x3-1/4	Ceiling Garage Entrance	40				
Shinglee							
10 Squares 16"		Shingles For Roof Certigrade Red Cedar 4-1/2" Expoeure					
Outside Finish Lumber							
60 Ft.	1x6	Facias Main & Garage	60				
64 Ft.	1x8	Facias Porch & Garage	64				
58 Ft.	1x8	Plancier - Porch & Garage	58				
75 Ft.	1x8	Plancier - Main	75				
30 Ft.	1x3	Frieze Main	30				
30 Ft.	1x6	Garage Door Jamb & Trim	30				
3 Pc.	1x2-10	Garage Door Stops	5				
1 Pc.	1x8-10	Shiplap Garage Entrance Frieze	7				
1 Pc.	1x10-10	Shiplap Garage Entrance Frieze	8				
40 Ft.	1x10	Porch Lintle Frieze	40				
30 Ft.	1x6	Porch Lintle Frieze	30				
35 Ft.	1x4	Porch Lintle Soffit & Frieze	35				
150 Lin.Ft.	1x2	Porch Lattice	25				
25 Ft.	1x4 to 1x8	Miscellaneous O.S.Finish	25				

MATERIAL LIST FOR THE JANUARY 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)					
Blinds					FINISH HARDWARE
2 Pr.		For 10x12 - 12 Lt.Window With Panel Extension	4		Cellar Sash Sets
		Center Cut Out - See Plan	1		Garage Sash Sets
2 Pr.		For 8x10 - 12 Lt. Windows	4-1/2 Pr. 4x4		Door Butts
Doors and Jambs For Main Rooms First Floor			12 Pr. 3-1/2x3-1/2		Door Butts
1 3/0x6/8x1-3/4		Front Door Glz. See Plan	2 Pr. 3x3		Casement Sash Butts
1 2/6x6/8x1-3/4		Sides Door Glz. French	3 Pr. 2-1/2		Cupboard Door Butts, Narrow
2 2/6x6/8x1-3/8		Inside Doors Panelled	2 Pr. 3-1/2x3-1/2		Bathroom Door Butts
1 2/0x6/8x1-3/8		Inside Doors Panelled	1 Pr. 2-1/2		Medicine Cabinet Butts, Narrow
3 Sets 7/8x5-5/8		Door Jambs For 2/6x6/8 & Smaller Doors	1		Front Door Lock Set
1 Set 7/8x5-5/8		C.O.Jambs For 4/0x6/8 Opg.	12		Rear Door Lock Set
1 Set 7/8x5-5/8		C.O.Jambs For 3/6x6/8 Opg.	2		Inside Door Lock Sets
For Balance - First Floor			1 Single		Bathroom Door Lock Sets
1 2/8x6/8x1-3/4		Rear Door Glz.	1 Set 1-3/8"		French Door Lock Set
1 2/8x6/8x1-3/8		Inside Door Panelled	2		Door Double Acting Hinge
1 2/0x6/8x1-3/8		Inside Door Panelled	2 Sets		Push Plates
2 Sets 7/8x5-5/8		Door Jambs For 2/8x6/8 & Smaller Doors	15		Casement Sash Fasteners, Single
1 8/0x8/0x1-3/4		Garage Doors Overhead Type, Glz.Complete with Hardware & Equipment, See Plan	30		Sash Locks
1 Set 8x12x7/8		Chute Door, Jambs & Trim	4		Sash Lifts
Doors and Jambs for Second Floor			2		Sash Lifts, Bathroom
4 2/6x6/6x1-3/8		Inside Door Panelled	2		Sash Locks, Bathroom
1 2/4x6/6x1-3/8		Inside Door Panelled	3		Cupboard Turns
1 2/0x6/6x1-3/8		Inside Door Panelled	1		Cupboard Turn, Med.Case
1 1/0x6/6x1-3/8		Inside Door Panelled	14		Metal Base Knobs
6 Sets 7/8x5-5/8		Door Jambs For 2/6x6/6 & Smaller Doors	1		Metal Base Knob, Bathroom
4 Sets 7/8x3-5/8		Door Jambs For 2/4x6/6 & Smaller Doors	5 Doz.		Coat and Hat Hooks
1 Set 12x16x7/8		Pipe Door, Jambs & Trim	4 Sets		Window Blind Hangers
1 Set 8x12x7/8		Chute Door, Jambs & Trim			
Interior Finish: Main Rooms, First Floor			Rough Hardware		
1		Sides of Trim For 3/0x6/8 Door	4 Hanks		Sash Cord
3		Sides of Trim For 2/6x6/8 Door	30	1/2x16"	Anchor Bolts with Nuts & Washers
1		Sides of Trim For 2/0x6/8 Door	4 Sets	6"	Post Caps & Sockets, Including Lag Screws
1		Sides of Trim For 2/0x6/8 Closet Door	1 Pr.	5"	T.Hinges
2		Sides of Trim For 4/0x6/3 C.O.	425 Lbs.		Sash Weights
2		Sides of Trim For 3/6x6/8 C.O.			
2		Sides of Trim For 10x12 - 12 Lt.Windows			BUILDING PAPER
1		Sides of Trim For 8x10 - 12 Lt.Windows	7 Rolls 50#		500 Ft.Building Paper
1		Sides of Trim For 8x12 - 12 Lt.Windows			
2		Sides of Trim For 10x12 - 6 Lt.Casement Sash-Base			SHEET METAL MATERIAL
115 Lin.Ft.		Base Shoe	480 Sq.Ft.		Metal Roofing with Nails
130 Lin.Ft.		Picture Mould	25 Ft. 14"		Valley Tin
120 Lin.Ft.		Closet Base	25	5x7"	Tin Shingles
15 Lin.Ft.		Hook Strips	80 Lin.Ft. 5"		Gutter Eaves Trough
10 Lin.Ft.		Thresholds	100 Lin.Ft.		Gutter Crown Mould
1 Pc. 3/6		Thresholds	2-1/2 Doz.		Hangers For Crown Mould Gutter
1 Pc. 3/0		Thresholds	2 Doz. 5"		Hangers For Eaves Trough Gutter
Interior Finish: Balance of Rooms, First Floor			4	5"	O.S.Mitres For Eaves Trough Gutter
3		Sides of Trim For 2/8x6/8 Doors	5		O.S.Mitres For Crown Mould Gutter
2		Sides of Trim For 2/6x6/8 Doors	4		End Caps For Crown Mould Gutter
2		Sides of Trim For 2/0x6/8 Doors	14	5"	End Caps For Eaves Trough Gutter
1		Sides of Trim For 20x18 - 2 Lt.Windows	7	5x3"	Drop Outlets For Eaves Trough Gutter
1		Sides of Trim For 20x18 - 2 Lt.Mull Windows	120 Lin.Ft. 3"		Conductor Pipe
4 Lin.Ft.		Window Stool Garage	22	3"	Elbows
4 Lin.Ft.		Sash Stool Garage	3 Doz. 3"		Conductor Pipe, Hooks
16 Lin.Ft.		Window Stop Garage	11	3"	Strainers
55 Lin.Ft.		Base	4		Drop Outlets For Crown Mould Gutter
55 Lin.Ft.		Base Shoe	2		Conductor Heads, See Plan
40 Lin.Ft.		Chair Rail, Kitchen & Toilet	18 Lin.Ft.		Chute Lining See Plan
1 Pc. 3/0		Thresholds			
Interior Finish: Second Floor					NAILS
8		Sides of Trim For 2/6x6/6 Doors	90 Lbs. 20d		Common Nails
2		Sides of Trim For 2/4x6/6 Doors	90 Lbs. 16d		Common Nails
4		Sides of Trim For 2/0x6/6 Doors	35 Lbs. 10d		Common Nails
4		Sides of Trim For 2/0x6/6 Closet Doors	180 Lbs. 8d		Common Nails
2		Sides of Trim For 10x12 - 12 Lt.Windows	10 Lbs. 6d		Common Nails
4		Sides of Trim For 8x12 - 12 Lt.Windows	10 Lbs. 10d		Casing Nails
2		Sides of Trim For 1/0x6/6 Door	50 Lbs. 8d		Casing Nails
1		Sides of Trim For 1/0x6/6 Closet Door	10 Lbs. 6d		Casing Nails
200 Lin.Ft.		Base	5 Lbs. 10d		Finish Nails
260 Lin.Ft.		Base Shoe	15 Lbs. 8d		Finish Nails
60 Lin.Ft.		Closet Base	5 Lbs. 6d		Finish Nails
180 Lin.Ft.		Picture Mould	2 Lbs. 4d		Finish Nails
28 Lin.Ft.		Chair Rail Bathroom	1 Lb. 7/8"		Finish Brads (16 Gauge)
50 Lin.Ft.		Hook Strips	50 Lbs. 3d		Shingle Nails Hot Dipped Zinc Coated
1 Set 24x30		Scuttle Trim, Door & Jamb	60 Lbs. 8d		Coated Nails For Siding
Main Stair			2 Lbs. 20d		Cut Nails For Furring
1		Starting Newel			PAINT
1		Quarter Circle End Tread & Riser	10-1/2 Gals.		Outside Body Paint
10		Treads	3 Gals.		Outside Trim Paint
13		Risers	1 Gals.		Porch Ceiling Paint
5		Landing Treads	1/2 Gals.		Blind or Shutter Paint
8 Lin.Ft.		Rail	2 Gals.		Sheet Metal Paint (Mineral)
10 32"		Balusters	1 Pint		Mineral Paint - Ornamental Iron
6 Lin.Ft.		Nosing	5 Gals.		Inside Varnish
5 Lin.Ft.		Face Mould	6 Gals.		Floor Varnish
24 Lin.Ft.		Wall String (2 Mem.)	1/2 Gals.		Spar Varnish
5 Lin.Ft.		Face String	1/2 Gals.		Shellac
1		Wall Rosette	3-1/2 Gals.		Liquid Wood Filler
2		Stair Rails, Acorn Ends	3/4 Gals.		Flat White
12 Lin.Ft.		Wall Rail	1-1/2 Gals.		White Enamel
3		Wall Rail Brackets	2 Gals.		Boiled Linseed Oil
Miscellaneous			2 Gals.		Turpentine
70 Lin.Ft.		Stair Cove Moulding	25 Lbs.		Putty
1 Pc. 3/4x4"	5	Stair Part.Corner Trim			
1 Pc. 3/4x3"	5	Stair Part.Corner Trim			
Cabinets					
1		Mantle Shelf & Trim, See Plan			
1		Medicine Cabinet			
2 2/8x8/0		Kitchen Cabinet 1 Pr.Panel Doors Above, 1 Pr. Panel Doors & 2 Drawers Below - With Hdwe., (See Plan)			

MATERIAL LIST FOR THE FEBRUARY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
2 Pc.	2x6-20	Garage - - - - -	40	74 Ft.	1x10	Faciae Main - - - - -	74
4 Pc.	2x6-14	Main Building - - - - -	56	30 Ft.	1x8	Plancier Main - - - - -	30
10 Pc.	2x6-12	Main Building & Garage - - - - -	120	56 Ft.	1x12	Frieze - - - - -	56
4 Pc.	2x6-10	Main Building - - - - -	40	106 Ft.	1-1/4x6"	Frieze Gable - - - - -	106
Girders and Lintles				20 Ft.	1x6	Porch Facia - - - - -	20
1 Pc.	6x8-10	Main Building - - - - -	40	80 Ft.	1x12"	Porch Lintle Frieze - - - - -	80
1 Pc.	6x8-8	Main Building - - - - -	32	1 Pc.	1x8-20	Porch Plancier - - - - -	13
4 Pc.	2x10-18	Front Porch Roof Beam - - - - -	120	15 Ft.	1x4	Porch Lintle Soffit - - - - -	15
Girder Poste				25 Ft.	1x4 to 1x10	Miscellaneous O.S.Finish - - - - -	25
4 Pc.	6x6-7	Main Building - - - - -	84	Inside Finish Lumber			
1 Pc.	4x4-7	Stair Post - - - - -	9	5 Pc.	1x12-10	Shelving - - - - -	50
Floor Joists, Headers and Trimmers				3 Pc.	1-1/4x10-14	Cellar Stair Treads - - - - -	44
30 Pc.	2x10-10	First Floor Main Building - - - - -	500	3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
35 Pc.	2x10-12	First Floor Main Building - - - - -	700	1 Pc.	2x4-12	Cellar Stair Rails & Newel - - - - -	8
2 Pc.	2x10-14	Fire Place Headers - - - - -	47	1 Pc.	1x4-8	Cellar Stair Rails - - - - -	3
2 Pc.	2x10-14	Box Sills - - - - -	47	3 Pc.	2x4-14	Clothes Hamper - - - - -	28
2 Pc.	2x10-12	Box Sills - - - - -	40	60 Ft.	1x4	Clothes Hamper - - - - -	60
1 Pc.	2x4-12	Hearth Floor Supports - - - - -	8	INSULATION			
23 Pc.	2x10-22	Second Floor Main Building - - - - -	843	2700 Sq.Ft.		Insulating Material - - - - -	
6 Pc.	2x10-12	Second Floor Main Building - - - - -	120	MASONRY MATERIAL			
16 Pc.	2x10-10	Second Floor Over Garage - - - - -	267	Concrete Foundation 1-3-5 Mixture - 830 Cu.Ft.			
2 Pc.	1x10-14	Second Floor Fire Stops - - - - -	23	25 Cu.Yds.		Crushed Stone or Gravel - - - - -	
2 Pc.	1x10-12	Second Floor Fire Stops - - - - -	20	15 Cu.Yds.		Coarse Sand - - - - -	
Ceiling Joists				35 Bbls.		Portland Cement - - - - -	
22 Pc.	2x6-14	Main Building - - - - -	308	Stone Work			
10 Pc.	2x6-12	Main Building - - - - -	120	240 Sq.Ft.	4"	Flagstone - - - - -	
4 Pc.	2x6-10	Main Building - - - - -	40	Cement Floor and Steps 4" One Course 872 Sq.Ft.			
15 Pc.	2x4-10	Front Porch - - - - -	100	8-3/4 Cu.Yds.		Crushed Stone or Gravel - - - - -	
2 Pc.	2x10-10	Garage Door Beams - - - - -	33	5-3/4 Cu.Yds.		Coarse Sand - - - - -	
Outside Studs				14 Bbls.		Portland Cement - - - - -	
6 Pc.	2x4-18	Main Building - - - - -	72	Chimneys and Fireplace			
20 Pc.	2x4-16	Main Building - - - - -	213	5000		Common Brick - - - - -	
86 Pc.	2x4-8	Main Building - - - - -	459	135		Face Brick For Fireplace - - - - -	
20 Pc.	2x4-14	Gables - - - - -	187	120		Fire Clay Brick - - - - -	
17 Pc.	2x4-12	Gables - - - - -	136	5 Cu.Yds.		Sand - - - - -	
36 Pc.	2x4-9	Garage - - - - -	216	5 Bbls.		Lime - - - - -	
12 Pc.	2x4-14	Dormers (Cut) - - - - -	112	1 Bbl.		Portland Cement - - - - -	
4 Pc.	2x6-8	Window Lintles - - - - -	32	50 Lbs.		Fire Clay - - - - -	
Inside Studs				52 Lin.Ft.	8x12"	Flue Lining - - - - -	
43 Pc.	2x4-8	First Floor - - - - -	229	12 Sq.Ft.	1/2"	Wire Mesh For Hearth Reinforcing - - - - -	
12 Pc.	2x6-8	First Floor - - - - -	96	1		Damper - - - - -	
1 Pc.	2x6-14	First Floor C.O.Lintles - - - - -	14	1		Ash Dump - - - - -	
83 Pc.	2x4-8	Second Floor - - - - -	443	1		Cleanout Door - - - - -	
3 Pc.	2x6-8	Second Floor - - - - -	24	1	4x4x1/4"	Angle Iron 3'8" Long - - - - -	
18 Pc.	2x4-10	Second Floor (Cut) - - - - -	120	Plastering			
Stud and Partition Plates				535 Yds.		Plaster, Including Plaster Base, Nails, Metal Lath Corner Strips, and Metal Corner Beads - - - - -	
38 Pc.	2x4-14	Outsids Walls - - - - -	355	72 Yds.		Cement Plaster, Including Metal Lath & Staples For Garage & Over Boiler Space - - - - -	
43 Pc.	2x4-12	Inside Partitions - - - - -	344	ORNAMENTAL IRON			
3 Pc.	2x6-12	Inside Partitions - - - - -	36	2	3'9"	W.I. Including Fittings, For Stoop, See Plan - - - - -	
1 Pc.	2x6-10	Inside Partitions - - - - -	10	MILLWORK			
Rafters				Outside Millwork and Mouldings			
61 Pc.	2x6-14	Main Building & Garage - - - - -	854	400 Lin.Ft.		Bed Moulding - - - - -	
30 Pc.	2x6-8	Main Building - - - - -	240	70 Lin.Ft.		Cove Moulding - - - - -	
17 Pc.	2x6-6	Garage - - - - -	102	20 Lin.Ft.		1/4 Round Moulding - - - - -	
15 Pc.	2x6-12	Front Porch - - - - -	180	4	6x6 7/6	Porch Columns See Plan - - - - -	
6 Pc.	2x4-6	Dormers Front (Cut) - - - - -	24	2	3x6 7/6	Pilasters See Plan - - - - -	
2 Pc.	2x6-8	Valley Rafters - - - - -	16	Outside Door Frames			
2 Pc.	1x8-14	Ridge Boards - - - - -	19	1	2/8x6/8x1-3/4	Grade Door Frame D.C. - - - - -	
1 Pc.	1x8-10	Ridge Boards - - - - -	7	1	3/0x6/8x1-3/4	Front Door Frame No Headcasing - - - - -	
Step and Stair Carriages				2	2/8x6/8x1-3/4	Side Door Frames D.C. - - - - -	
2 Pc.	2x10-14	Cellar Stairs - - - - -	47	1	8/0x7/6	O.S.Door Frame For Overhead Garage Door No Headcasing - - - - -	
2 Pc.	2x10-16	Main Stairs - - - - -	53	Window and Sash Frames			
2 Pc.	2x6-12	Stairs Platform - - - - -	24	4	10x12x1-1/8	3 Lt.Cellar Sash Frames Plank - - - - -	
1 Pc.	2x6-8	Stairs Platform - - - - -	8	2	9x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P No Headcasing - - - - -	
Sheathing, Boards, Sub-flooring, Furring, Etc.,				4	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
1060 Ft.	1x4	Roof Sheathing Laid 4-1/2" O.C. - - - - -	1060	6	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
486 Ft.	1x6	Roof Sheathing D&M Over Rooms Only - - - - -	486	1	8x10x1-3/8	16 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
1600 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally - - - - -	1600	1	Mull 9x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
2140 Ft.	1x8	Box Sheathing O.S.Walls Shiplap Laid Diagonally - - - - -	2140	1	Mull 20x16x1-3/8	2 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
200 Ft.	1x6	Ribbons, Backing & Furring - - - - -	200	Windows and Sash			
8 Pc.	1x2-8	Furring Inside Walls Chimney Breast - - - - -	11	4	10x12x1-1/8	3 Lt.Cellar Sash Glz. - - - - -	
1300 Lin.Ft.	1x1	Ground (Around Inside Openings) - - - - -	108	4	9x12x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
70 Ft.	1x4	Bridging - - - - -	70	10	8x10x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
20 Ft.	1x4	Lookouts - - - - -	20	1	8x10x1-3/8	16 Lt.Ck.Rail Window Glz. - - - - -	
80 Ft.	1x2	Floor Stripping 2nd Floor Only - - - - -	80	2	20x16x1-3/8	2 Lt.Ck.Rail Window Glz. Div. 6 Lt. - - - - -	
Siding For Outside Walls							
2030 Ft.	3/4x10"	Dev.Siding 1" Lap - - - - -	2030				
Flooring and Ceiling							
350 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor - - - - -	350				
320 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - - - -	320				
760 Ft.	3/4x3-1/4	Flooring, Second Floor - - - - -	760				
200 Ft.	5/8x3-1/4	Ceiling Porches - - - - -	200				
Shingles							
14 Squares 16"		Shingles For Roof Certigrade Red Cedar 4-1/2" Exposure - - - - -					
Lath							
50	48"	Exterior Lath For Frieze Furring - - - - -					

MATERIAL LIST FOR THE FEBRUARY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			MILLWORK (CONTINUED)		
Blinds			Miscellaneous		
1 Pr.		Blinds For 3/0x7/0 Door - - - - -	70 Lin.Ft.		Stair Cove Moulding - - - - -
1 Pr.		Blinds For 8x10 - 16 Lt.Window - - - - -			
2 Pr.		Blinds For 9x12 - 12 Lt.Window - - - - -			
4 Pr.		Blinds For 8x10 - 12 Lt.Window - - - - -			
Doors and Jambs For Main Rooms First Floor			Cabinets		
1	3/0x7/0x1-3/4	Front Door Glz. - - - - -	1		Mantel Shelf & Trim, See Plan - - - - -
1	2/8x6/8x1-3/4	Side Door Glz. French - - - - -	1		Medicine Cabinet - - - - -
1	2/8x6/8x1-3/8	Inside Door Glz. French - - - - -	2	3/0x8/0	Kitchen Cabinets, 1 Pr. Panelled Doors Above & 1 Pr. Panelled Doors Below, Including 2
1	2/6x6/8x1-3/8	Inside Door Panelled - - - - -			drswers, Complete with Hardware, See Plan - -
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -			
2 Sets	7/8x5-5/8	Door Jambs For 2/8x6/8 Doors or Smaller - - - - -			
1 Set	7/8x3-5/8	Door Jambs For 2/0x6/8 Doors - - - - -			
1 Set	7/8x7-5/8	Door Jambs For 5/0x6/8 C.O. - - - - -			
For Balance - First Floor			FINISH HARDWARE		
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	4		Cellar Sash Sets - - - - -
1	2/8x6/8x1-3/4	Side Door Glz. French - - - - -	5-1/2 Pr.	4x4	Door Butts - - - - -
1	2/8x6/8x1-3/8	Inside Door Panelled - - - - -	12 Pr.	3-1/2x3-1/2	Door Butts - - - - -
1	2/6x6/8x1-3/8	Garage Door, Panelled & 1 Side Metal Clad - - - - -	3 Pr.	2-1/2	Cupboard Door Butts, Narrow - - - - -
1	10x6/8x1-3/8	Flush Door - - - - -	1 Pr.	3-1/2x3-1/2	Bathroom Door Butts - - - - -
3 Sets	7/8x5-5/8	Door Jambs For 2/8x6/8 Doors or Smaller - - - - -	1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow - - - - -
1 Set	7/8x3-5/8	Door Jambs For 2/8x6/8 C.O. - - - - -			Front Door Lock Set - - - - -
1 Set	8/0x7/6x1-3/4	Garage Doors, Overhead Type, Complete with Hardware, See Plan - - - - -			Rear Door Lock Set - - - - -
1 Set	8x16x7/8	Chute Door, Jamb & Trim - - - - -			Inside Door Lock Sets - - - - -
Doors and Jambs For Second Floor					Bathroom Door Lock Set - - - - -
1	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	3 Single		French Door Lock Set - - - - -
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	16		Sash Locks - - - - -
4	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	32		Sash Lifts - - - - -
6 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 Doors or Smaller - - - - -	2		Sash Lifts, Bathroom - - - - -
2 Sets	7/8x3-5/8	Door Jambs For 2/0x6/6 Doors - - - - -	1		Sash Lock, Bathroom - - - - -
1 Set	16x20x7/8	Pipe Door, Jambs & Trim - - - - -	3		Cupboard Turns - - - - -
1 Set	12x16x7/8	Chute Door, Jambs & Trim - - - - -	1		Cupboard Turn, Med. Case - - - - -
Interior Finish: Main Rooms, First Floor					Metal Base Knobs - - - - -
1		Sides of Trim For 3/0x6/8 Door - - - - -	15		Metal Base Knob, Bathroom - - - - -
2		Sides of Trim For 2/8x6/8 Door - - - - -	1		Coat and Hat Hooks - - - - -
1		Sides of Trim For 2/6x6/8 Door - - - - -	4 Doz.		Window Blinds Hangers - - - - -
1		Sides of Trim For 2/0x6/8 Door - - - - -	8 Sets		
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -			
2		Sides of Trim For 5/0x6/8 C.O. - - - - -			
76 Lin.Ft.		Sides of Trim For 9x12 - 12 Lt.Window - - - - -			
86 Lin.Ft.		Base - - - - -			
105 Lin.Ft.		Base Shoe - - - - -			
10 Lin.Ft.		Picture Mould - - - - -			
10 Lin.Ft.		Closet Base - - - - -			
1 Pc.	3/6	Hook Strips - - - - -			
1 Pc.	3/0	Thresholds - - - - -			
		Thresholds - - - - -			
Interior Finish: Balance of Rooms, First Floor					
5		Sides of Trim For 2/8x6/8 Door - - - - -			
2		Sides of Trim For 2/6x6/8 Door - - - - -			
1		Sides of Trim For 10"x6/8 Door - - - - -			
2		Sides of Trim For 2/8x6/8 C.O. - - - - -			
1		Sides of Trim For 10"x6/8 Closet Door - - - - -			
1		Sides of Trim For 2/6x6/8 Garage Door - - - - -			
2		Sides of Trim For 8x10 - 12 Lt.Garage Windows - - - - -			
1 Mull.		Sides of Trim For 9x12 - 12 Lt.Window - - - - -			
1 Mull.		Sides of Trim For 20x16 - 2 Lt.Window - - - - -			
80 Lin.Ft.		Base - - - - -			
80 Lin.Ft.		Base Shoe - - - - -			
46 Lin.Ft.		Picture Mould - - - - -			
70 Lin.Ft.		Chair Rail - - - - -			
2 Pc.	3/0	Thresholds - - - - -			
6 Lin.Ft.		Closet Base - - - - -			
Interior Finish: Second Floor					</

MATERIAL LIST FOR THE MARCH 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
14 Pc.	2x6-12	Main Building Wall Plates	168	140 Ft.	1x6	Plancier, Facia & Frieze	140
6 Pc.	2x6-10	Main Building Wall Plates	60	60 Ft.	1x10	Frieze	60
2 Pc.	2x6-14	Main Building Wall Plates	28	110 Lin.Ft.	1x2	Porch Trellis	18
2 Pc.	2x6-16	Main Building Wall Plates	32	1 Pc.	2x4-8	Trellis Frame	5
1 Pc.	2x10-16	Main Building Box Sills	27	2 Pc.	4x4-8	Porch Posts	21
1 Pc.	2x10-14	Main Building Box Sills	23	2 Pc.	2x4-8	Porch Pilasters	11
3 Pc.	2x10-12	Main Building Box Sills	60	20 Ft.1x4 to 1x10		Miscellaneous O.S.Finish	20
1 Pc.	2x10-10	Main Building Box Sills	17	Inside Finish Lumber			
Girders and Lintles				4 Pc.	1x12-10	Shelving	40
1 Pc.	6x8-16	Main Building	64	3 Pc.1-1/4x10-14		Cellar Stair Treads	44
1 Pc.	6x8-10	Main Building	40	3 Pc.	1x8-14	Cellar Stair Risers	28
1 Pc.	6x8-8	Main Building	32	2 Pc.	2x4-12	Cellar Stair Rails & Newels	16
Girder Posts				1 Pc.	1x4-10	Cellar Stair Rails	3
3 Pc.	6x6-7	Main Building	63	1 Pc.	1x6-10	D&M Access Door Panel	5
2 Pc.	4x4-7	Stair Landing Posts	19	1 Pc.	1x3-4	Access Door Cleat	1
Floor Joists, Headers and Trimmers				INSULATION			
5 Pc.	2x10-16	First Floor Main Building	133	1625 Sq.Ft.		Insulating Material	
32 Pc.	2x10-12	First Floor Main Building	640	MASONRY MATERIAL			
34 Pc.	2x10-10	First Floor Main Building	567	Concrete Foundation 1-3-5 Mixture - 930 Cu.Ft.			
6 Pc.	2x10-8	First Floor Main Building	80	28 Cu.Yds.		Crushed Stone or Gravel	
1 Pc.	2x4-12	Hearth Floor Supports	8	17 Cu.Yds.		Coarse Sand	
3 Pc.	2x8-12	Bay Ceiling Beams	48	40-1/4 Bbls.		Portland Cement	
Ceiling Joists				Stone Work			
12 Pc.	2x6-18	Main Building	216	36 Sq.Ft. 4"		Flagstone	
7 Pc.	2x6-16	Main Building	112	Concrete Blocks			
14 Pc.	2x6-12	Main Building	168	3	12x12x8"	Cement Pier Blocks	
15 Pc.	2x6-10	Main Building	150	Cement Floor and Steps - 454 Sq.Ft.			
3 Pc.	2x6-14	Main Building	42	1/4-1/2 Cu.Yds.		Crushed Stone or Gravel	
Outside Studs				2-3/4 Cu.Yds.		Coarse Sand	
116 Pc.	2x4-8	Main Building	619	7 Bbls.		Portland Cement	
18 Pc.	2x4-6	Main Building	72	Chimneys and Fireplace			
33 Pc.	2x4-8	Gables	176	3800		Common Brick	
8 Pc.	2x4-6	Bay Studs	32	60		Face Brick For Fireplace	
9 Pc.	1x4-10	Corner Bracing	30	120		Fire Clay Brick	
Inside Studs				4 Cu.Yds.		Sand	
105 Pc.	2x4-8	First Floor	560	4 Bbls.		Lime	
8 Pc.	2x6-8	First Floor	64	1 Bbl.		Portland Cement	
Stud and Partition Plates				50 Lbs.		Fire Clay	
28 Pc.	2x4-14	Outside Walls	261	44 Lin.Ft. 8x12"		Flue Lining	
28 Pc.	2x4-12	Inside Partitions	224	12 Sq.Ft. 1/2"		Wire Mesh For Hearth Reinforcing	
3 Pc.	2x6-8	Insids Partitions	24	1		Damper	
2 Pc.	2x6-12	Bay Plates	24	1		Ash Dump	
Rafters				1		Cleanout Door	
13 Pc.	2x6-18	Main Building	234	1	4x4x1/4"	Angle Iron 3/8 Long	
36 Pc.	2x6-16	Main Building	576	Plastering			
13 Pc.	2x6-14	Main Building	182	350 Yds.		Plaster, Including Plaster Base, Nails, Metal	
15 Pc.	1x6-8	Collar Beams	60	12 Yds.		Lath Corner Strips, and Metal Corner Beads	
6 Pc.	2x4-9	Bays Cut	36			Cement Plaster, Including Metal Lath &	
6 Pc.	1x8-10	Bays Cut to Curve	40			Staples For Over Boiler Space	
4 Pc.	2x4-8	Dormers	21	MILLWORK			
1 Pc.	2x6-10	Valley Rafters Dormer	10	Outside Millwork and Mouldings			
1 Pc.	1x8-16	Ridge Boards	11	16 Lin.Ft.		Crown Moulding	
2 Pc.	1x8-10	Ridge Boards	13	250 Lin.Ft.		Bed Moulding	
1 Pc.	1x6-6	Ridge Boards	3	20 Lin.Ft.		Cove Moulding	
1 Pc.	2x6-8	Access Door Jamb	8	20 Lin.Ft.		1/4 Round Moulding	
Step and Stair Carriages				1		Circular Porch Roof, Complete See Plan	
2 Pc.	2x10-14	Cellar Stairs	47	1		Flower Box, See Plan	
1 Pc.	2x6-16	Stairs Platform	16	2		Flower Box Brackets, See Plan	
Sheathing, Boards, Sub-flooring, Furring, Etc.,				Outside Door Frames			
1100 Ft.	1x4	Roof Sheathing Laid 4-1/2" O.C.	1100	1	3/0x6/8x1-3/4	Front Door Frame With 3/0x10" O.S.Circular	
175 Ft.	1x6	Roof Sheathing D&M Over Bay	175			Head Transom - See Plan	
1030 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally	1030	1	2/8x6/8x1-3/4	Rear Door Frame D.C.	
1400 Ft.	1x8	Box Sheathing O.S.Walls Shiplap	1400	Window and Sash Frames			
125 Ft.	1x6	Backing & Furring	125	3	10x16x1-1/8	3 Lt.Cellar Sash Frames Plank	
8 Pc.	1x2-9	Furring Inside Walls (Chimney Breast)	12	2	8x12x1-3/8	16 Lt.Ck.Rail Window Frames P&P No Headcasing	
800 Lin.Ft. 1x1		Ground (Around Inside Openings)	67	2	8x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P No Headcasing	
50 Ft.	1x4	Bridging	50	1	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P No Headcasing	
20 Ft.	1x4	Lookouts	20	1	Mull 24x16x1-3/8	2 Lt.Ck.Rail Window Frames P&P No Headcasing	
Siding For Outside Walls				2	8x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C.	
1250 Ft.	3/4x12"	Bev.Siding	1250	1	Triple	Bay Window Frame, Center Window 10x12 - 12 Lt.	
44 Ft.	1x6	V.Siding	44		(See Plan)	Ck.Rail, Bays 22x24"x1-3/8" 2 Lt.P&P	
1 Pc.	1x8-18	Shiplap Siding	12	2	3/0x1/6x1-3/8	O.S.Half Circle Head Sash Frame See Plan	
Flooring and Ceiling				Windows and Sash			
350 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor	350	3	10x16x1-1/8	3 Lt.Cellar Sash Glz.	
575 Ft.	3/4x3-1/4	Flooring, Balance First Floor	575	2	8x12x1-3/8	16 Lt.Ck.Rail Window Glz.	
40 Ft.	5/8x3-1/4	Ceiling Porches	40	1	10x12x1-3/8	12 Lt.Ck.Rail Window Glz.	
Shingles				4	8x12x1-3/8	12 Lt.Ck.Rail Window Glz.	
13 Squares 16"		Shingles For Roof Certigrade Red Cedar		1	8x10x1-3/8	12 Lt.Ck.Rail Window Glz.	
		4-1/2" Exp.		2	22x24x1-3/8	2 Lt.Ck.Rail Window Glz. Div. 12 Lts.	
Lath				2	24x16x1-3/8	2 Lt.Ck.Rail Window Glz. Div. 6 Lt.Each	
50	48"	Exterior Lath For Frieze Furring		2	3/0x1/6x1-3/8	Half Circle Sash Glz. Div. 6 Lts.	
				1	3/0x10"x1-3/8	Circle Head Transom Glz. Div. 4 Lts.	
Blinds				Blinds			
2 Pr.				2 Pr.		Blinds For 8x12 - 16 Lt.Windows	
3 Pr.				3 Pr.		Blinds For 8x12 - 12 Lt.Windows	

MATERIAL LIST FOR THE MARCH 1938 CITY CALENDAR

Quantity Size			ARTICLE AND DESCRIPTION			Quantity Size			ARTICLE AND DESCRIPTION		
MILLWORK (CONTINUED)						HARDWARE (CONTINUED)					
Doors and Jambs For Main Rooms First Floor											
1	3/0x6/8x1-3/4	Front Door Glz. See Plan	-	-	-	11		Sash Locks	-	-	-
1	2/6x6/8x1-3/8	Inside Door Panelled	-	-	-	22		Sash Lifts	-	-	-
1	2/0x6/8x1-3/8	Inside Door Panelled	-	-	-	2		Sash Lifts, Bathroom	-	-	-
2 Sets	7/8x5-5/8	Door Jambs For 2/6x6/8 Doors or Smaller	-	-	-	1		Sash Lock, Bathroom	-	-	-
1 Set	7/8x5-5/8	Door Jambs For 2/8x6/8 C.O.	-	-	-	1		Cupboard Turn	-	-	-
						10		Cupboard Turn, Med. Case	-	-	-
						1		Metal Base Knobs	-	-	-
						1		Metal Base Knobs, Bathroom	-	-	-
						4 Doz.		Coat and Hat Hooks	-	-	-
						1 Pr.		Transom Butts	-	-	-
						1		Transom Lift	-	-	-
						5 Sets		Window Blind Hangers	-	-	-
For Balance - First Floor											
1	2/8x6/8x1-3/4	Rear Door Glz.	-	-	-	Rough Hardware					
1	2/8x6/8x1-3/8	Inside Door Panelled	-	-	-	3		Hanks	-	-	-
2	2/6x6/8x1-3/8	Inside Door Panelled	-	-	-	26	1/2x16"	Sash Cord	-	-	-
3	2/0x6/8x1-3/8	Inside Door Panelled	-	-	-	3	6"	Anchor Bolts With Nuts & Washers	-	-	-
1	1/10x6/8x1-3/8	Inside Door Panelled	-	-	-	300	Lbs.	C.I. Post Cape & Sockete with Lag Screws	-	-	-
1	1/0x6/8x1-3/8	Inside Door Panelled	-	-	-						
7 Sets	7/8x5-5/8	Door Jambs For 2/8x6/8 Doors or Smaller	-	-	-						
1 Set	7/8x3-5/8	Door Jambs For 1/0x6/8 Doors	-	-	-						
1 Set	12x16x7/8	Pipe Door, Jamb & Trim	-	-	-						
						BUILDING PAPER					
Interior Finish: Main Rooms, First Floor						4	Rolls 50#	Building Paper (500 Ft. Rolls)	-	-	-
1		Sides of Trim For 3/0x6/8 Door with 3/0x10" Circular Transom Opg. See Plan	-	-	-	SHEET METAL MATERIAL					
1		Sides of Trim For 2/6x6/8 Door	-	-	-	70	Sq. Ft.	Metal Roofing with Nails & Felt	-	-	-
1		Sides of Trim For 2/0x6/8 Door	-	-	-	50	Lin. Ft. 14"	Valley Tin & Flashing	-	-	-
1		Sides of Trim For 2/8x6/8 C.O.	-	-	-	65	Pc. 10x12	Tin Shingles	-	-	-
1		Sides of Trim For 2/0x6/8 Closet Door	-	-	-	70	Lin. Ft. 5"	Gutter Eaves Trough	-	-	-
2		Sides of Trim For 8x12 - 16 Lt. Windows	-	-	-	20	5"	Hangers	-	-	-
1		Sides of Trim For Triple Bay Window Center 10x12 - 2 Lt., Sides 22"x24" - 2 Lt. See Plan	-	-	-	6	5"	End Caps	-	-	-
		Base	-	-	-	6	5x3"	Drop Outlets	-	-	-
70	Lin. Ft.	Base Shoe	-	-	-	60	Lin. Ft. 3"	Conductor Pipe	-	-	-
80	Lin. Ft.	Picture Mould	-	-	-	12	3"	Elbows	-	-	-
85	Lin. Ft.	Closet Base	-	-	-	18	3"	Conductor Pipe, Hooks	-	-	-
10	Lin. Ft.	Hook Strips	-	-	-	6	3"	Strainers	-	-	-
1	Pc. 3/6	Thresholds	-	-	-						
Interior Finish: Balance of Rooms, First Floor											
3		Sides of Trim For 2/8x6/8 Doors	-	-	-	60	Lbs. 20d	Common Nails	-	-	-
5		Sides of Trim For 2/6x6/8 Doors	-	-	-	60	Lbs. 16d	Common Nails	-	-	-
4		Sides of Trim For 2/0x6/8 Doors	-	-	-	25	Lbs. 10d	Common Nails	-	-	-
1		Sides of Trim For 1/10x6/8 Doors	-	-	-	125	Lbs. 8d	Common Nails	-	-	-
1		Sides of Trim For 1/0x6/8 Doors	-	-	-	10	Lbs. 6d	Common Nails	-	-	-
1		Sides of Trim For 2/8x6/8 C.O.	-	-	-	5	Lbs. 10d	Casing Nails	-	-	-
1		Sides of Trim For 1/10x6/8 Closet Doors	-	-	-	45	Lbs. 8d	Casing Nails	-	-	-
2		Sides of Trim For 2/0x6/8 Closet Doors	-	-	-	5	Lbs. 6d	Casing Nails	-	-	-
1		Sides of Trim For 1/0x6/8 Closet Doors	-	-	-	5	Lbs. 10d	Finish Nails	-	-	-
4		Sides of Trim For 8x12 - 12 Lt. Windows	-	-	-	15	Lbs. 8d	Finish Nails	-	-	-
1		Sides of Trim For 8x10 - 12 Lt. Windows	-	-	-	5	Lbs. 6d	Finish Nails	-	-	-
1		Sides of Trim For 24x16 - 2 Lt. Windows	-	-	-	2	Lbs. 4d	Finish Nails	-	-	-
1	Mull	Base	-	-	-	1	Lb. 7/8"	Finish Brads (16 Gauge)	-	-	-
145	Lin. Ft.	Base Shoe	-	-	-	60	Lbs. 3d	Shingle Nails Hot Dipped Zinc Coated	-	-	-
200	Lin. Ft.	Picture Mould	-	-	-	40	Lbs. 8d	Coated Nails For Siding	-	-	-
100	Lin. Ft.	Chair Rail	-	-	-	2	Lbs. 3d	Fine Lath Nails	-	-	-
50	Lin. Ft.	Hook Strips	-	-	-	2	Lbs. 20d	Cut Nails	-	-	-
50	Lin. Ft.	Shelf Cleats	-	-	-						
30	Lin. Ft.	Thresholds	-	-	-						
1	Pc. 3/0	Closet Base	-	-	-						
55	Lin. Ft.	Scuttle Door, Jamb & Trim	-	-	-						
1 Set	26x26"7/8		-	-	-						
Main Stair											
2		Landing Treads	-	-	-	PAINT					
						6-1/2	Gals.	Outside Body Paint	-	-	-
						2-1/2	Gals.	Outside Trim Paint	-	-	-
						1/2	Gals.	Porch Ceiling Paint	-	-	-
						1/2	Gals.	Blind or Shutter Paint	-	-	-
						1	Gals.	Sheet Metal Paint (Mineral)	-	-	-
						3-1/2	Gals.	Inside Varnish	-	-	-
						4-1/2	Gals.	Floor Varnish	-	-	-
						1/2	Gals.	Spar Varnish	-	-	-
						1/4	Gals.	Shellac	-	-	-
						2	Gals.	Liquid Wood Filler	-	-	-
						1/2	Gals.	Flat White	-	-	-
						3/4	Gals.	White Enamel	-	-	-
						2	Gals.	Boiled Linseed Oil	-	-	-
						2	Gals.	Turpentine	-	-	-
						20	Lbs.	Putty	-	-	-

MATERIAL LIST FOR THE APRIL 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
2 Pc.	2x8-18	Main Building Wall Plates - - - - -	48	130 Ft.	1x6	Facias & Frieze - - - - -	130
8 Pc.	2x8-14	Main Building Wall Plates - - - - -	149	42 Ft.	1x8	Plancier & Frieze - - - - -	42
2 Pc.	2x8-12	Main Building Wall Plates - - - - -	32	2 Pc.	1x4-10	Dormer Plancier - - - - -	7
2 Pc.	2x8-10	Main Building Wall Plates - - - - -	27	50 Ft.	1x8	Porch Lintle Frieze - - - - -	50
3 Pc.	2x10-16	Main Building Box Sills - - - - -	80	15 Ft.	1x4	Porch Lintls Soffit - - - - -	15
Girders and Lintles				20 Ft.1x4 to 1x10		Miscellaneous O.S.Finish - - - - -	20
2 Pc.	6x8-14	Main Building - - - - -	112	Inside Finish Lumber			
1 Pc.	6x8-8	Main Building - - - - -	32	4 Pc.	1x12-10	Shelving - - - - -	40
2 Pc.	2x8-16	Front Porch Roof Beam - - - - -	43	3 Pc.1-1/4x10-14		Csllar Stair Treads - - - - -	44
4 Pc.	2x8-10	Front Porch Roof Beam - - - - -	53	3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
Girder Posts				2 Pc.	2x4-10	Cellar Stair Rails & Newels - - - - -	13
4 Pc.	6x6-7	Main Building - - - - -	84	2 Pc.	1x4-6	Cellar Stair Rails - - - - -	4
Floor Joists, Headers and Trimmers				INSULATION			
22 Pc.	2x10-10	First Floor Main Building - - - - -	367	1900 Sq.Ft.		Insulating Material - - - - -	
37 Pc.	2x10-12	First Floor Main Building - - - - -	740	MASONRY MATERIAL			
1 Pc.	2x4-12	Hearth Floor Supports - - - - -	8	Concrete Foundation 1-3-5 Mixture - 950 Cu.Ft.			
4 Pc.	2x4-14	Fire Stops - - - - -	37	28-1/4 Cu.Yds.		Crushed Stone or Gravel - - - - -	
4 Pc.	2x4-10	Fire Stops - - - - -	27	17 Cu.Yds.		Coarss Sand - - - - -	
38 Pc.	2x10-12	Second Floor Main Building - - - - -	760	40 Bbls.		Portland Cement - - - - -	
21 Pc.	2x10-10	Second Floor Main Building - - - - -	350	Cement Floor and Steps 4" One Course - 700 Sq.Ft.			
Csiling Joists				7 Cu.Yds.		Crushed Stone or Gravel - - - - -	
11 Pc.	2x6-10	Main Building - - - - -	110	4-3/4 Cu.Yds.		Coarss Sand - - - - -	
13 Pc.	2x6-14	Main Building - - - - -	182	10-3/4 Bbls.		Portland Cement - - - - -	
4 Pc.	2x6-8	Dormers - - - - -	32	Iron and Stesl			
9 Pc.	2x6-10	Front Porch - - - - -	90	1	4x4x1/4"	Angle Iron 5'4" Long - - - - -	
1 Pc.	2x6-16	Chimney Headers - - - - -	16	6	4x4x1/4"	Angle Iron 4'0" Long - - - - -	
Outside Studs				2	4x4x1/4"	Angle Iron 3'8" Long - - - - -	
112 Pc.	2x4-10	Main Building - - - - -	747	1	4x4x1/4"	Angle Iron 3'4" Long - - - - -	
26 Pc.	2x4-12	Gables - - - - -	208	5	4x4x1/4"	Angle Iron 3'10" Long - - - - -	
10 Pc.	2x4-8	Porch Gables - - - - -	53	Brickwork and Fireplace			
48 Pc.	2x4-8	Dormers - - - - -	256	10400		Common Brick - - - - -	
8 Pc.	2x6-8	Window Lintles - - - - -	64	60		Face Brick For Fireplace - - - - -	
2 Pc.	2x8-8	Window Lintles - - - - -	21	120		Fire Clay Brick - - - - -	
Inside Studs				10-1/2 Cu.Yds.		Sand - - - - -	
58 Pc.	2x4-8	First Floor - - - - -	309	10-1/2 Bbls.		Lime - - - - -	
8 Pc.	2x6-8	First Floor - - - - -	64	1 Bbl.		Portland Cement - - - - -	
46 Pc.	2x4-8	Second Floor - - - - -	245	50 Lbs.		Fire Clay - - - - -	
16 Pc.	2x4-10	Second Floor (Cut) - - - - -	107	52 Lin.Ft. 8x12"		Flue Lining - - - - -	
6 Pc.	2x6-8	Second Floor - - - - -	48	15 Sq.Ft. 1/2"		Wire Mesh Reinforcing For Hearth - - - - -	
Stud and Partition Plates				1		Damper - - - - -	
28 Pc.	2x4-14	Outside Walls - - - - -	261	1		Ash Dump - - - - -	
34 Pc.	2x4-12	Inside Partitions - - - - -	272	1		Clsanout Door - - - - -	
3 Pc.	2x6-14	Inside Partitions - - - - -	42	1	4x4x1/4"	Angle Iron 3'8" Long - - - - -	
Rafters				1200		Ties For Brick Veneer - - - - -	
35 Pc.	2x6-18	Main Building - - - - -	630	Plastering			
6 Pc.	2x6-10	Main Building (Cut) - - - - -	60	435 Yds.		Plaster, Including Plaster Base, Nails, Metal	
5 Pc.	1x6-6	Collar Beams Porch - - - - -	15	12 Yds.		Lath Corner Strips, and Metal Corner Bsads -	
13 Pc.	2x6-12	Front Porch - - - - -	156			Cement Plaster, Including Metal Lath &	
13 Pc.	2x6-14	Dormers - - - - -	182			Stapls For Over Boiler Space - - - - -	
10 Pc.	2x4-8	Dormers (Cut)-- - - - - -	53	MILLWORK			
2 Pc.	2x6-12	Vallsy Rafters - - - - -	24	Outside Millwork and Mouldings			
2 Pc.	1x8-14	Ridge Boards - - - - -	19	280 Lin.Ft.		Bed Moulding - - - - -	
1 Pc.	1x8-10	Ridge Boards - - - - -	7	60 Lin.Ft.		Cove Moulding - - - - -	
2 Pc.	1x6-8	Ridge Boards - - - - -	8	20 Lin.Ft.		Drip Cap - - - - -	
Step and Stair Carriages				4	6x6-8	Porch Columns See Plan - - - - -	
2 Pc.	2x10-14	Cellar Stairs - - - - -	47	1		Front Entrance & Door Frame 3/0x6/3x1-3/4	
2 Pc.	2x10-16	Main Stairs - - - - -	53			Transom 3/0x10x1-3/4 For Brick Veneer See Pl.	
Shsathing, Boards, Sub-flooring, Furring, Etc.,				Outsids Door Frames			
900 Ft.	1x4	Roof Sheathing, S.2.S. 4-1/2" O.C. -	900	2	2/8x6/8x1-3/4	Door Frames For Brick Veneer - - - - -	
380 Ft.	1x6	Roof Sheathing D&M (Over Rooms& Dormer)	380	Window and Sash Frames			
1310 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally -	1310	5	10x12x1-1/8	3 Lt.Cellar Sash Frames Plank - - - - -	
1920 Ft.	1x8	Box Sheathing O.S.Walls Shiplap		5	8x12x1-3/8	16 Lt.Ck.Rail Window Frames P&P Brick Veneer-	
		Laid Diagonally -	1920	1	8x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P Brick Veneer-	
200 Ft.	1x6	Ribbons, Backing & Furring - - - - -	200	1	32x16x1-3/8	2 Lt.Ck.Rail Window Frames P&P Brick Veneer -	
8 Pc.	1x2-8	Furring Inside Walls (Chimney Breast)	11	1	8x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
900 Lin.Ft.	1x1	Ground (Around Inside Openings) - -	75	2	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
110 Ft.	1x4	Bridging - - - - -	110	1	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
20 Ft.	1x4	Lookouts - - - - -	20	1	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P No Headcasing	
60 Ft.	1x2	Floor Striping 2 nd Floor Only - - -	60	1	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
Siding for Outside Walls				1	8x10x1-3/8	6 Lt.Sash Frame D.C. - - - - -	
705 Ft.	3/4x10"	Bev.Siding 1" Lap. - - - - -	630	Windows and Sash			
Flooring and Ceiling				5	10x12x1-1/8	3 Lt.Cellar Sash Glz. - - - - -	
460 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor - -	460	5	8x12x1-3/8	16 Lt.Ck.Rail Window Glz. - - - - -	
175 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - -	175	2	8x12x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
550 Ft.	3/4x3-1/4	Flooring, Second Floor - - - - -	550	5	8x10x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
110 Ft.	1x6	Attic Flooring D&M - - - - -	110	1	32x16x1-3/8	2 Lt.Ck.Rail Window Glz. Div. 8 Lts. - - - - -	
164 Ft.	5/8x3-1/4	Ceiling Porchss - - - - -	164	1	8x10x1-3/8	6 Lt.Casement Sash Glz. - - - - -	
Shingles				1	3/0x10x1-3/4	Transom Sash Glz. Div. 3 Lt. - - - - -	
11-1/2 Squares 16"		Shingles For Roof Certigrade Red Cedar		Blinds			
		4-1/2" Exposure - - - - -		4 Pr.	8x12	- 16 Lt.Window Blinds - - - - -	
Lath				1 Pr.	8x12	- 12 Lt.Window Blinds - - - - -	
250	48"	Exterior Lath For Furring - - - - -		1 Pr.	8x10	- 12 Lt.Window Blinds - - - - -	

MATERIAL LIST FOR THE APRIL 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			MILLWORK (CONTINUED)		
Doors and Jambs For Main Rooms First Floor			Cabinets		
1	3/0x6/8x1-3/4	Front Door Panelled	1		Mantel Shelf & Trim, See Plan
1	2/6x6/8x1-3/8	Inside Door Panelled	1		Medicine Cabinet
1	2/0x6/8x1-3/8	Inside Door Panelled			Kitchen Cabinet Over Ref.Space with Hdwe.
1	2/8x6/8x1-3/4	French Door Glz. 15 Lts.	2		See Plan
1	Set 7/8x5-5/8	Door Jambs For 2/6x6/8 Door			Combination Kitchen Cabinets, and Worktable
1	Set 7/8x3-5/8	Door Jambs For 2/0x6/8 Door			Complete with Hdwe., See Plan
2	Sets 7/8x5-5/8	C.O.Jambs For 4/6x6/8 & Smaller Doors	FINISH HARDWARE		
For Balance - First Floor			5		Cellar Sash Sets
1	2/8x6/8x1-3/4	Rear Door Glz.	1		Attic Sash Set
1	2/6x6/8x1-3/8	Inside Door Panelled	4-1/2	Pr. 4x4	Door Butts
1	1/8x6/8x1-3/8	Inside Door Panelled	8	Pr. 3-1/2x3-1/2	Door Butts
1	Set 7/8x7-5/8	Door Jambs For 2/6x6/8 Door	1	Pr. 2-1/2	Cupboard Door Butts, Narrow
1	Set 7/8x5-5/8	Door Jambs For 1/8x6/8 Door	1	Pr. 3-1/2x3-1/2	Bathroom Door Butts,
			1	Pr. 2-1/2	Medicine Cabinet Butts, Narrow
Doors and Jambs For Second Floor			1		Front Door Lock Set
2	2/6x6/6x1-3/8	Inside Door Panelled	1		Rear Door Lock Set
1	2/4x6/6x1-3/8	Inside Door Panelled	8		Inside Door Lock Sets
2	2/0x6/6x1-3/8	Inside Door Panelled	1		Bathroom Door Lock Set
1	2/0x6/0x1-3/8	Inside Door Panelled	1	Single	French Door Lock Set
6	Sets 7/8x5-5/8	Door Jambs For 2/6x6/6 Doors & Smaller	1	Set 1-3/8"	Floor Double Acting Hinge
1	Set 12x16x7/8	Pipe Door, Jambs & Trim	2		Push Plates
Interior Finish: Main Rooms, First Floor			12		Sash Locks
1		Sides of Trim For 3/0x6/8 Door with 3/0x10" Transom-	24		Sash Lifts
1		Sides of Trim For 2/3x6/8 Door	2		Sash Lifts, Bathroom
1		Sides of Trim For 2/6x6/8 Door	1		Sash Lock, Bathroom
1		Sides of Trim For 2/0x6/8 Door	1		Cupboard Turn
2		Sides of Trim For 4/6x6/8 C.O.	8		Cupboard Turn, Med.Case
2		Sides of Trim For 4/0x6/8 C.O.	1		Metal Base Knobs
1		Sides of Trim For 2/0x6/8 Closet Door	4	Doz.	Metal Base Knob, Bathroom
5		Sides of Trim For 8x12 - 16 Lt.Windows	1		Coat and Hat Hooks
10	Lin.Ft.	Closet Base	1		Transom Lift
80	Lin.Ft.	Base	1	Pr.	Transom Butts
90	Lin.Ft.	Base Shoe	6	Sets	Window Blind Hangers With Fasteners
120	Lin.Ft.	Picture Mould	Rough Hardware		
10	Lin.Ft.	Hook Strips	3	Hanks	Sash Cord
10	Lin.Ft.	Shelf Cleats	22		Anchor Bolts With Nuts & Washers
1	Pc. 3/6	Thresholds	4	Sets 6"	C.I.Post Caps & Sockets With Lag Screws
1	Pc. 3/0	Thresholds	325	Lbs.	Sash Weights
Interior Finish: Balance of Rooms, First Floor			BUILDING PAPER		
1		Sides of Trim For 2/8x6/8 Door	5	Rolls 50 Lb.	Building Paper (500 Ft.Rolls)
3		Sides of Trim For 2/6x6/8 Door	SHEET METAL MATERIAL		
1		Sides of Trim For 1/8x6/8 Door	175	Sq.Ft.	Metal Roofing with Nails
1		Sides of Trim For 1/8x6/8 Closet Door	50	Lin.Ft. 14"	Valley Tin Flashing
1		Sides of Trim For 8x12 - 12 Lt.Window	185	Pc. 10x12"	Tin Shingles
1		Sides of Trim For 32x16 - 2 Lt.Window	80	Lin.Ft. 5"	Gutter Eaves Trough
60	Lin.Ft.	Base	2	Doz. 5"	Hangers
70	Lin.Ft.	Base Shoe	12	5"	End Caps
40	Lin.Ft.	Chair Rail	6	5x3"	Drop Outlets
10	Lin.Ft.	Shelf Cleats	60	Lin.Ft. 3"	Conductor Pipe
10	Lin.Ft.	Hook Strips	12	3"	Elbows
10	Lin.Ft.	Closet Base	18	3"	Conductor Pipe, Hooks
1	Pc. 3/0	Thresholds	6	3"	Strainers
Interior Finish: Second Floor			12	Lin.Ft.	Vents For Gas Flue
4		Sides of Trim For 2/6x6/6 Doors	NAILS		
2		Sides of Trim For 2/4x6/6 Doors	80	Lbs. 20d	Common Nails
2		Sides of Trim For 2/0x6/6 Doors	80	Lbs. 16d	Common Nails
1		Sides of Trim For 2/0x6/0 Door	30	Lbs. 10d	Common Nails
2		Sides of Trim For 2/0x6/6 Closet Doors	160	Lbs. 8d	Common Nails
1		Sides of Trim For 8x12 - 12 Lt.Windows	15	Lbs. 6d	Common Nails
3		Sides of Trim For 8x10 - 12 Lt.Windows	45	Lbs. 8d	Casing Nails
1	Mullion	Sides of Trim For 8x10 - 12 Lt.Windows	5	Lbs. 10d	Casing Nails
4	Lin.Ft.	Sash Stool (Storage Room)	5	Lbs. 6d	Casing Nails
130	Lin.Ft.	Base	5	Lbs. 10d	Finish Nails
162	Lin.Ft.	Base Shoe	15	Lbs. 8d	Finish Nails
32	Lin.Ft.	Closet Base	5	Lbs. 6d	Finish Nails
115	Lin.Ft.	Picture Mould	2	Lbs. 4d	Finish Nails
24	Lin.Ft.	Chair Rail	1	Lb. 7/8"	Finish Brads (16 Gauge)
30	Lin.Ft.	Hook Strips	55	Lbs. 3d	Shingle Nails Hot Dipped Zinc Coated
10	Lin.Ft.	Shelf Cleats	20	Lbs. 8d	Cement Coated Nails For Siding
2	Lin.Ft.	Nosing	5	Lbs. 3d	Fine Lath Nails
60	Lin.Ft.	Cove Mould	2	Lbs. 20d	Cut Nails For Furring
3	Lin.Ft.	Face Mould	PAINT		
28	Lin.Ft.	Wall String (2 Mem.)	2-1/2	Gals.	Outside Body Paint
3	Lin.Ft.	Face String	3	Gals.	Outside Trim Paint
14	Lin.Ft.	Wall Rail	1	Gals.	Porch Ceiling Paint
3		Wall Rail Brackets	1/2	Gals.	Blind or Shutter Paint
2		Stair Rail Acorn Ends	1	Gals.	Sheet Metal Paint (Mineral)
Main Stair			6	Gals.	Paint For Brick Work Undercoat
1		Starting Newel	5-1/2	Gals.	Inside Varnish
1		Corner Pilaster Newel	6	Gals.	Floor Varnish
1		Circle End Tread & Riser, See Plan	1/2	Gals.	Spar Varnish
1		Circle Starting Tread & Riser, See Plan	1/4	Gals.	Shellac
11		Treads	2-1/2	Gals.	Liquid Wood Filler
12		Risers	1/2	Gals.	Flat White
9	Lin.Ft.	Landing Treads	1	Gals.	White Enamel
2	Lin.Ft.	Rail	6	Gals.	Paint For Brickwork Top Coat
6	32"	Balusters	2	Gals.	Boiled Linseed Oil
			2	Gals.	Turpentine
			15	Lbs.	Putty

MATERIAL LIST FOR THE MAY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
2 Pc.	2x6-12	Main Building Wall Plates - - - - -	24	125 Ft.	1x8	Facias, Frieze & Plancier - - - - -	125
4 Pc.	2x6-18	Main Building - - - - -	72	25 Ft.	1x6	Frieze (Dormer) - - - - -	25
4 Pc.	2x6-16	Main Building - - - - -	64	25 Ft.	1x12	Porch Lintle Frieze - - - - -	25
3 Pc.	2x6-14	Main Building - - - - -	42	20 Ft.	1x8	Porch Lintle Frieze - - - - -	20
2 Pc.	2x6-10	Main Building - - - - -	20	15 Ft.	1x6	Porch Lintle Soffit - - - - -	15
Girders and Lintles				6 Pc.	6x6-9	Rear Porch Posts - - - - -	162
1 Pc.	6x8-18	Main Building - - - - -	72	25 Ft. 1x4 to 1x10		Miscellaneous O.S. Finish - - - - -	25
1 Pc.	6x8-12	Main Building - - - - -	48	Inside Finish Lumber			
3 Pc.	2x10-16	Rear Porch Roof Beam - - - - -	80	4 Pc.	1x12-10	Shelving - - - - -	40
1 Pc.	2x10-20	Rear Porch Roof Beam (Cut) - - - - -	33	3 Pc. 1-1/4x10-14		Cellar Stair Treads - - - - -	44
Girder Posts				3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
4 Pc.	6x6-7	Main Building - - - - -	84	2 Pc.	2x4-10	Cellar Stair Rails & Newels - - - - -	13
Floor Joists, Headers and Trimmers				2 Pc.	1x4-8	Cellar Stair Rails - - - - -	5
12 Pc.	2x10-12	First Floor Main Building - - - - -	240	INSULATION			
12 Pc.	2x10-10	First Floor Main Building - - - - -	200	2050 Sq.Ft.		Material For Insulating - - - - -	
10 Pc.	2x10-16	First Floor Main Building - - - - -	267	MASONRY MATERIAL			
16 Pc.	2x10-14	First Floor Main Building - - - - -	373	Concrete Foundation 1-3-5 Mixture - 746 Cu.Ft.			
1 Pc.	2x10-18	First Floor Box Sill - - - - -	30	22 Cu.Yds.		Crushed Stone or Gravel - - - - -	
2 Pc.	2x10-12	First Floor Box Sill - - - - -	40	13-1/4 Cu.Yds.		Coarse Sand - - - - -	
1 Pc.	2x10-10	First Floor Box Sill - - - - -	17	30 Bbls.		Portland Cement - - - - -	
1 Pc.	2x4-8	Hearth Support - - - - -	5	Stone Work			
2 Pc.	2x6-8	Bay Headers - - - - -	16	50 So.Ft. 4"		Flagstone (Porch) - - - - -	
10 Pc.	2x10-16	Second Floor Main Building - - - - -	267	Cement Floor and Steps - 675 Sq.Ft.			
20 Pc.	2x10-14	Second Floor Main Building - - - - -	467	6-3/4 Cu.Yds.		Crushed Stone or Gravel - - - - -	
15 Pc.	2x10-12	Second Floor Main Building - - - - -	300	4-1/2 Cu.Yds.		Coarse Sand - - - - -	
10 Pc.	2x10-10	Second Floor Main Building - - - - -	167	10-1/2 Bbls.		Portland Cement - - - - -	
1 Pc.	2x10-8	Second Floor Main Building - - - - -	13	Chimneys and Fireplace			
2 Pc.	2x4-14	Raised Floor Framing - - - - -	19	3950		Common Brick - - - - -	
Ceiling Joists				1450		Face Brick - - - - -	
17 Pc.	2x6-16	Main Building - - - - -	272	120		Fire Clay Brick - - - - -	
5 Pc.	2x6-10	Main Building - - - - -	50	6 Cu.Yds.		Sand - - - - -	
3 Pc.	2x4-12	Lookouts - - - - -	24	6 Bbls.		Lime - - - - -	
Outside Studs				1 Bbl.		Portland Cement - - - - -	
134 Pc.	2x4-8	Main Building - - - - -	715	150		Face Brick For Fireplace - - - - -	
10 Pc.	1x4-10	Corner Braces - - - - -	33	50 Lin.Ft. 8x12"		Flue Lining - - - - -	
26 Pc.	2x4-14	Gables - - - - -	243	50 Lbs.		Fire Clay - - - - -	
7 Pc.	2x4-8	Gables - - - - -	37	15 Sq.Ft. 1/2"		Wire Mesh For Hearth Reinforcing - - - - -	
12 Pc.	2x6-6	Window Lintles - - - - -	72	1		Damper - - - - -	
38 Pc.	2x4-8	Dormers - - - - -	203	1		Ash Dump - - - - -	
8 Pc.	2x4-6	Dormers - - - - -	32	1		Cleanout Door - - - - -	
Inside Studs				1	4x4x1/4"	Angle Iron 3'8" Long - - - - -	
35 Pc.	2x4-8	First Floor - - - - -	187	2 Sets		Rough Cut Stone For Chimney Corbels - - - - -	
3 Pc.	2x6-8	First Floor - - - - -	24	14 Cu.Ft.		Rough Cut Stone For Chimney Trim - - - - -	
60 Pc.	2x4-8	Second Floor - - - - -	320	Plastering			
6 Pc.	2x6-8	Second Floor - - - - -	48	460 Yds.		Plaster, Including Plaster Base, Nails, Metal Lath Corner Strips, and Metal Corner Beads - - - - -	
14 Pc.	2x4-10	Second Floor (Cut) - - - - -	93	12 Yds.		Cement Plaster, Including Metal Lath & Staples For Over Boiler Space - - - - -	
Stud and Partition Plates				ORNAMENTAL IRON			
32 Pc.	2x4-14	Outside Walls - - - - -	299	1		Ornamental Chimney Anchor, See Plan - - - - -	
32 Pc.	2x4-12	Inside Partitions - - - - -	256	MILLWORK			
3 Pc.	2x6-6	Inside Partitions - - - - -	18	Outside Millwork and Mouldings			
Rafters				230 Lin.Ft.		Bed Moulding - - - - -	
28 Pc.	2x6-20	Main Building - - - - -	560	50 Lin.Ft.		Cove Moulding - - - - -	
8 Pc.	2x6-12	Main Building - - - - -	96	25 Lin.Ft.		1/4 Round Moulding - - - - -	
18 Pc.	2x6-6	Main Building - - - - -	108	25 Lin.Ft.		Drip Cap - - - - -	
2 Pc.	2x4-12	Bays (Cut) - - - - -	16	1		Front Entrance & Door Frame, 3/0x6/8x1-3/4 O.S. See Plan - - - - -	
18 Pc.	2x6-16	Dormers - - - - -	288	1	5/0	Flower Box See Plan - - - - -	
1 Pc.	2x6-10	Hip Rafters (Cut) - - - - -	10	2		Flower Box Brackets, See Plan - - - - -	
2 Pc.	2x8-14	Valley Rafters - - - - -	37	2		Bay Brackets, See Plan - - - - -	
1 Pc.	2x6-10	Valley Rafters - - - - -	10	Outside Door Frames			
2 Pc.	1x8-14	Ridge Boards - - - - -	19	1 2/6x6/8x1-3/4		Side Door Frame D.C. - - - - -	
1 Pc.	1x8-12	Ridge Boards - - - - -	8	1 2/8x6/8x1-3/4		Rear Door Frame D.C. - - - - -	
Step and Stair Carriages				Window and Sash Frames			
2 Pc.	2x10-14	Cellar Stairs - - - - -	47	3 10x12x1-1/8		3 Lt. Cellar Sash Frames Plank - - - - -	
2 Pc.	2x10-16	Main Stairs - - - - -	53	4 8x12x1-3/8		8 Lt. Sash Frames D.C. For Pairs Sash - - - - -	
Sheathing, Boards, Sub-flooring, Furring, Etc.,				1 8x10x1-3/8		6 Lt. Sash Frames D.C. For Pairs Sash - - - - -	
725 Ft.	1x4	Roof Sheathing S.2.S.4-1/2" O.C. - - - - -	725	1 8x10x1-3/8		8 Lt. Sash Frames D.C. For Pairs Sash - - - - -	
540 Ft.	1x6	Roof Sheathing D&M - - - - -	540	1 8x10x1-3/8		8 Lt. Sash Frames No Head For Pairs Sash - - - - -	
1360 Ft.	1x6	Sub-flooring D&M Laid Diagonally - - - - -	1360	1 Single 8x10x1-3/8		8 Lt. Sash Frames No Head For Pairs Sash - - - - -	
1860 Ft.	1x8	Box Sheathing O.S. Walls Ship Lap - - - - -	1860	5 Single 8x10x1-3/8		8 Lt. Sash Frames D.C. - - - - -	
150 Ft.	1x6	Backing & Furring - - - - -	150	1 2/4x3/2x1-3/8		(Opg. Size) Sash Frame D.C. - - - - -	
8 Pc.	1x2-8	Furring Inside Walls (Chimney Breast) - - - - -	11	1 Triple		Bay Sash Frame 8x10x1-3/8 - 8 Lt. Pair Center 8x10x1-3/8 4 Lt. Sides - - - - -	
20 Ft.	1x6	Furring Roofs (Cut to Curve) - - - - -	20	1 1/0x2/3x1-3/8		(Opg. Size) Sash Frame See Plan - - - - -	
900 Lin.Ft.	1x1	Ground (Around Inside Openings) - - - - -	75	Windows and Sash			
114 Ft.	1x4	Bridging - - - - -	114	3 10x12x1-1/8		3 Lt. Cellar Sash Glz. - - - - -	
75 Ft.	1x2	Flooring Stripping 2nd Floor Only - - - - -	75	4 Pr. 8x12x1-3/8		Sash Glz. 9 Lts. Each Sash - - - - -	
Siding For Outside Walls				1 Pr. 8x10x1-3/8		Sash Glz. 6 Lts. Each Sash - - - - -	
130 Ft. 3/4x10"		Bev. Siding Rustic 1-1/2" Lap (Incl. Blinds) - - - - -	130	3 Pr. 8x10x1-3/8		Sash Glz. 8 Lts. Each Sash - - - - -	
20 Ft. 3/4x10"		Ship Lap Siding - - - - -	20	6 Single 8x10x1-3/8		8 Lt. Sash Glz. - - - - -	
13-1/2 Squares 16"		Stained Wall Shingles Certigrade Red Cedar 12" Exp. Double Course - - - - -		1 Single 8x10x1-3/8		6 Lt. Sash Glz. - - - - -	
Flooring and Ceiling				2 Single 8x10x1-3/8		4 Lt. Sash Glz. - - - - -	
530 Ft. 3/4x3-1/4		Flooring, Main Rooms First Floor - - - - -	530	1 Single 8x10x1-3/8		(Opg. Size) Sash Glz. Ledged Glass - - - - -	
145 Ft. 3/4x3-1/4		Flooring, Balance First Floor - - - - -	145	1 Single 1/0x2/3x1-3/8		(Opg. Size) Sash Glz. Ledged Glass - - - - -	
570 Ft. 3/4x3-1/4		Flooring, Second Floor - - - - -	570	LATH			
125 Ft. 1x6		Attic Flooring D&M (Storage Room) - - - - -	125	50	48"	Exterior Lath For Gable Furring - - - - -	
120 Ft. 5/8x3-1/4		Ceiling Porches - - - - -	120				

MATERIAL LIST FOR THE MAY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)					
Blinds			FINISH HARDWARE		
3 Pr.		Blinds For Pairs Sash 8x12 - 8 Lt. - - - - -	3		Cellar Sash Sets - - - - -
4 Pr.		Blinds For Pairs Sash 8x10 - 8 Lt. - - - - -	1		Attic Sash Set - - - - -
2 Single		Blinds For 8x10 - 8 Lt.Sash - - - - -	4-1/2 Pr.	4x4	Door Butts - - - - -
Doors and Jambs For Main Rooms First Floor			7 Pr.	3-1/2x3-1/2	Door Butts - - - - -
1	3/0x6/8x1-3/4	Front Door "V" Joint Glz. See Plan - - - - -	25 Pr.	3x3	Casement Sash Butts - - - - -
1	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	1 Pr.	3x3	Casement Sash Butts, Bathroom - - - - -
1	2/6x6/8x1-3/4	French Door Glz. - - - - -	1 Pr.	2-1/2	Cupboard Door Butts, Narrow - - - - -
1 Set	7/8x5-5/8	Door Jambs For 2/6x6/8 Door - - - - -	1 Pr.	3-1/2x3-1/2	Bathroom Door Butts - - - - -
For Balance - First Floor			1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow - - - - -
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	1		Front Door Lock Set - - - - -
1	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	1		Rear Door Lock Set - - - - -
1 Set	7/8x5-5/8	Door Jambs For 2/6x6/8 Door - - - - -	7		Inside Door Lock Set - - - - -
Doors and Jambs For Second Floor			1		Bathroom Door Lock Set - - - - -
3	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	1 Single		French Door Lock Set - - - - -
1	2/2x6/6x1-3/8	Inside Door Panelled - - - - -	1 Set	1-3/8"	Floor Double Acting Hinge - - - - -
1	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	2		Push Plates - - - - -
1	2/1x1/6x1-3/8	Inside Door Panelled - - - - -	9 Sets		Casement Sash Fasteners, Single - - - - -
1	1/4x6/6x1-3/8	Inside Door Panelled - - - - -	8 Sets		Casement Sash Fasteners, Double - - - - -
3 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	1 Set		Casement Sash Fasteners, Single Bathroom - - - - -
4 Sets	7/8x3-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	1		Cupboard Turn - - - - -
1 Set	12x16x7/8	Pipe Door, Jambs & Trim - - - - -	1		Cupboard Turn, Med.Case - - - - -
Interior Finish: Main Rooms, First Floor			9		Metal Base Knobs - - - - -
1		Sides of Trim For 3/0x6/8 Door - - - - -	1		Metal Base Knob, Bathroom - - - - -
2		Sides of Trim For 2/6x6/8 Door - - - - -	2 Doz.		Coat and Hat Hooks - - - - -
4		Sides of Trim For Pr. 8x12 - 8 Lt.Sash - - - - -	3		W.I.Hinge Plates - - - - -
2		Sides of Trim For 8x10 - 8 Lt.Sash - - - - -	8 Sets		Window Blind Hangers With Fasteners - - - - -
1 Triple		Sides of Trim For Bay - Center Pr. 8 Lt. 8x10 Sides 8x10 - 4 Lt.With Special - - - - -	Rough Hardware		
		Wide Stool, See Plan - - - - -	22	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
115 Lin.Ft.		Base - - - - -	4 Sets	6"	C.I.Post Caps & Sockets With Lag Screws - - - - -
115 Lin.Ft.		Base Shoe - - - - -	BUILDING PAPER		
130 Lin.Ft.		Picture Mould - - - - -	6 Rolls	50 Lbs.	Building Paper (500 Ft.Rolls) - - - - -
6 Lin.Ft.		Thresholds - - - - -	SHEET METAL MATERIAL		
Interior Finish: Balance of Rooms, First Floor			300 Sq.Ft.		Metal Roofing, With Nails - - - - -
1		Sides of Trim For 2/8x6/8 Door - - - - -	75 Lin.Ft.	14"	Valley Tin Flashing - - - - -
2		Sides of Trim For 2/6x6/8 Door - - - - -	110 Pc.	10x12	Tin Shingles - - - - -
1		Sides of Trim For 2/6x6/8 Cellar Door - - - - -	60 Lin.Ft.	5"	Gutter Eaves Trough - - - - -
1		Sides of Trim For Pr. 8x10 - 6 Lt.O.S.Sash - - - - -	18	5"	Hangers - - - - -
1		Sides of Trim For 8x10 - 8 Lt.Sash - - - - -	1	5"	I.S.Mitres - - - - -
45 Lin.Ft.		Base - - - - -	10	5"	End Caps - - - - -
45 Lin.Ft.		Base Shoe - - - - -	6	5x3"	Drop Outlets - - - - -
45 Lin.Ft.		Chair Rail - - - - -	60 Lin.Ft.	3"	Conductor Pipe - - - - -
1 Pc.	3/0	Thresholds - - - - -	12	3"	Elbows - - - - -
Interior Finish: Second Floor			18	3"	Conductor Pipe, Hooks - - - - -
5		Sides of Trim For 2/6x6/6 Doors - - - - -	6	3"	Strainers - - - - -
2		Sides of Trim For 2/2x6/6 Doors - - - - -	16 Lin.Ft.		Vents For Gas Flue - - - - -
1		Sides of Trim For 2/0x6/6 Doors - - - - -	NAILS		
1		Sides of Trim For 1/4x6/6 Doors - - - - -	75 Lbs.	20d	Common Nails - - - - -
1		Sides of Trim For 2/4x4/6 Doors - - - - -	75 Lbs.	16d	Common Nails - - - - -
1		Sides of Trim For 2/6x6/6 Closet Doors - - - - -	25 Lbs.	10d	Common Nails - - - - -
1		Sides of Trim For 2/0x6/6 Closet Doors - - - - -	150 Lbs.	8d	Common Nails - - - - -
2		Sides of Trim For Pr. 8x10 - 8 Lt.Sash - - - - -	15 Lbs.	6d	Common Nails - - - - -
3		Sides of Trim For 8x10 - 8 Lt.Sash - - - - -	5 Lbs.	10d	Casing Nails - - - - -
1		Sides of Trim For 8x10 - 8 Lt.Sash - - - - -	45 Lbs.	8d	Casing Nails - - - - -
1		Sides of Trim For 2/4x3/2 O.S.Sash - - - - -	10 Lbs.	6d	Casing Nails - - - - -
1		Sides of Trim For 1/4x6/6 Closet Door - - - - -	5 Lbs.	10d	Finish Nails - - - - -
1		Sides of Trim For 2/4x4/6 Closet Door - - - - -	15 Lbs.	8d	Finish Nails - - - - -
1 Pc.		Sash Stool 2 Ft.Long - - - - -	5 Lbs.	6d	Finish Nails - - - - -
150 Lin.Ft.		Base - - - - -	2 Lbs.	4d	Finish Nails - - - - -
210 Lin.Ft.		Base Shoe - - - - -	1 Lb.	7/8"	Finish Brads (16 Gauge) - - - - -
55 Lin.Ft.		Closet Base - - - - -	50 Lbs.	3d	Shingle Nails Hot Dipped Zinc Coated (Roof) - - - - -
120 Lin.Ft.		Picture Mould - - - - -	10 Lbs.	8d	Cement Coated Nails For Siding - - - - -
26 Lin.Ft.		Chair Rail - - - - -	2 Lbs.	3d	Fine Lath Nails - - - - -
42 Lin.Ft.		Hook Strips - - - - -	65 Lbs.	5d	Galv.Shingle Nails Hot Dipped Zinc Coated (Walls) - - - - -
30 Lin.Ft.		Shelf Cleats - - - - -	2 Lbs.	20d	Cut Nails For Furring - - - - -
Main Stair			PAINT		
1		Starting Newel - - - - -	1 Gals.		Outside Body Paint - - - - -
1		Quarter Circle End Tread & Riser - - - - -	2-1/2 Gals.		Outside Trim Paint - - - - -
13		Treads - - - - -	1/2 Gals.		Porch Ceiling Paint - - - - -
14		Risers - - - - -	1/2 Gals.		Blind or Shutter Paint - - - - -
2		Landing Treads - - - - -	1 Gals.		Sheet Metal Paint (Mineral) - - - - -
10 Lin.Ft.		Rail - - - - -	5 Gals.		Inside Varnish - - - - -
28	32"	Balusters - - - - -	5 Gals.		Floor Varnish - - - - -
8 Lin.Ft.		Nosing - - - - -	1/2 Gals.		Spar Varnish - - - - -
60 Lin.Ft.		Cove - - - - -	1/4 Gals.		Shellac - - - - -
10 Lin.Ft.		Face Mould - - - - -	2-1/2 Gals.		Liquid Wood Filler - - - - -
18 Lin.Ft.		Wall String (2 Mem.) - - - - -	1/2 Gals.		Flat White - - - - -
10 Lin.Ft.		Face String - - - - -	3/4 Gals.		White Enamel - - - - -
1		Stair Part.Jamb - - - - -	1 Gals.		Boiled Linseed Oil - - - - -
2		Stair Part.Casing - - - - -	2 Gals.		Turpentine - - - - -
Cabinets			20 Lbs.		Putty - - - - -
1		Mantel Shelf & Bracket, See Plan - - - - -			
1		Medicine Cabinet - - - - -			
1		Kitchen Cabinet Over Ref.Space With Hdwe., See Plan - - - - -			
1		Combination Kitchen Cabinet and Worktable, Complete with Hdwe.,See Plan - - - - -			
1		Broom Closet Complete with Hdwe., - - - - -			

MATERIAL LIST FOR THE MAY 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
2 Pc.	2x6-12	Main Building - - - - -	24	100 Ft.	1x6	Frieze - - - - -	100
4 Pc.	2x6-18	Main Building - - - - -	72	25 Ft.	1x12	Porch Lintle Frieze - - - - -	25
4 Pc.	2x6-16	Main Building - - - - -	64	22 Ft.	1x8	Porch Lintle Frieze - - - - -	22
3 Pc.	2x6-14	Main Building - - - - -	42	12 Ft.	1x4	Porch Lintle Soffit - - - - -	12
2 Pc.	2x6-10	Main Building - - - - -	20	6	6x6-9	Porch Posts (Rear) - - - - -	162
Girders and Lintles				25 Ft.1x4 to 1x10		Miscellaneous O.S.Finish - - - - -	25
1 Pc.	6x8-18	Main Building - - - - -	72	Inside Finish Lumber			
1 Pc.	6x8-12	Main Building - - - - -	48	4 Pc.	1x12-10	Shelving - - - - -	40
2 Pc.	2x6-10	Front Porch Roof Beam (Cut) - - - - -	20	3 Pc.1-1/4x10-14		Cellar Stair Treads - - - - -	44
3 Pc.	2x10-16	Rear Porch Roof Beam - - - - -	80	3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
1 Pc.	2x10-20	Rear Porch Roof Beam(Cut) - - - - -	33	2 Pc.	2x4-10	Cellar Stair Rails & Newels - - - - -	13
Girder Posts				2 Pc.	1x4-8	Cellar Stair Rails - - - - -	5
4 Pc.	6x6-7	Main Building - - - - -	84	INSULATION			
Floor Joists, Headers and Trimmers				2050 Sq.Ft.		Insulating Material - - - - -	
12 Pc.	2x10-12	First Floor Main Building - - - - -	240	MASONRY MATERIAL			
12 Pc.	2x10-10	First Floor Main Building - - - - -	200	Concrete Foundation 1-3-5 Mixture - 746 Cu.Ft.			
10 Pc.	2x10-16	First Floor Main Building - - - - -	267	22 Cu.Yds.		Crushed Stone or Gravel - - - - -	
16 Pc.	2x10-14	First Floor Main Building - - - - -	373	13-1/4 Cu.Yds.		Coarse Sand - - - - -	
1 Pc.	2x10-18	First Floor Box Sill - - - - -	30	30 Bbls.		Portland Cement - - - - -	
2 Pc.	2x10-12	First Floor Box Sill - - - - -	40	Stone Work			
1 Pc.	2x10-10	First Floor Box Sill - - - - -	17	50 Sq.Ft. 4"		Flagstone - - - - -	
1 Pc.	2x4-8	Hearth Headers - - - - -	5	Cement Floor and Steps 675 Sq.Ft.			
10 Pc.	2x10-16	Second Floor Main Building - - - - -	267	6-3/4 Cu.Yds.		Crushed Stone or Gravel - - - - -	
20 Pc.	2x10-14	Second Floor Main Building - - - - -	467	4-1/2 Cu.Yds.		Coarse Sand - - - - -	
15 Pc.	2x10-12	Second Floor Main Building - - - - -	300	10-1/2 Bbls.		Portland Cement - - - - -	
10 Pc.	2x10-10	Second Floor Main Building - - - - -	167	Cut Stone			
1 Pc.	2x10-8	Second Floor Main Building - - - - -	13	2 Pc.	4"	Cut Stone Chimney Ledges, See Plan - - - - -	
2 Pc.	2x4-14	Raised Floor Framing - - - - -	19	Chimneys and Fireplace			
Ceiling Joists				4200		Common Brick - - - - -	
18 Pc.	2x6-16	Main Building - - - - -	288	1520		Face Brick For Chimney - - - - -	
6 Pc.	2x6-10	Main Building - - - - -	60	120		Fire Clay Brick - - - - -	
4 Pc.	2x4-6	Front Porch - - - - -	16	5 Cu.Yds.		Sand - - - - -	
Outside Studs				5 Bbls.		Lime - - - - -	
134 Pc.	2x4-8	Main Building - - - - -	715	1 Bbl.		Portland Cement - - - - -	
10 Pc.	1x4-10	Corner Braces - - - - -	33	150		Face Brick For Fireplace - - - - -	
26 Pc.	2x4-14	Gables - - - - -	243	50 Lbs.		Fire Clay - - - - -	
10 Pc.	2x4-12	Gables - - - - -	80	52 Lin.Ft. 8x12"		Fluc Lining - - - - -	
6 Pc.	2x6-6	Window Lintles - - - - -	36	15 Sq.Ft. 1/2"		Wire Mesh For Hearth Reinforcing - - - - -	
38 Pc.	2x4-8	Dormers - - - - -	203	1		Damper - - - - -	
8 Pc.	2x4-6	Dormers - - - - -	32	1		Ash Dump - - - - -	
Inside Studs				1		Cleanout Door - - - - -	
35 Pc.	2x4-8	First Floor - - - - -	187	1 4x4x1/4"		Angle Iron 3'8" Long - - - - -	
3 Pc.	2x6-8	First Floor - - - - -	24	Plastering			
60 Pc.	2x4-8	Second Floor - - - - -	320	460 Yds.		Plaster, Including Plaster Base, Nails, Metal Lath Corner Strips, and Metal Corner Beads - - - - -	
6 Pc.	2x6-8	Second Floor - - - - -	48	12 Yds.		Cement Plaster, Including Metal Lath & Staples For Over Boiler Space - - - - -	
16 Pc.	2x4-10	Second Floor (Cut) - - - - -	107	MILLWORK			
Stud and Partition Plates				Outside Millwork and Mouldings			
32 Pc.	2x4-14	Outside Walls - - - - -	299	225 Lin.Ft.		Bed Moulding - - - - -	
33 Pc.	2x4-12	Inside Partitions - - - - -	264	70 Lin.Ft.		Cove Moulding - - - - -	
3 Pc.	2x6-6	Inside Partitions - - - - -	18	40 Lin.Ft.		1/4 Round Moulding - - - - -	
3 Pc.	2x4-10	Porch Plates & Blocking - - - - -	20	1 5-1/2x5-1/2		7/6 Porch Columns - - - - -	
Rafters				2		7/6 - Pilasters - - - - -	
30 Pc.	2x6-20	Main Building - - - - -	600	1		Flower Box, See Plan - - - - -	
8 Pc.	2x6-16	Main Building & Porch - - - - -	128	2		Flower Box Brackets, See Plan - - - - -	
9 Pc.	2x6-8	Main Building (Cut) - - - - -	72	Outside Door Frames			
3 Pc.	1x6-8	Collar Beams - - - - -	12	1 3/0x6/8x1-3/4		Front Door Frame D.C. - - - - -	
19 Pc.	2x6-14	Dormers - - - - -	266	1 2/8x6/8x1-3/4		Rear Door Frame D.C. - - - - -	
5 Pc.	2x4-8	Dormers (Cut) - - - - -	27	1 2/6x6/8x1-3/4		Side Door Frame D.C. - - - - -	
2 Pc.	2x8-18	Valley Rafters - - - - -	48	Window and Sash Frames			
2 Pc.	2x6-6	Valley Rafters - - - - -	12	3 10x12x1-1/8		3 Lt.Cellar Sash Frames Plank - - - - -	
3 Pc.	1x8-14	Ridge Boards - - - - -	28	5 8x12x1-3/8		16 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
1 Pc.	1x6-8	Ridge Boards - - - - -	4	5 8x12x1-3/8		12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
Step and Stair Carriages				3 8x10x1-3/8		12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
2 Pc.	2x10-14	Cellar Stairs - - - - -	47	1 8x10x1-3/8		12 Lt.Ck.Rail Window Frames P&P No Headcasing - - - - -	
2 Pc.	2x10-16	Main Stairs - - - - -	53	2 8x12x1-3/8		12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
Sheathing, Boards, Sub-flooring, Furring, Etc.,				1 32x16x1-3/8		2 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
740 Ft.	1x4	Roof Sheathing S.2.S.4-1/2" O.C. - - - - -	740	Windows and Sash			
550 Ft.	1x6	Roof Sheathing D&M - - - - -	550	3 10x12x1-1/8		3 Lt.Cellar Sash Glz. - - - - -	
1360 Ft.	1x6	Sub-flooring D&M Laid Diagonally - - - - -	1360	5 8x12x1-3/8		16 Lt.Ck.Rail Window Glz. - - - - -	
2200 Ft.	1x8	Box Sheathing O.S.Walls Shiplap - - - - -	2200	7 8x12x1-3/8		12 Lt.Ck.Rail Window Glz. - - - - -	
150 Ft.	1x6	Backing & Furring - - - - -	150	4 8x10x1-3/8		12 Lt.Ck.Rail Window Glz. - - - - -	
8 Pc.	1x2-8	Furring Inside Walls (Chimney Breast) - - - - -	11	1 32x16x1-3/8		2 Lt.Ck.Rail Window Glz. Div. 6 Lts. - - - - -	
900 Lin.Ft. 1x1		Ground (Around Inside Openings) - - - - -	75	Blinds			
114 Ft.	1x4	Bridging - - - - -	114	4 Pr.		8x12 - 16 Lt.Window Blinds - - - - -	
75 Ft.	1x2	Floor Stripping 2nd Floor Only - - - - -	75	2 Pr.		8x10 - 12 Lt.Window Blinds - - - - -	
Siding For Outside Walls				3 Pr.		8x12 - 12 Lt.Window Blinds - - - - -	
1900 Ft.	3/4x10"	Rev.Siding 1" Lap - - - - -	1900	Shingles			
Flooring and Ceiling				10 Squares 16"		Shingles For Roof Certigrade Red Cedar 4-1/2" Exposure - - - - -	
530 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor - - - - -	530	Lath			
145 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - - - -	145	50	48"	Exterior Lath For Gable Furring - - - - -	
570 Ft.	3/4x3-1/4	Flooring, Second Floor - - - - -	570				
110 Ft.	1x6	Attic Flooring D&M (Storage Room) - - - - -	110				
150 Ft.	5/8x3-1/4	Ceiling Porches - - - - -	150				

MATERIAL LIST FOR THE MAY 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)					
Doors and Jambs For Main Rooms First Floor			FINISH HARDWARE		
1	3/0x6/8x1-3/4	Front Door Glz. See Plan - - - - -	3		Cellar Sash Sets - - - - -
1	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	4-1/2 Pr.	4x4	Door Butts - - - - -
1	2/6x6/8x1-3/4	French Door Glz. - - - - -	7 Pr.	3-1/2x3-1/2	Door Butts - - - - -
1 Set	7/8x5-5/8	Door Jambs For 2/6x6/8 Door - - - - -	1 Pr.	2-1/2	Cupboard Door Butts, Narrow - - - - -
For Balance - First Floor			1 Pr.	3-1/2x3-1/2	Bathroom Door Butts - - - - -
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow - - - - -
1	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	1		Front Door Lock Set - - - - -
1 Set	7/8x5-5/8	Door Jambs For 2/6x6/8 Door - - - - -	1		Rear Door Lock Set - - - - -
Doors and Jambs For Second Floor			7		Inside Door Lock Sets - - - - -
3	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	1		Bathroom Door Lock Set - - - - -
1	2/2x6/6x1-3/8	Inside Door Panelled - - - - -	1 Single		French Door Lock Set - - - - -
1	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	1 Set	1-3/8"	Floor Double Acting Hinge - - - - -
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	2		Push Plates - - - - -
1	1/4x6/6x1-3/8	Inside Door Panelled - - - - -	16		Sash Locks - - - - -
3 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	32		Sash Lifts - - - - -
4 Sets	7/8x3-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	2		Sash Lifts, Bathroom - - - - -
1 Set	12x16x7/8	Pipe Door, Jambs & Trim - - - - -	1		Sash Lock, Bathroom - - - - -
Interior Finish: Main Rooms, First Floor			1		Cupboard Turn - - - - -
1		Sides of Trim For 3/0x6/8 Door - - - - -	1		Cupboard Turn, Med.Case - - - - -
2		Sides of Trim For 2/6x6/8 Door - - - - -	9		Metal Base Knobs - - - - -
5		Sides of Trim For 8x12 - 16 Lt.Window - - - - -	2 Doz.		Metal Base Knobs, Bathroom - - - - -
2		Sides of Trim For 8x12 - 12 Lt.Window - - - - -	9 Sets		Coat and Hat Hooks - - - - -
115 Lin.Ft.		Base - - - - -	Rough Hardware		
115 Lin.Ft.		Base Shoe - - - - -	4 Hanks		Sash Cord - - - - -
130 Lin.Ft.		Picture Mould - - - - -	22	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
6 Lin.Ft.		Thresholds - - - - -	4 Sets	6"	C.I.Post Caps & Sockets With Lag Screws - - - - -
Interior Finish: Balance of Rooms, First Floor			425 Lbs.		Sash Weights - - - - -
1		Sides of Trim For 2/8x6/8 Door - - - - -	BUILDING PAPER		
2		Sides of Trim For 2/6x6/8 Door - - - - -	6 Rolls	50 Lbs.	Building Paper (500 Ft.Rolls) - - - - -
1		Sides of Trim For 2/6x6/8 Cellar Door - - - - -	SHEET METAL MATERIAL		
1		Sides of Trim For 8x10 - 12 Lt.Window - - - - -	320 Sq.Ft.		Metal Roofing - - - - -
1		Sides of Trim For 32x16 - 2 Lt.Window - - - - -	100 Lin.Ft.	14"	Valley Tin Flashing - - - - -
45 Lin.Ft.		Base - - - - -	180 Pc.	10x12	Tin Shingles - - - - -
45 Lin.Ft.		Base Shoe - - - - -	60 Lin.Ft.	5"	Gutter Eaves Trough - - - - -
45 Lin.Ft.		Chair Rail - - - - -	18	5"	Hangers - - - - -
1 Pc.	3/0	Thresholds - - - - -	1	5"	I.S.Mitres - - - - -
Interior Finish: Second Floor			10	5"	End Caps - - - - -
5		Sides of Trim For 2/6x6/6 Doors - - - - -	6	5x3"	Drop Outlets - - - - -
2		Sides of Trim For 2/2x6/6 Doors - - - - -	60 Lin.Ft.	3"	Conductor Pipe - - - - -
1		Sides of Trim For 2/0x6/6 Doors - - - - -	12	3"	Elbows - - - - -
1		Sides of Trim For 1/4x6/6 Doors - - - - -	18	3"	Conductor Pipe, Hooks - - - - -
1		Sides of Trim For 2/4x6/6 Doors - - - - -	6	3"	Strainers - - - - -
1		Sides of Trim For 2/6x6/6 Closet Doors - - - - -	1		Conductor Heads, See Plan - - - - -
5		Sides of Trim For 2/0x6/6 Closet Doors - - - - -	16 Lin.Ft.		Vents For Gas Flue - - - - -
2		Sides of Trim For 8x12 - 12 Lt.Windows - - - - -	NAILS		
1		Sides of Trim For 8x10 - 12 Lt.Windows - - - - -	80 Lbs.	20d	Common Nails - - - - -
1		Sides of Trim For 1/4x6/6 Closet Doors - - - - -	80 Lbs.	16d	Common Nails - - - - -
4 Lin.Ft.		Window Stool (Storage Room) - - - - -	30 Lbs.	10d	Common Nails - - - - -
16 Lin.Ft.		Window Stop (Storage Room) - - - - -	165 Lbs.	8d	Common Nails - - - - -
150 Lin.Ft.		Base - - - - -	15 Lbs.	6d	Common Nails - - - - -
210 Lin.Ft.		Base Shoe - - - - -	5 Lbs.	10d	Casing Nails - - - - -
55 Lin.Ft.		Closet Base - - - - -	45 Lbs.	8d	Casing Nails - - - - -
120 Lin.Ft.		Picture Mould - - - - -	15 Lbs.	6d	Casing Nails - - - - -
26 Lin.Ft.		Chair Rail - - - - -	5 Lbs.	10d	Finish Nails - - - - -
42 Lin.Ft.		Hook Strips - - - - -	15 Lbs.	8d	Finish Nails - - - - -
30 Lin.Ft.		Shelf Cleats - - - - -	5 Lbs.	6d	Finish Nails - - - - -
Main Stair			2 Lbs.	4d	Finish Nails - - - - -
1		Starting Newel - - - - -	1 Lb.	7/8"	Finish Brads (16 Gauge) - - - - -
1		Circle End Tread & Riser - - - - -	50 Lbs.	3d	Shingle Nails Hot Dipped Zinc Coated - - - - -
13		Treads - - - - -	55 Lbs.	8d	Cement Coated Nails For Siding - - - - -
14		Risers - - - - -	2 Lbs.	3d	Fine Lath Nails - - - - -
2		Landing Treads - - - - -	2 Lbs.	20d	Cut Nails For Furring - - - - -
10 Lin.Ft.		Rail - - - - -	PAINT		
28	32"	Balusters - - - - -	9 Gals.		Outside Body Paint - - - - -
8 Lin.Ft.		Nosing - - - - -	3 Gals.		Outside Trim Paint - - - - -
60 Lin.Ft.		Cove - - - - -	1 Gals.		Porch Ceiling Paint - - - - -
10 Lin.Ft.		Face Mould - - - - -	1 Gals.		Blind or Shutter Paint - - - - -
18 Lin.Ft.		Wall String (2 Mem.) - - - - -	1 Gals.		Sheet Metal Paint (Mineral) - - - - -
10 Lin.Ft.		Face String - - - - -	5 Gals.		Inside Varnish - - - - -
1 Pc.		Stair Part.Jamb - - - - -	5 Gals.		Floor Varnish - - - - -
2 Pc.		Stair Part.Casing - - - - -	1/2 Gals.		Spar Varnish - - - - -
Miscellaneous			1/4 Gals.		Shellac - - - - -
60 Lin.Ft.		Stair Cove Moulding - - - - -	2-1/2 Gals.		Liquid Wood Filler - - - - -
Cabinets			1/2 Gals.		Flat White - - - - -
1		Mantel Shelf & Brackets, See Plan - - - - -	3/4 Gals.		White Enamel - - - - -
1		Medicine Cabinet - - - - -	2 Gals.		Boiled Linseed Oil - - - - -
1		Kitchen Cabinet Over Ref.Space With Hdwe. See Plan - - - - -	2 Gals.		Turpentine - - - - -
1		Combination Kitchen Cabinet and Worktable Complete with Hdwe.,See Plan - - - - -	25 Lbs.		Putty - - - - -
1		Broom Closet, Complete With Hdwe., - - - - -			

MATERIAL LIST FOR THE JUNE 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
8 Pc.	2x6-16	Main Building Wall Plates - - - - -	128	96 Ft.	1x6	Facias & Frieze - - - - -	96
4 Pc.	2x6-14	Main Building Wall Plates - - - - -	56	36 Ft.	1x6	Plancier - - - - -	36
6 Pc.	2x6-10	Main Building Wall Plates - - - - -	60	160 Lin.Ft.	1x2	Porch Trellis - - - - -	27
3 Pc.	2x10-16	Main Building Box Sills - - - - -	80	25 Ft.	1x10	Porch Lintle Frieze - - - - -	25
1 Pc.	2x10-14	Main Building Box Sills - - - - -	23	15 Ft.	1x6	Porch Lintle Frieze - - - - -	15
Girders and Lintles				10 Ft.	1x4	Porch Lintle Soffit - - - - -	10
2 Pc.	6x8-16	Main Building - - - - -	128	20 Ft.1x4 to 1x10		Miscellaneous O.S.Finish - - - - -	20
1 Pc.	6x8-14	Main Building - - - - -	56	Inside Finish Lumber			
2 Pc.	2x8-12	Front Porch Roof Beam - - - - -	32	3 Pc.	1x12-10	Shelving - - - - -	30
4 Pc.	2x8-8	Front Porch Roof Beam - - - - -	43	3 Pc.1-1/4x10-14		Cellar Stair Treads - - - - -	45
Girder Posts				3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
4 Pc.	6x6-7	Main Building - - - - -	84	2 Pc.	2x4-12	Cellar Stair Rails - - - - -	16
2 Pc.	4x4-14	Stair Posts - - - - -	37	3 Pc.1-1/4x10-16		Attic Stair Treads - - - - -	50
Floor Joists, Headers and Trimmers				3 Pc.	1x8-16	Attic Stair Risers - - - - -	32
14 Pc.	2x10-18	First Floor Main Building - - - - -	420	2 Pc.1-1/4x10-16		Attic Stair Wall Strings - - - - -	33
18 Pc.	2x10-14	First Floor Main Building - - - - -	420	2 Pc.	2x4-14	Attic Stair Rails - - - - -	19
24 Pc.	2x10-12	First Floor Main Building - - - - -	480	2 Pc.	2x4-10	Attic Stair Rails - - - - -	13
1 Pc.	2x10-8	First Floor Main Building - - - - -	13	1 Pc.	4x4-12	Attic Stair Rail Posts - - - - -	16
Ceiling Joists				INSULATION			
10 Pc.	2x8-20	Main Building - - - - -	267	1800 Sq.Ft.		Insulating Material - - - - -	
21 Pc.	2x8-14	Main Building - - - - -	392	MASONRY MATERIAL			
14 Pc.	2x8-12	Main Building - - - - -	224	Concrete Foundation 1-3-5 Mixture - 920 Cu.Ft.			
4 Pc.	2x8-9	Main Building - - - - -	48	27 Cu.Yds.		Crushed Stone or Gravel - - - - -	
2 Pc.	2x8-8	Main Building - - - - -	21	16-1/2 Cu.Yds.		Coarse Sand - - - - -	
2 Pc.	2x6-14	Bay - - - - -	28	38-1/2 Bbls.		Portland Cement - - - - -	
7 Pc.	2x4-8	Front Porch - - - - -	37	Cement Floor and Steps 4" One Course - 900 Sq.Ft.			
Outside Studs				9 Cu.Yds.		Crushed Stone or Gravel - - - - -	
140 Pc.	2x4-8	Main Building - - - - -	747	6 Cu.Yds.		Coarse Sand - - - - -	
30 Pc.	2x4-9	Gables (Some Cut) - - - - -	180	13 Bbls.		Portland Cement - - - - -	
1 Pc.	2x4-16	Porch Gables - - - - -	11	Chimneys and Fireplace			
3 Pc.	2x8-9	Beams For Bay - - - - -	36	4200		Common Brick - - - - -	
6 Pc.	2x6-10	Lintles - - - - -	60	50		Faces Brick Fireplace - - - - -	
Inside Studs				120		Fire Clay Brick Fireplace - - - - -	
102 Pc.	2x4-8	First Floor - - - - -	544	4-1/2 Cu.Yds.		Sand - - - - -	
5 Pc.	2x6-8	First Floor - - - - -	40	4-1/2 Bbls.		Lime - - - - -	
Stud and Partition Plates				1 Bbl.		Portland Cement - - - - -	
32 Pc.	2x4-14	Outside Walls - - - - -	299	40 Lbs.		Fire Clay - - - - -	
28 Pc.	2x4-12	Inside Partitions - - - - -	224	44 Ft. 8x12"		Flue Lining - - - - -	
1 Pc.	2x6-16	Inside Partitions - - - - -	16	1		Damper - - - - -	
Rafters				1		Ash Dump - - - - -	
42 Pc.	2x6-16	Main Building - - - - -	756	1		Cleanout Door - - - - -	
8 Pc.	2x6-12	Main Building - - - - -	96	1		Angle Iron 4/0 Long - - - - -	
10 Pc.	1x6-6	Collar Beams - - - - -	30	12 Sq.Ft. 1/2"		Wire Mesh Reinforcing For Hearth - - - - -	
10 Pc.	1x8-10	Bays (Cut to Curvs) - - - - -	67	Plastering			
7 Pc.	2x4-9	Front Porch - - - - -	42	380 Yds.		Plastering, Including Base, Nails, Metal Lath	
17 Pc.	2x4-12	Knee Braces - - - - -	136	12 Yds.		Corner Strips, and Metal Corner Beads - -	
2 Pc.	2x3-14	Valley Rafters - - - - -	37			Cement Plaster On Metal Lath Over Boiler - -	
1 Pc.	1x8-16	Ridge Boards - - - - -	11	MILLWORK			
1 Pc.	1x8-14	Ridge Boards - - - - -	9	Outside Millwork and Mouldings			
1 Pc.	1x8-12	Ridge Boards - - - - -	8	210 Lin.Ft.		Bed Moulding - - - - -	
Step and Stair Carriages				44 Lin.Ft.		Cove Moulding - - - - -	
2 Pc.	2x10-14	Cellar Stairs - - - - -	47	20 Lin.Ft.		1/4 Round Moulding - - - - -	
1 Pc.	2x6-16	Stairs Platform - - - - -	16	20 Lin.Ft.		Drip Cap - - - - -	
2 Pc.	2x10-16	Attic Stairs - - - - -	53	20 Lin.Ft.		Porch Rail Top - - - - -	
Sheathing, Boards, Sub-flooring, Furring, Etc.,				20 Lin.Ft.		Porch Rail Bottom - - - - -	
1170 Ft.	1x4	Roof Sheathing S.2.S.Laid 4-1/2" O.C. 1170		118 Lin.Ft. 1-3/8"		Baluster Stock Square - - - - -	
185 Ft.	1x6	Roof Sheathing D&M - - - - -	185	8 5-1/2x5-1/2 7/3		Porch Columns Squares See Plan - - - - -	
1025 Ft.	1x6	Sub-flooring D&M Laid Diagonally - - - - -	1025	2 2-3/4x5-1/2 7/3		Pilasters Square See Plan - - - - -	
1770 Ft.	1x8	Box Sheathing O.S.Walls Shiplap - - - - -	1770	1		Front Entrance & Frame For 3/0x6/8x1-3/4 Door	
		Laid Diagonally - - - - -				See Plan - - - - -	
80 Ft.	1x6	Backing & Furring - - - - -	80	Outside Door Frames			
8 Pc.	1x2-8	Furring Inside Walls - - - - -	11	1 Mull		Door & Window Frame 2/8x6/8x1-3/4 Door and	
850 Lin.Ft. 1x1		Ground (Around Inside Openings) - - - - -	71			36x18 -1-3/8" 2 Lt.Windows See Plan - - - - -	
90 Ft.	1x4	Bridging - - - - -	90	1 2/6x6/8x1-3/4		French Door Frame D.C. - - - - -	
Siding For Outside Walls				Window and Sash Frames			
1660 Ft. 3/4x10"		Bev.Siding - - - - -	1660	6 10x16x1-1/8		3 Lt.Cellar Sash Frames Plank - - - - -	
Flooring and Ceiling				2 10x12x1-3/8		12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
380 Ft. 3/4x3-1/4		Flooring, Main Rooms First Floor Living		4 8x12x1-3/8		12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
		Room and Dinette - - - - -	380	3 8x10x1-3/8		12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
530 Ft. 3/4x3-1/4		Flooring, Balance First Floor - - - - -	530	1 Triple		Bay Window Frame 8x12x1-3/8 12 Lt.Ck.Rl.	
610 Ft. 1x6		Attic Flooring (Space 29'0"x17'0") - - - - -	610			See Plan - - - - -	
120 Ft. 5/8x3-1/4		Ceiling Porches 8/0 Long - - - - -	120	Windows and Sash			
Shingles				6 10x16x1-1/8		3 Lt.Cellar Sash Glz. - - - - -	
13-1/2 Squares 16"		Shingles For Roof Certigrade Red Cedar		2 10x12x1-3/8		12 Lt.Ck.Rail Window Glz. - - - - -	
		4-1/2" Exp. - - - - -		7 8x12x1-3/8		12 Lt.Ck.Rail Window Glz. - - - - -	
				3 8x10x1-3/8		12 Lt.Ck.Rail Window Glz. - - - - -	
				1 36x18x1-3/8		2 Lt.Ck.Rail Window Glz. Div. 8 Lts. - - - - -	
Blinds				Doors and Jambs For Main Rooms First Floor			
2 Pr.		Blinds For 10x12 - 12 Lt.Windows - - - - -		1 3/0x6/8x1-3/4		Front Door Panelled - - - - -	
2 Pr.		Blinds For 8x12 - 12 Lt.Windows - - - - -		1 2/6x6/8x1-3/8		Inside Door Panelled - - - - -	
3 Pr.		Blinds For 8x10 - 12 Lt.Windows - - - - -		1 2/6x6/8x1-3/4		French Door Glz. 12 Lts. - - - - -	
Doors and Jambs For Main Rooms First Floor				1 Set 7/8x5-5/8		Door Jambs For 2/6x6/8 Door - - - - -	
1 3/0x6/8x1-3/4		Front Door Panelled - - - - -		1 Set 7/8x5-5/8		C.O.Jambs For 2/6x6/8 Opg. - - - - -	
1 2/6x6/8x1-3/8		Inside Door Panelled - - - - -		1 Set 7/8x5-5/8		C.O.Jambs For 4/0x6/8 Opg. - - - - -	
1 2/6x6/8x1-3/4		French Door Glz. 12 Lts. - - - - -					
1 Set 7/8x5-5/8		Door Jambs For 2/6x6/8 Door - - - - -					
1 Set 7/8x5-5/8		C.O.Jambs For 2/6x6/8 Opg. - - - - -					
1 Set 7/8x5-5/8		C.O.Jambs For 4/0x6/8 Opg. - - - - -					

MATERIAL LIST FOR THE JUNE 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			HARDWARE (CONTINUED)		
For Balance - First Floor					
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	24		Sash Lifts - - - - -
3	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	2		Sash Lifts, Bathroom - - - - -
2	2/4x6/8x1-3/8	Inside Door Panelled - - - - -	1		Sash Lock, Bathroom - - - - -
2	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	1		Cupboard Turn - - - - -
1	1/4x6/8x1-3/8	Inside Door Panelled - - - - -	1		Cupboard Turn, Med. Case - - - - -
6	Sets 7/8x5-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	10		Metal Base Knobs - - - - -
2	Sets 7/8x3-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	1		Metal Base Knob, Bathroom - - - - -
1	12x16x7/8	Pipe Door, Jamb & Trim - - - - -	3	Doz.	Coat and Hat Hooks - - - - -
			7	Sets	Window Blind Hangers With Fastners - - - - -
Interior Finish: Main Rooms, First Floor					
1		Sides of Trim For 3/0x6/8 Door - - - - -	Rough Hardware		
2		Sides of Trim For 2/6x6/8 Door - - - - -	3	Hanks	Sash Cord - - - - -
1		Sides of Trim For 2/6x6/8 C.O. - - - - -	32	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
2		Sides of Trim For 4/0x6/8 C.O. - - - - -	4	Sets	Post Caps & Bases - - - - -
1		Sides of Trim For 10x12 - 12 Lt. Windows - - - - -	312	Lbs.	Sash Weights - - - - -
1		Sides of Trim For 8x12 - 12 Lt. Windows - - - - -			
1		Sides of Trim For Triple Bay Window See Plan - - - - -			
94	Lin.Ft.	Base - - - - -			
94	Lin.Ft.	Base Shoe - - - - -			
110	Lin.Ft.	Picture Mould - - - - -	5	Rolls 50#	BUILDING PAPER
6	Lin.Ft.	Thresholds - - - - -			Building Paper (500 Ft. Rolls) For Walls and Floors - - - - -
Interior Finish: Balance of Rooms, First Floor					
6		Sides of Trim For 2/6x6/8 Doors - - - - -	180	Ft.	SHEET METAL MATERIAL
3		Sides of Trim For 2/4x6/8 Doors - - - - -	75	Ft. 14"	Metal Roofing with Nails - - - - -
2		Sides of Trim For 2/0x6/8 Doors - - - - -	70	Ft.	Valley Tin - - - - -
1		Sides of Trim For 1/4x6/8 Doors - - - - -	2	Doz.	Gutter Crown Mould - - - - -
1		Sides of Trim For 2/6x6/8 Cellar Stair Door - - - - -	1		Hangers - - - - -
1		Sides of Trim For 2/4x6/8 Attic Stair Door - - - - -	10		I.S. Mitres - - - - -
2		Sides of Trim For 2/0x6/8 Closet Stair Door - - - - -	5		End Caps - - - - -
1		Sides of Trim For 1/4x6/8 Closet Stair Door - - - - -	50	Ft. 3"	Drop Outlets - - - - -
1		Sides of Trim For Mull Door & Window See Plan - - - - -	10		Conductor Pipes - - - - -
1		Sides of Trim For 10x12 - 12 Lt. Window - - - - -	15		Elbows - - - - -
1		Sides of Trim For 8x10 - 12 Lt. Window - - - - -	5		Conductor Pipe, Hooks - - - - -
3		Sides of Trim For 8x12 - 12 Lt. Window - - - - -	12	Ft.	Strainers - - - - -
1		Sides of Trim For 2/6x6/8 C.O. - - - - -			Vents For Gas Flue - - - - -
1		Sides of Trim For 2/8x6/8 Door - - - - -			
6	Lin.Ft.	Window Stool Attic - - - - -	75	Lbs. 20d	Common Nails - - - - -
6	Lin.Ft.	Window Apron Attic - - - - -	30	Lbs. 16d	Common Nails - - - - -
36	Lin.Ft.	Window Stop Attic - - - - -	75	Lbs. 10d	Common Nails - - - - -
160	Lin.Ft.	Base - - - - -	140	Lbs. 8d	Common Nails - - - - -
186	Lin.Ft.	Base Shoe - - - - -	5	Lbs. 6d	Common Nails - - - - -
94	Lin.Ft.	Picture Mould - - - - -	5	Lbs. 10d	Casing Nails - - - - -
62	Lin.Ft.	Chair Rail - - - - -	30	Lbs. 8d	Casing Nails - - - - -
26	Lin.Ft.	Hook Strips - - - - -	5	Lbs. 6d	Casing Nails - - - - -
3	Lin.Ft.	Thresholds - - - - -	5	Lbs. 10d	Finish Nails - - - - -
26	Lin.Ft.	Closet Base - - - - -	15	Lbs. 8d	Finish Nails - - - - -
Miscellaneous			5	Lbs. 6d	Finish Nails - - - - -
60	Lin.Ft.	Stair Cove Moulding - - - - -	2	Lbs. 4d	Finish Nails - - - - -
3	Pc. 3/0	Landing Treads - - - - -	1	Lb. Box 7/8"	Finish Brads (16 Gauge) - - - - -
Cabinets			60	Lbs. 3d	Shingle Nails Hot Dipped Zinc Coated - - - - -
1		Mantel Shelf & Trim See Plan - - - - -	50	Lbs. 8d	Coated Nails For Siding - - - - -
1		Medicine Cabinet - - - - -	5	Lbs. 20d	Cut Nails - - - - -
1		Kitchen Cabinet Above Sink & Ref. Complete With Hdwe., See Plan - - - - -			
1		Kitchen Worktable Complete with Hdwe. See Plan - - - - -			
FINISH HARDWARE			PAINT		
6		Cellar Sash Sets - - - - -	6	Gals.	Outside Body Paint - - - - -
4-1/2	Pr. 4x4	Door Butts - - - - -	2-1/2	Gals.	Outside Trim Paint - - - - -
7	Pr. 3-1/2x3-1/2	Door Butts - - - - -	1/2	Gals.	Porch Ceiling Paint - - - - -
1	Pr. 2-1/2	Cupboard Door Butts, Narrow - - - - -	1	Gals.	Blind or Shutter Paint - - - - -
1	Pr. 3-1/2x3-1/2	Bathroom Door Butts - - - - -	1	Gals.	Sheet Metal Paint (Mineral) - - - - -
1	Pr. 2-1/2	Medicine Cabinet Butts, Narrow - - - - -	1/2	Gals.	Paint For Brickwork Undercoat - - - - -
1		Front Door Lock Set - - - - -	1/2	Gals.	Paint For Brick Work - - - - -
1		Rear Door Lock Set - - - - -	3-1/2	Gals.	Inside Varnish - - - - -
7		Inside Door Lock Sets - - - - -	3-1/2	Gals.	Floor Varnish - - - - -
1		Bathroom Door Lock Set - - - - -	1/2	Gals.	Spar Varnish - - - - -
1	Single	French Door Lock Set - - - - -	1/4	Gals.	Shellac - - - - -
1	Set	Floor Double Acting Hinge - - - - -	2	Gals.	Liquid Wood Filler - - - - -
2		Push Plates - - - - -	1	Gals.	Flat White - - - - -
12		Sash Locks - - - - -	1/2	Gals.	White Enamsl - - - - -
			2	Gals.	Boiled Linseed Oil - - - - -
			2	Gals.	Turpentine - - - - -
			25	Lbs.	Putty - - - - -

MATERIAL LIST FOR THE JUNE 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION
LUMBER				INSULATION		
Wall Plates or Sills for Foundation				1800 Ft.		Insulating Material - - - - -
8 Pc.	2x6-16	Main Building Wall Plates - - - - -	128			
4 Pc.	2x6-14	Main Building Wall Plates - - - - -	56			
6 Pc.	2x6-10	Main Building Wall Plates - - - - -	60			
3 Pc.	2x10-16	Main Building Box Sills - - - - -	80			
1 Pc.	2x10-14	Main Building Box Sills - - - - -	23			
Girders and Lintles				MASONRY MATERIAL		
2 Pc.	6x8-16	Main Building - - - - -	128	Concrete Foundation	1-3-5 Mixture - 950 Cu.Ft.	
1 Pc.	6x8-14	Main Building - - - - -	56	28 Cu.Yds.	Crushed Stone or Gravel - - - - -	
2 Pc.	2x8-12	Front Porch Roof Beam - - - - -	32	17 Cu.Yds.	Coarse Sand - - - - -	
4 Pc.	2x8-8	Front Porch Roof Beam - - - - -	43	49-1/2 Bbls.	Portland Cement - - - - -	
Girder Posts				Cement Floor and Steps	4" One Course - 900 Sq.Ft.	
4 Pc.	6x6-7	Main Building - - - - -	84	9 Cu.Yds.	Crushed Stone or Gravel - - - - -	
2 Pc.	4x4-14	Stair Posts - - - - -	37	6 Cu.Yds.	Coarse Sand - - - - -	
Floor Joists, Headers and Trimmers				13 Bbls.	Portland Cement - - - - -	
14 Pc.	2x10-18	First Floor Main Building - - - - -	420	Chimneys and Fireplace		
18 Pc.	2x10-14	First Floor Main Building - - - - -	420	3500	Common Brick - - - - -	
24 Pc.	2x10-12	First Floor Main Building - - - - -	480	50	Face Brick - - - - -	
1 Pc.	2x10-8	First Floor Main Building - - - - -	13	120	Fire Clay Brick - - - - -	
Ceiling Joists				4 Cu.Yds.	Sand - - - - -	
10 Pc.	2x6-20	Main Building - - - - -	200	4 Bbls.	Lime - - - - -	
3 Pc.	2x6-16	Main Building - - - - -	48	1 Bbl.	Portland Cement - - - - -	
28 Pc.	2x6-14	Main Building - - - - -	392	40 Lbs.	Fire Clay - - - - -	
11 Pc.	2x6-12	Main Building - - - - -	132	30 Ft. 8x12"	Flue Lining - - - - -	
2 Pc.	2x6-8	Main Building - - - - -	16	1	Damper - - - - -	
7 Pc.	2x4-8	Porch - - - - -	37	1	Ash Dump - - - - -	
2 Pc.	2x6-14	Bay - - - - -	28	1	Cleanout Door - - - - -	
Outside Studs				1	Angle Iron 3/10 Long - - - - -	
140 Pc.	2x4-10	Main Building - - - - -	933	12 Sq.Ft. 1/2"	Wire Mesh Reinforcing For Hearth - - - - -	
4 Pc.	2x4-12	Porch Bulkhead Rail - - - - -	32	Plastering		
4 Pc.	2x4-12	Above Porch Beams - - - - -	32	380 Yds.	Plastering, Including Base, Nails, Metal Lath	
14 Pc.	2x4-8	Porch Column Cores - - - - -	75	12 Yds.	Corner Strips, and Metal Corner Beads - - - - -	
Inside Studs					Cement Plaster On Metal Lath Over Boiler - - - - -	
102 Pc.	2x4-8	First Floor - - - - -	544	MILLWORK		
5 Pc.	2x6-8	First Floor - - - - -	40	Outside Millwork and Mouldings		
Stud and Partition Plates				50 Lin.Ft.	Cove Moulding - - - - -	
32 Pc.	2x4-14	Outside Walls - - - - -	299	110 Lin.Ft.	1/4 Round Moulding - - - - -	
28 Pc.	2x4-12	Inside Partitions - - - - -	224	2	Hood Brackets - - - - -	
1 Pc.	2x6-16	Inside Partitions - - - - -	16	1	Flower Box - - - - -	
2 Pc.	2x4-16	Roof Joist Supports - - - - -	21	Outside Door Frames		
2 Pc.	2x4-14	Roof Joist Supports - - - - -	19	1 3/0x6/8x1-3/4	Front Door Frame D.C. - - - - -	
5 Pc.	2x4-12	Roof Joist Supports - - - - -	40	1 Mull	Door & Window Frame 2/8x6/8x1-3/4 Door and	
Rafters					36x18 - 1-3/8" 2 Lt.Window, See Plan - - - - -	
27 Pc.	2x8-14	Main Building Roof Joists - - - - -	504	1 2/6x6/8x1-3/4	French Door Frame D.C. - - - - -	
13 Pc.	2x8-16	Main Building Roof Joists - - - - -	277	Window and Sash Frames		
24 Pc.	2x4-12	Cant Strips - - - - -	192	6 10x16x1-1/8	3 Lt.Cellar Sash Frames Plank - - - - -	
7 Pc.	2x4-9	Front Porch - - - - -	42	4 8x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
3 Pc.	2x4-12	Front Hood Rafters, Etc., - - - - -	24	1 8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
Step and Stair Carriages				1 Triple	Bay Window Frame 8x12x1-3/8 - 12 Lt.Ck.Rail	
2 Pc.	2x10-14	Cellar Stairs - - - - -	47		See Plan - - - - -	
1 Pc.	2x6-16	Stairs Platform - - - - -	16	2 Triple 2/0x4/10x1-3/8 (Opg.Size) Sash Frames - - - - -		
Sheathing, Boards, Sub-flooring, Furring, Etc.,				Windows and Sash		
1100 Ft.	1x6	Roof Shsathing D&M - - - - -	1100	6 10x16x1-1/8	3 Lt.Cellar Sash Glz. - - - - -	
1030 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally - - - - -	1030	7 8x12x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
1800 Ft.	1x8	Box Sheathing O.S.Walls Shiplap		1 8x10x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
		Laid Diagonally - - - - -	1800	1 36x18x1-3/8	2 Lt.Ck.Rail Window Glz. Div. 8 Lts. - - - - -	
170 Ft.	1x6	Ribbons, Backing & Furring - - - - -	170	6 2/0x4/10x1-3/8	(Opg.Size) Sash Glz. See Plan - - - - -	
8 Pc.	1x2-8	Furring Inside Walls - - - - -	11	Doors and Jambs For Main Rooms First Floor		
850 Lin.Ft.	1x1	Ground (Around Inside Openings) - - - - -	71	1 3/0x6/8x1-3/4	Front Door Glz. See Plan - - - - -	
90 Ft.	1x4	Bridging - - - - -	90	1 2/6x6/8x1-3/8	Inside Door Panelled - - - - -	
Siding For Outside Walls				1 2/6x6/8x1-3/4	French Door Glz. 12 Lts. - - - - -	
900 Ft.	1x8	Shiplap Siding - - - - -	900	1 Set 7/8x5-5/8	Door Jambs For 2/6x6/8 Door - - - - -	
880 Ft.	1x6	Drop Siding - - - - -	880	1 Set 7/8x5-5/8	C.O.Jambs For 2/6x6/8 Opg. - - - - -	
Flooring and Ceiling				1 Set 7/8x5-5/3	C.O.Jambs For 4/0x6/8 Opg. - - - - -	
380 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor		For Balance - First Floor		
		Living Room & Dinette - - - - -	380	1 2/8x6/8x1-3/4	Rear Door Glz. - - - - -	
530 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - - - -	530	3 2/6x6/8x1-3/8	Inside Door Panelled - - - - -	
120 Ft.	5/8x3-1/4	Ceiling Porches - - - - -	120	2 2/4x6/8x1-3/8	Inside Door Panelled - - - - -	
Outside Finish Lumber				2 2/0x6/8x1-3/8	Inside Door Panelled - - - - -	
90 Ft.	1x6	Facias - - - - -	90	1 1/4x6/8x1-3/8	Inside Door Panelled - - - - -	
290 Ft.	3x6	Coping - - - - -	290	6 Sets 7/8x5-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	
5 Pc.	1x2-12	Corner Boards - - - - -	10	2 Sets 7/8x3-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	
5 Pc.	1x3-12	Corner Boards - - - - -	15	1 12x16x7/8	Pipe Door, Jamb & Trim - - - - -	
1 Pc.	2x8-14	Bulkhead Rails - - - - -	19	Interior Finish: Main Rooms, First Floor		
1 Pc.	2x8-12	Bulkhead Rails - - - - -	16	1	Sides of Trim For 3/0x6/8 Door - - - - -	
1 Pc.	2x4-12	Porch Lintle Soffit - - - - -	8	2	Sides of Trim For 2/6x6/8 Door - - - - -	
2 Pc.	2x4-8	Porch Lintls Soffit - - - - -	11	1	Sides of Trim For 2/6x6/8 C.O. - - - - -	
20 Ft.1x4 to 1x10		Miscellaneous O.S.Finish - - - - -	20	2	Sides of Trim For 4/0x6/8 C.O. - - - - -	
Inside Finish Lumber				1	Sides of Trim For 8x12 - 12 Lt.Window - - - - -	
3 Pc.	1x12-10	Shelving - - - - -	30	1	Sides of Trim For Triple Bay Window See Plan - - - - -	
3 Pc.1-1/4x10-14		Cellar Stair Treads - - - - -	44	1	Sides of Trim For 2/0x4/10 (Opg.Size) Triple	
3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28		Sash - - - - -	
2 Pc.	2x4-12	Cellar Stair Rails - - - - -	16	94 Lin.Ft.	Base - - - - -	
				94 Lin.Ft.	Base Shoe - - - - -	
				110 Lin.Ft.	Picture Mould - - - - -	
				6 Lin.Ft.	Thresholds - - - - -	

MATERIAL LIST FOR THE JUNE 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			FINISH HARDWARE (CONTINUED)		
Interior Finish: Balance of Rooms First Floor					
6		Sides of Trim For 2/6x6/8 Doors - - - - -	8		Sash Locks - - - - -
3		Sides of Trim For 2/4x6/8 Doors - - - - -	16		Sash Lifts - - - - -
2		Sides of Trim For 2/0x6/8 Doors - - - - -	2		Sash Lifts, Bathroom - - - - -
1		Sides of Trim For 1/4x6/8 Doore - - - - -	1		Sash Lock, Bathroom - - - - -
1		Sides of Trim For 2/6x6/8 Cellar Stair Door -	1		Cupboard Turn - - - - -
1		Sides of Trim For 2/4x6/8 Attic Stair Door -	1		Cupboard Turn, Med.Case - - - - -
2		Sides of Trim For 2/0x6/8 Closet Doors - - -	10		Metal Base Knobs - - - - -
1		Sides of Trim For 1/4x6/8 Closet Doors - - -	1		Metal Base Knob, Bathroom - - - - -
1		Sides of Trim For Mull Door & Window See Plan	3 Doz.		Coat and Hat Hooks - - - - -
1		Sides of Trim For 2/0x4/10 (Opg.Size) Triple Sash -	Rough Hardware		
1		Sides of Trim For 8x10 - 12 Lt.Windows - - -	2 Hanks		Sash Cord - - - - -
3		Sides of Trim For 8x12 - 12 Lt.Windows - - -	32	1/2x16"	Anchor Bolts - - - - -
1		Sides of Trim For 2/6x6/8 C.O. - - - - -	4 Sets		Post Caps & Bases - - - - -
1		Sides of Trim For 2/8x6/8 Door - - - - -	225 Lbs.		Sash Weights - - - - -
160 Lin.Ft.		Base - - - - -			
186 Lin.Ft.		Base Shoe - - - - -	BUILDING PAPER		
94 Lin.Ft.		Picture Mould - - - - -	5 Rolls	50#	Building Paper (500 Ft.Rolls) For Walls and Floors - -
62 Lin.Ft.		Chair Rail - - - - -			
26 Lin.Ft.		Hook Strips - - - - -	SHEET METAL MATERIAL		
3 Lin.Ft.		Thresholds - - - - -	1050 Ft.		Metal Roofing with Nails - - - - -
26 Lin.Ft.		Closet Base - - - - -	40 Ft.	3"	Conductor Pipe - - - - -
			1 Doz.	3"	Conductor Pipe, Hooks - - - - -
			3	3"	Strainere - - - - -
			3		Conductor Heads - - - - -
			8 Ft.		Vents For Gas Flue - - - - -
Miscellaneous					
2 Pc.	3/0	Landing Tread - - - - -			
			NAILS		
			60 Lbs.	20d	Common Nails - - - - -
			30 Lbs.	16d	Common Nails - - - - -
			60 Lbs.	10d	Common Nails - - - - -
			125 Lbs.	8d	Common Nails - - - - -
Cabinets			5 Lbs.	6d	Common Nails - - - - -
1		Mantel Shelf & Trim See Plan - - - - -	5 Lbs.	10d	Casing Nails - - - - -
1		Medicine Cabinet - - - - -	30 Lbs.	8d	Casing Nails - - - - -
1		Kitchen Cabinet Above Sink & Ref. Complete With Hdwe. See Plan -	5 Lbs.	6d	Casing Nails - - - - -
1		Kitchen Worktable Complete with Hdwe.See Plan	5 Lbs.	10d	Finish Nails - - - - -
			15 Lbs.	8d	Finish Nails - - - - -
			5 Lbs.	6d	Finish Nails - - - - -
			2 Lbs.	4d	Finish Nails - - - - -
			1 Lb.	7/8"	Finish Brads (16 Gauge) - - - - -
			55 Lbs.	8d	Box Nails - - - - -
			5 Lbs.	20d	Cut Nails - - - - -
			PAINT		
FINISH HARDWARE			6 Gals.		Outside Body Paint - - - - -
4-1/2 Pr.	4x4	Door Butts - - - - -	2 Gals.		Outside Trim Paint - - - - -
7 Pr.	3-1/2x3-1/2	Door Butts - - - - -	1/2 Gals.		Porch Ceiling Paint - - - - -
6 Pr.	3x3	Casement Sash Butts - - - - -	1-1/2 Gals.		Sheet Metal Paint (Mineral) - - - - -
1 Pr.	2-1/2	Cupboard Door Butts, Narrow - - - - -	1/2 Gals.		Paint For Brick Work Undercoat - - - - -
1 Pr.	3-1/2x3-1/2	Bathroom Door Butte - - - - -	1/2 Gals.		Paint For Brick Work - - - - -
1 Pr.	2-1/2	Medicine Cabinet Butte, Narrow - - - - -	3-1/2 Gals.		Inside Varnish - - - - -
1		Front Door Lock Set - - - - -	3-1/2 Gals.		Floor Varnish - - - - -
1		Rear Door Lock Set - - - - -	1/2 Gals.		Spar Varnish - - - - -
7		Inside Door Lock Sets - - - - -	1/4 Gals.		Shellac - - - - -
1		Bathroom Door Lock Sete - - - - -	2 Gal &		Liquid Wood Filler - - - - -
1 Single		French Door Lock Set - - - - -	1 Gals.		Flat White - - - - -
1 Set	1-3/8"	Floor Double Acting Hinge - - - - -	1/2 Gale.		White Enamel - - - - -
2		Push Plates - - - - -	2 Gals.		Boiled Linseed Oil - - - - -
			2 Gals.		Turpentine - - - - -
			25 Lbs.		Putty - - - - -

MATERIAL LIST FOR THE JULY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION
LUMBER				INSULATION		
Wall Plates or Sills for Foundation				2100 Sq.Ft. Insulating Material		
2 Pc.	2x6-16	Main Building Wall Plates	32	MASONRY MATERIAL		
2 Pc.	2x6-14	Main Building Wall Plates	28	Concrete Foundation 1-3-5 Mixture - 890 Cu.Ft.		
10 Pc.	2x6-12	Main Building Wall Plates	120	26-1/2 Cu.Yds.		Crushed Stone or Gravel
4 Pc.	2x6-9	Main Building Wall Plates	36	16 Cu.Yds.		Coarse Sand
3 Pc.	2x10-18	Main Building Box Sills	90	37-1/4 Bbls.		Portland Cement
Girders and Lintles				Stone Work		
2 Pc.	6x8-16	Main Building	128	300 Sq.Ft. 4"		Flagstone
1 Pc.	6x8-8	Main Building	32	Cement Floor and Steps 1-3-5 Mixture - 886 Sq.Ft.		
2 Pc.	2x8-20	Side Porch Roof Beam	53	9 Cu.Yds.		Crushed Stone or Gravel
4 Pc.	2x8-10	Side Porch Roof Beam	53	6 Cu.Yds.		Coarse Sand
Girder Posts				13-1/2 Bbls.		Portland Cement
4 Pc.	6x6-7	Main Building	84	Chimneys and Fireplace		
Floor Joists, Headers and Trimmers				6700		Common Brick
12 Pc.	2x10-14	First Floor Main Building	280	60		Face Brick For Fireplace
32 Pc.	2x10-12	First Floor Main Building	640	120		Fire Clay Brick
23 Pc.	2x10-10	First Floor Main Building	383	6-1/2 Cu.Yds.		Sand
4 Pc.	1x10-16	Fire Stops	53	6-1/2 Bbls.		Lime
18 Pc.	2x10-16	Second Floor Main Building	480	1 Bbl.		Portland Cement
23 Pc.	2x10-12	Second Floor Main Building	460	50 Lbs.		Fire Clay
15 Pc.	2x10-10	Second Floor Main Building	250	24 Lin.Ft. 12x12"		Flue Lining
Ceiling Joists				30 Lin.Ft. 8x12"		Flue Lining
24 Pc.	2x6-22	Main Building	528	15 Sq.Ft. 1/2"		Wire Mesh Reinforcing For Hearth
16 Pc.	1x4-8	Ceil. Joist Hangers	42	1		Damper
22 Pc.	2x6-10	Side Porch	220	1		Ash Dump
Outside Studs				1		Cleanout Door
90 Pc.	2x4-16	Main Building	960	1	4x4x1/4"	Angle Iron 4 Ft. Long
42 Pc.	2x4-8	Main Building	226	Plastering		
36 Pc.	2x4-6	Main Building	144	580 Yds.		Plastering, Including Plaster Base, Nails, Metal Lath Corner Strips, and Metal Corner Beads
26 Pc.	2x4-8	Gables	138	12 Yds.		Cement Plaster, Including Metal Lath & Staples For Over Boiler Space
10 Pc.	2x4-12	Blocking	80	ORNAMENTAL IRON		
2 Pc.	2x8-8	Door Lintles	21	1		Ornamental Chimney Anchor, See Plan
Inside Studs				MILLWORK		
70 Pc.	2x4-8	First Floor	372	Outside Millwork and Mouldings		
16 Pc.	2x6-8	First Floor	128	130 Lin.Ft.		Crown Moulding
4 Pc.	2x6-6	First Floor C.O. Headers	24	80 Lin.Ft.		Bed Moulding
88 Pc.	2x4-8	Second Floor	469	70 Lin.Ft.		Cove Moulding
14 Pc.	2x6-8	Second Floor	112	30 Lin.Ft.		1/4 Round Moulding
Stud and Partition Plates				45 Lin.Ft.		Band Moulding
36 Pc.	2x4-14	Outside Walls	336	4 Pc. 10"0"		Deck Rail Top
40 Pc.	2x4-12	Inside Partitions	320	4 Pc. 10"0"		Deck Rail Bottom
3 Pc.	2x6-16	Inside Partitions	48	200 Lin.Ft. 1-3/8"		Baluster Stock
3 Pc.	2x6-14	Inside Partitions	42	10 5x5 7/3		Porch Columns See Plan
4 Pc.	2x4-10	Porch Plates	27	2 2-1/2x5 7/3		Pilasters See Plan
Rafters				10 4x4 2/6		Deck Newels See Plan
48 Pc.	2x6-16	Main Building	768	2 2x4 2/6		Deck Pilaster Newels, See Plan
22 Pc.	2x6-12	Deck Joists	264	1		Front Entrance, Triple, Door & Sidelight
2 Pc.	1x8-16	Ridge Boards	21	4		Frame Door 3/0x6/8x1-3/4 Sash 1/2x6/8x1-3/8"
Step and Stair Carriages						O.S., See Plan
2 Pc.	2x10-14	Cellar Stairs	47			Turned Drop Finials, See Plan
2 Pc.	2x10-16	Main Stairs	53	Outside Door Frames		
Sheathing, Boards, Sub-flooring, Furring, Etc.,				2 2/6x6/8x1-3/4		Side Door Frame D.C.
740 Ft.	1x4	Roof Sheathing S.S.Laid 4-1/2" O.C.	740	1 2/8x6/8x1-3/4		Rear Door Frame D.C.
545 Ft.	1x6	Roof Sheathing D&M	545	1 2/6x6/6x1-3/4		Balcony Door Frame D.C.
1760 Ft.	1x6	Sub-flooring D&M Laid Diagonally	1760	Window and Sash Frames		
2350 Ft.	1x8	Box Sheathing O.S.Walls Shiplap Laid Diagonally	2350	4 10x12x1-1/8		3 Lt. Cellar Sash Frames Plank
175 Ft.	1x6	Ribbons, Backing & Furring	175	2 10x12x1-3/8		15 Lt. Ck. Rail Window Frames P&P Spl. Head Trim
14 Pc.	1x2-8	Furring Inside Walls (Chimney)	19	3 9x12x1-3/8		See Plan
1350 Lin.Ft. 1x1		Ground (Around Inside Openings)	112	3 10x10x1-3/8		15 Lt. Ck. Rail Window Frames P&P D.C.
146 Ft.	1x4	Bridging	146	5 10x10x1-3/8		12 Lt. Ck. Rail Window Frames P&P D.C.
15 Ft.	1x4	Lookouts	15	1 30x16x1-3/8		12 Lt. Ck. Rail Window Frames P&P No Headcasing
120 Ft.	1x2	Floor Stripping On 2nd Floor Only	120	1 18x18x1-3/8		2 Lt. Ck. Rail Window Frames P&P D.C.
Siding for Outside Walls				1 1/8x2/6x1-3/8		2 Lt. Ck. Rail Window Frames P&P D.C.
18-1/2 Squares 24"		Wall Shingles Certigrade Red Cedar Stained Laid Double Course 12" Exposure		Windows and Sash		
Flooring and Ceiling				4 10x12x1-1/8		3 Lt. Cellar Sash Glz.
575 Ft. 3/4x3-1/4		Flooring, Main Rooms First Floor	575	3 10x12x1-3/8		15 Lt. Ck. Rail Window Glz.
215 Ft. 3/4x3-1/4		Flooring, Balance First Floor	215	8 10x10x1-3/8		12 Lt. Ck. Rail Window Glz.
835 Ft. 3/4x3-1/4		Flooring, Second Floor	835	3 9x12x1-3/8		12 Lt. Ck. Rail Window Glz.
250 Ft. 5/8x3-1/4		Ceiling Porches	250	1 30x16x1-3/8		2 Lt. Ck. Rail Window Glz. Div. 6 Lt.
Shingles				1 18x18x1-3/8		2 Lt. Ck. Rail Window Glz. Div. 8 Lt.
11 Squares 5/2 16"		Shingles For Roof Certigrade Red Cedar 4-1/2" Exposure		2 1/2x6/8x1-3/8		O.S. Sidelight Sash, Glz. Div. 4 Lt.
Lath				1 1/8x2/6x1-3/8		O.S. Sash Glz. Div. 6 Lt.
50	48"	Exterior Lath For Frieze Furring		Blinds		
Outside Finish Lumber				2 Pr.		Blinds For 10x12 - 15 Lt. Windows
3 Pc.	1x10-10	Plancier Main	25	6 Pr.		Blinds For 10x10 - 12 Lt. Windows
45 Ft.	1x8	Frieze Main	45	3 Pr.		Blinds For 9x12 - 12 Lt. Windows
35 Ft.	1x6	Frieze Gable	35	Doors and Jambs For Main Rooms First Floor		
25 Ft.	1x6	Porch Facia	25	1 3/0x6/8x1-3/4		Front Door Panelled
32 Ft.	1x8	Porch Plancier	32	1 2/6x6/8x1-3/8		Inside Door Panelled
44 Ft.	1x12	Porch Lintle Frieze	44	2 2/6x6/8x1-3/4		French Doors, Glz. 10 Lt.
28 Ft.	1x8	Porch Lintle Frieze	28	1 Set 7/8x5-5/8		Door Jambs For 2/6x6/8 Door
32 Ft.	1x4	Porch Lintle Soffit & Frieze	32	2 Sets 7/8x5-5/8		C.O. Jambs For 4/0x6/8 & Smaller
25 Ft. 1x4 to 1x10		Miscellaneous O.S. Finish	25	1 Set 7/8x7-5/8		C.O. Jambs For 4/0x6/8
Inside Finish Lumber						
6 Pc.	1x12-10	Shelving	60			
3 Pc. 1-1/4x10-14		Cellar Stair Treads	44			
3 Pc.	1x8-14	Cellar Stair Risers	28			
2 Pc.	2x4-12	Cellar Stair Rails & Newels	16			

MATERIAL LIST FOR THE JULY 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)					
For Balance - First Floor			FINISH HARDWARE		
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	4		Cellar Sash Sets - - - - -
2	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	7-1/2 Pr.	4x4	Door Butts - - - - -
2	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	12 Pr.	3-1/2x3-1/2	Door Butts - - - - -
1	1/6x6/8x1-3/8	Inside Door Panelled - - - - -	1 Pr.	3x3	Casement Sash Butts - - - - -
2 Sets	7/8x5-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	2 Pr.	3-1/2x3-1/2	Bathroom & Lav. Door Butts - - - - -
3 Sets	7/8x3-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow - - - - -
Doors and Jambs For Second Floor			1		Front Door Lock Set - - - - -
3	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	1		Rear Door Lock Set - - - - -
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	12		Inside Door Lock Sets - - - - -
5	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	2		Bathroom & Lav. Door Lock Set - - - - -
1	2/6x6/6x1-3/4	French Door Glz. 10 Lts. - - - - -	3 Single		French Door Lock Sets - - - - -
3 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	1 Set	1-3/8"	Floor Double Acting Hinge - - - - -
5 Sets	7/8x3-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	2		Push Plates - - - - -
1 Set	7/8x7-5/8	Door Jambs For 2/6x6/6 Door - - - - -	1 Set		Casement Sash Fasteners, Single - - - - -
1 Set	7/8x5-5/8	Jambs For 3/0x6/6 C.O. - - - - -	14		Sash Locks - - - - -
Interior Finish: Main Rooms, First Floor			28		Sash Lifts - - - - -
3		Sides of Trim For 2/6x6/8 Doors - - - - -	2		Sash Lifts, Bathroom & Lav. - - - - -
4		Sides of Trim For 4/0x6/8 C.O. - - - - -	4		Sash Lock, Bathroom & Lav. - - - - -
1		Sides of Trim For 2/8x6/8 C.O. - - - - -	1		Cupboard Turn, Med. Case - - - - -
1 Triple		Sides of Trim For Door & Sidelights, Door 3/0x6/8, Sash Each Side 1/2x6/8 O.S. - - - - -	15		Metal Base Knobs - - - - -
3		Sides of Trim For 10x12 - 15 Lt. Windows - - - - -	1		Metal Base Knob, Bathroom - - - - -
2		Sides of Trim For 9x12 - 12 Lt. Windows - - - - -	5 Doz.		Coat and Hat Hooks - - - - -
125 Lin.Ft.		Base - - - - -	11 Sets		Window Blinds Hangers With Fasteners - - - - -
125 Lin.Ft.		Base Shoe - - - - -	Rough Hardware		
160 Lin.Ft.		Picture Mould - - - - -	4 Hanks		Sash Cord - - - - -
10 Lin.Ft.		Thresholds - - - - -	24	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
Interior Finish: Balance of Rooms, First Floor			4 Sets	6"	C.I. Post Caps & Sockets With Lag Screws - - - - -
1		Sides of Trim For 2/8x6/8 Door - - - - -	400 Lbs.		Sash Weights - - - - -
4		Sides of Trim For 2/6x6/8 Door - - - - -	BUILDING PAPER		
3		Sides of Trim For 2/0x6/8 Door - - - - -	7 Rolls	50 Lb.	Building Paper For Walls & Floors (500 Ft. Rl.)
1		Sides of Trim For 1/6x6/8 Door - - - - -	SHEET METAL MATERIAL		
1		Sides of Trim For 2/8x6/8 C.O. - - - - -	270 Sq.Ft.		Metal Roofing With Nails - - - - -
1		Sides of Trim For 2/6x6/8 Cellar Door - - - - -	25 Lin.Ft.	14"	Valley Tin Flashing - - - - -
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	70 Lin.Ft.	5"	Gutter Eaves Trough - - - - -
1		Sides of Trim For 1/6x6/8 Closet Door - - - - -	50 Lin.Ft.		Gutter Crown Mould - - - - -
1		Sides of Trim For 9x12 - 12 Lt. Window - - - - -	15	5"	Hangers For Crown Mould - - - - -
1		Sides of Trim For 30x16 - 2 Lt. Window - - - - -	20	5"	Hangers For Gutter Eaves Trough - - - - -
1		Sides of Trim For 18x18 - 2 Lt. Window - - - - -	2		O.S. Mitres For Crown Mould - - - - -
70 Lin.Ft.		Base - - - - -	4	5"	End Caps For Eaves Trough - - - - -
90 Lin.Ft.		Base Shoe - - - - -	2		End Caps For Crown Mould - - - - -
40 Lin.Ft.		Chair Rail - - - - -	2		Drop Outlets For Crown Mould - - - - -
12 Lin.Ft.		Hook Strips - - - - -	90 Lin.Ft.	3"	Conductor Pipe - - - - -
20 Lin.Ft.		Shelf Cleats - - - - -	16	3"	Elbows - - - - -
3 Lin.Ft.		Thresholds - - - - -	28	3"	Conductor Pipe, Hooks - - - - -
20 Lin.Ft.		Closet Base - - - - -	6	3"	Strainers - - - - -
Interior Finish: Second Floor			4	5x3"	Drop Outlets For Eaves Trough - - - - -
7		Sides of Trim For 2/6x6/6 Doors - - - - -	2		Conductor Heads, See Plan - - - - -
2		Sides of Trim For 2/4x6/6 Doors - - - - -	NAILS		
5		Sides of Trim For 2/0x6/6 Doors - - - - -	90 Lbs.	20d	Common Nails - - - - -
2		Sides of Trim For 3/0x6/6 C.O. - - - - -	90 Lbs.	16d	Common Nails - - - - -
5		Sides of Trim For 3/0x6/6 Closet Doors - - - - -	30 Lbs.	10d	Common Nails - - - - -
8		Sides of Trim For 3/0x6/6 Closet Doors - - - - -	180 Lbs.	8d	Common Nails - - - - -
1		Sides of Trim For 10x10 - 12 Lt. Windows - - - - -	15 Lbs.	6d	Common Nails - - - - -
1		Sides of Trim For 1/8x2/6 O.S. Closet Sash - - - - -	5 Lbs.	10d	Casing Nails - - - - -
205 Lin.Ft.		Base - - - - -	60 Lbs.	8d	Casing Nails - - - - -
260 Lin.Ft.		Base Shoe - - - - -	5 Lbs.	6d	Casing Nails - - - - -
55 Lin.Ft.		Closet Base - - - - -	10 Lbs.	10d	Finish Nails - - - - -
200 Lin.Ft.		Picture Mould - - - - -	20 Lbs.	8d	Finish Nails - - - - -
28 Lin.Ft.		Chair Rail - - - - -	5 Lbs.	6d	Finish Nails - - - - -
55 Lin.Ft.		Hook Strips - - - - -	2 Lbs.	4d	Finish Nails - - - - -
40 Lin.Ft.		Shelf Cleats - - - - -	1 Lb.	7/8"	Finish Brads (16 Gauge) - - - - -
3 Lin.Ft.		Thresholds - - - - -	50 Lbs.	3d	Shingle Nails Hot Dipped Zinc Coated - - - - -
Main Stair			100 Lbs.	5d	Galv. Nails Hot Dipped Zinc Coated - - - - -
1		Starting Newel Colonial - - - - -	2 Lbs.	3d	Fine Lath Nails - - - - -
1		Landing Newel Colonial - - - - -	5 Lbs.	20d	Cut Nails For Furring - - - - -
1		Circle End Tread & Riser, See Plan - - - - -	PAINT		
13		Treads - - - - -	3-1/2 Gals.		Outside Trim Paint - - - - -
14		Risers - - - - -	1 Gals.		Porch Ceiling Paint - - - - -
2	3/0	Landing Treads - - - - -	1 Gals.		Blind or Shutter Paint - - - - -
20 Lin.Ft.		Rail Colonial - - - - -	2 Gals.		Sheet Metal Paint (Mineral) - - - - -
45	32"	Balusters Colonial - - - - -	1 Gals.		Paint For Brickwork, Undercoat - - - - -
14 Lin.Ft.		Nosing - - - - -	6 Gals.		Inside Varnish - - - - -
8 Lin.Ft.		Face Mould - - - - -	7-1/2 Gals.		Floor Varnish - - - - -
18 Lin.Ft.		Wall String (2 Mem.) - - - - -	1/2 Gals.		Spar Varnish - - - - -
8 Lin.Ft.		Face String - - - - -	1/2 Gals.		Shellac - - - - -
10 Lin.Ft.		Well Casing - - - - -	3 Gals.		Liquid Wood Filler - - - - -
1		Wall Rosette - - - - -	1/2 Gals.		Flat White - - - - -
1		Easing - - - - -	1 Gals.		White Enamel - - - - -
14 Lin.Ft.		Wall Rail - - - - -	1 Gals.		Paint For Brickwork, Top Coat - - - - -
3		Wall Rail Brackets - - - - -	1 Gals.		Boiled Linseed Oil - - - - -
2		Stair Rail Acorn Ends - - - - -	2 Gals.		Turpentine - - - - -
Miscellaneous			25 Lbs.		Putty - - - - -
60 Lin.Ft.		Stair Cove Moulding - - - - -			
1 Pc.	4/0	Stair Part. Jamb - - - - -			
1 Pc.	8/0	Stair Part. Casing - - - - -			
Cabinets					
1		Mantle Shelf & Trim, See Plan - - - - -			
1		Medicine Cabinet - - - - -			
2		Kitchen Cabinets Over Worktable With Hdwe., See Plan - - - - -			
1		Kitchen Worktable Complete with Hdwe., See Plan - - - - -			

MATERIAL LIST FOR THE AUGUST 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills For Foundation				Inside Finish Lumber			
2 Pc.	2x6-18	Main Building - - - - -	36	4 Pc.	1x12-10	Shelving - - - - -	40
2 Pc.	2x6-16	Main Building - - - - -	32	3 Pc. 1-1/4x10-14	Cellar Stair Treads - - - - -		44
4 Pc.	2x6-14	Main Building - - - - -	56	3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
9 Pc.	2x6-12	Main Building - - - - -	108	2 Pc.	2x4-12	Cellar Stair Rails & Newels - - - - -	16
				2 Pc.	1x4-8	Cellar Stair Rails - - - - -	5
Girders and Lintles							
2 Pc.	6x8-14	Main Building - - - - -	112				
2 Pc.	2x8-12	Front Porch Roof Beams - - - - -	32				
2 Pc.	2x8-10	Front Porch Roof Beam - - - - -	26				
2 Pc.	2x8-9	Front Porch Roof Beam - - - - -	24				
Girder Posts							
4 Pc.	6x6-7	Main Building - - - - -	84				
2 Pc.	4x4-7	Stair Posts - - - - -	19				
Floor Joists, Headers and Trimmers							
15 Pc.	2x10-16	First Floor Main Building - - - - -	400				
53 Pc.	2x10-14	First Floor Main Building - - - - -	1237				
7 Pc.	2x10-10	First Floor Main Building - - - - -	117				
1 Pc.	2x10-18	First Floor Box Sill - - - - -	30				
1 Pc.	2x10-16	First Floor Box Sill - - - - -	27				
2 Pc.	2x10-14	First Floor Box Sill - - - - -	47				
1 Pc.	2x4-14	Hearth Floor Support - - - - -	9				
9 Pc.	2x10-20	Second Floor Main Building - - - - -	300				
10 Pc.	2x10-18	Second Floor Main Building & Headers - - - - -	300				
29 Pc.	2x10-14	Second Floor Main Building - - - - -	677				
12 Pc.	2x10-12	Second Floor Main Building - - - - -	240				
Ceiling Joists							
12 Pc.	2x6-14	Main Building - - - - -	168				
12 Pc.	2x6-9	Main Building - - - - -	108				
6 Pc.	2x4-12	Front Porch - - - - -	48				
Outside Studs							
138 Pc.	2x4-8	Main Building - - - - -	736				
10 Pc.	2x4-12	Main Gables - - - - -	80				
18 Pc.	2x4-10	Main Gables - - - - -	120				
6 Pc.	2x4-9	Main Gables - - - - -	36				
6 Pc.	2x4-8	Porch Gables - - - - -	32				
36 Pc.	2x4-8	Dormers - - - - -	192				
2 Pc.	2x4-14	Dormers, Deck Framing - - - - -	19				
Inside Studs							
85 Pc.	2x4-8	First Floor - - - - -	453				
16 Pc.	2x6-8	First Floor - - - - -	128				
4 Pc.	2x6-12	First Floor C.O. Headers - - - - -	48				
90 Pc.	2x4-8	Second Floor - - - - -	480				
6 Pc.	2x6-8	Second Floor - - - - -	48				
6 Pc.	2x6-8	Window Lintles - - - - -	48				
Stud and Partition Plates							
32 Pc.	2x4-14	Outside Walls - - - - -	299				
45 Pc.	2x4-12	Inside Partitions - - - - -	360				
3 Pc.	2x6-12	Inside Partitions - - - - -	36				
3 Pc.	2x6-10	Inside Partitions - - - - -	30				
1 Pc.	2x4-12	Mantle Nailing Blocks - - - - -	8				
Rafters							
18 Pc.	2x6-20	Main Building - - - - -	360				
34 Pc.	2x6-18	Main Building - - - - -	612				
4 Pc.	2x6-10	Main Building - - - - -	40				
4 Pc.	1x6-8	Collar Beams - - - - -	16				
12 Pc.	2x4-10	Front Porch - - - - -	80				
12 Pc.	2x6-14	Dormers Rear - - - - -	168				
4 Pc.	2x4-6	Dormers Front - - - - -	16				
2 Pc.	2x8-20	Valley Rafters - - - - -	53				
3 Pc.	1x8-16	Ridge Boards - - - - -	32				
1 Pc.	1x6-10	Ridge Boards - - - - -	5				
Step and Stair Carriages							
2 Pc.	2x10-14	Cellar Stairs - - - - -	47				
2 Pc.	2x10-16	Main Stairs - - - - -	53				
Sheathing, Boards, Sub-flooring, Furring, Etc.,							
1075 Ft.	1x4	Roof Sheathing S.2.S.Laid 4-1/2" O.C. - - - - -	1075				
410 Ft.	1x6	Roof Sheathing D&M Over Rooms & Deck - - - - -	410				
1875 Ft.	1x6	Sub-flooring D&M Laid Diagonally - - - - -	1875				
2060 Ft.	1x8	Box Sheathing O.S.Walls Ship Lap Laid Diagonally - - - - -	2060				
150 Ft.	1x6	Backing & Furring - - - - -	150				
5 Pc.	1x2-8	Furring Inside Walls For Chimney Breast - - - - -	7				
1250 Lin.Ft.	1x1	Ground (Around Inside Openings) - - - - -	104				
80 Ft.	1x4	Bridging - - - - -	80				
70 Ft.	1x2	Floor Stripping For 2nd Floor Only - - - - -	70				
Siding For Outside Walls							
1625 Ft.	3/4x10"	Bev.Siding 1" Lap. - - - - -	1625				
25 Ft.	1x8	Shiplap Siding - - - - -	25				
Flooring and Ceiling							
570 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor - - - - -	570				
430 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - - - -	430				
525 Ft.	3/4x3-1/4	Flooring, Second Floor - - - - -	525				
150 Ft.	5/8x3-1/4	Ceiling Porches - - - - -	150				
Shingles							
15-1/2 Squares	5/2	Shingles For Roof Certigrade Red Cedar 4-1/2" Exp. - - - - -					
Lath							
250	48"	Exterior Lath For Furring - - - - -					
Outside Finish Lumber							
1 Pc.	1x2-14	Panel Strips (Dormers) - - - - -	3				
120 Ft.	1x6	Frieze - - - - -	120				
20 Ft.	1x10	Porch Lintle Frieze - - - - -	20				
18 Ft.	1x8	Porch Lintle Frieze - - - - -	18				
10 Ft.	1x4	Porch Lintle Soffit - - - - -	10				
15 Ft.	1x6	Porch Lintle Facia - Cut to Design - - - - -					
25 Ft.	1x4 to 1x10	Miscellaneous O.S.Finish - - - - -	25				

MATERIAL LIST FOR THE AUGUST 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)					
For Balance - First Floor			FINISH HARDWARE		
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	4		Cellar Sash Sets - - - - -
3	2/6x6/8x1-3/8	Inside Doors Panelled - - - - -	4-1/2 Pr.	4x4	Door Butts - - - - -
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	11 Pr.	3-1/2x3-1/2	Door Butts - - - - -
1	1/10x6/8x1-3/8	Inside Door Panelled - - - - -	1 Pr.	2-1/2	Cupboard Door Butts, Narrow - - - - -
6 Sets	7/8x5-5/8	Door Jambs For 2/6x6/8 Doors & Smaller - - - - -	2 Pr.	3-1/2x3-1/2	Bathroom Door Butts, & Toilet - - - - -
1 Set	7/8x5-5/8	Door Jambs For 5/0x6/8 C.O. - - - - -	1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow - - - - -
Doors and Jambs For Second Floor			1		Front Door Lock Set - - - - -
2	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	1		Rear Door Lock Set - - - - -
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	11		Inside Door Lock Sets - - - - -
3	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	2		Toilet & Bathroom Door Lock Sets - - - - -
6 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 Doors & Smaller - - - - -	1 Single		French Door Lock Set - - - - -
1 Set	12x16x7/8	Pipe Door, Jambs & Trim - - - - -	1 Set	1-3/8"	Double Acting Hinge For Floor - - - - -
Interior Finish: Main Rooms, First Floor			2		Push Plates - - - - -
1		Sides of Trim For 3/0x6/8 Door - - - - -	15		Sash Locks - - - - -
2		Sides of Trim For 2/6x6/8 Door - - - - -	30		Sash Lifts - - - - -
1		Sides of Trim For 2/4x6/8 Door - - - - -	4		Sash Lifts, Bathroom & Toilet - - - - -
1		Sides of Trim For 2/0x6/8 Door - - - - -	2		Sash Locks, Bathroom & Toilet - - - - -
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	1		Cupboard Turn - - - - -
4		Sides of Trim For 4/0x6/8 C.O. - - - - -	10		Cupboard Turn, Med. Case - - - - -
2		Sides of Trim For 3/4x6/8 C.O. - - - - -	2		Metal Base Knobs - - - - -
3		Sides of Trim For 10x12 - 12 Lt. Windows - - - - -	4 Doz.		Metal Base Knobs, Bathroom & Toilet - - - - -
1 Mull.		Sides of Trim For 10x12 - 12 Lt. Windows - - - - -	2 Sets		Coat and Hat Hooks - - - - -
135 Lin.Ft.		Base - - - - -	Rough Hardware		
145 Lin.Ft.		Base Shoe - - - - -	4 Hanks		Sash Cord - - - - -
165 Lin.Ft.		Picture Mould - - - - -	28	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
10 Lin.Ft.		Closet Base - - - - -	4 Sets	6"	C.I. Post Caps & Sockets Incl. Lag Screws - - - - -
10 Lin.Ft.		Hook Strips - - - - -	400 Lbs.		Sash Weights - - - - -
10 Lin.Ft.		Shelf Cleats - - - - -	Building Paper		
1 Pc.	3/6	Thresholds - - - - -	6 Rolls	50 Lb.	Building Paper (500 Ft. Rolls) - - - - -
1 Pc.	3/0	Thresholds - - - - -	SHEET METAL MATERIAL		
Interior Finish: Balance of Rooms, First Floor			15 Sq.Ft.		Metal Roofing Including Nails & Felt - - - - -
1		Sides of Trim For 2/8x6/8 Door - - - - -	75 Lin.Ft.	14"	Valley Tin Flashing - - - - -
7		Sides of Trim For 2/6x6/8 Door - - - - -	125	10x12	Tin Shingles - - - - -
1		Sides of Trim For 2/4x6/8 Door - - - - -	80 Lin.Ft.		Gutter Crown Mould - - - - -
1		Sides of Trim For 2/0x6/8 Door - - - - -	2 Doz.		Hangers - - - - -
1		Sides of Trim For 1/10x6/8 Door - - - - -	1		I.S. Mitres Crown Mould - - - - -
2		Sides of Trim For 5/0x6/8 C.O. - - - - -	15		End Caps Crown Mould - - - - -
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	7	3"	Drop Outlets Crown Mould - - - - -
1		Sides of Trim For 1/10x6/8 Closet Door - - - - -	70 Lin.Ft.	3"	Conductor Pipe, Crown Mould - - - - -
1		Sides of Trim For 10x12 - 12 Lt. Windows - - - - -	12	3"	Elbows - - - - -
2		Sides of Trim For 8x12 - 12 Lt. Windows - - - - -	20	3"	Conductor Pipe, Hooks - - - - -
2		Sides of Trim For 8x10 - 12 Lt. Windows - - - - -	7	3"	Strainers - - - - -
1		Sides of Trim For 40x16 - 2 Lt. Windows - - - - -	14 Lin.Ft.		Vents For Gas Flue - - - - -
130 Lin.Ft.		Base - - - - -	90 Lbs.	20d	Common Nails - - - - -
140 Lin.Ft.		Base Shoe - - - - -	90 Lbs.	16d	Common Nails - - - - -
50 Lin.Ft.		Picture Mould - - - - -	30 Lbs.	10d	Common Nails - - - - -
60 Lin.Ft.		Chair Rail - - - - -	180 Lbs.	8d	Common Nails - - - - -
10 Lin.Ft.		Hook Strips - - - - -	10 Lbs.	6d	Common Nails - - - - -
10 Lin.Ft.		Shelf Cleats - - - - -	5 Lbs.	10d	Casing Nails - - - - -
1 Pc.	3/0	Thresholds - - - - -	55 Lbs.	8d	Casing Nails - - - - -
10 Lin.Ft.		Closet Base - - - - -	10 Lbs.	6d	Casing Nails - - - - -
Interior Finish: Second Floor			5 Lbs.	10d	Finish Nails - - - - -
4		Sides of Trim For 2/6x6/6 Doors - - - - -	15 Lbs.	8d	Finish Nails - - - - -
2		Sides of Trim For 2/4x6/6 Doors - - - - -	5 Lbs.	6d	Finish Nails - - - - -
3		Sides of Trim For 2/0x6/6 Doors - - - - -	2 Lbs.	4d	Finish Nails - - - - -
3		Sides of Trim For 2/0x6/6 Closet Doors - - - - -	1 Lb.	7/8"	Finish Brads (16 Gauge) - - - - -
2		Sides of Trim For 8x10 - 12 Lt. Windows - - - - -	75 Lbs.	3d	Galv. Shingle Nails Hot Dipped Zinc Coated - - - - -
2 Mull.		Sides of Trim For 8x12 - 12 Lt. Windows - - - - -	45 Lbs.	8d	Coated Nails, For Siding - - - - -
120 Lin.Ft.		Base - - - - -	2 Lbs.	3d	Fine Lath Nails - - - - -
140 Lin.Ft.		Base Shoe - - - - -	2 Lbs.	20d	Cut Nails For Furring - - - - -
16 Lin.Ft.		Closet Base - - - - -	PAINT		
115 Lin.Ft.		Picture Mould - - - - -	7-1/2 Gals.		Outside Body Paint - - - - -
24 Lin.Ft.		Chair Rail - - - - -	2-1/2 Gals.		Outside Trim Paint - - - - -
15 Lin.Ft.		Hook Strips - - - - -	1-1/4 Gals.		White Enamel - - - - -
10 Lin.Ft.		Shelf Cleats - - - - -	1 Gals.		Porch Ceiling Paint - - - - -
Main Stair			1/4 Gals.		Blind or Shutter Paint - - - - -
1		Starting Newel - - - - -	1 Gals.		Sheet Metal Paint (Mineral) - - - - -
1		Circle End Tread & Riser, See Plan - - - - -	1 Gals.		Paint For Brick Work, Undercoat - - - - -
12		Treads - - - - -	5 Gals.		Inside Varnish - - - - -
13		Risers - - - - -	6 Gals.		Floor Varnish - - - - -
3		Landing Treads - - - - -	1/2 Gals.		Spar Varnish - - - - -
4 Lin.Ft.		Rail - - - - -	1/4 Gals.		Shellac - - - - -
8	32"	Balusters - - - - -	3 Gals.		Liquid Wood Filler - - - - -
4 Lin.Ft.		Nosing - - - - -	3/4 Gals.		Flat White - - - - -
5 Lin.Ft.		Face Mould - - - - -	1/4 Gal.		White Enamel - - - - -
32 Lin.Ft.		Wall String (2 Mem.) - - - - -	1 Gals.		Paint For Brick Top Coat - - - - -
5 Lin.Ft.		Face String - - - - -	2 Gals.		Boiled Linseed Oil - - - - -
1		Wall Rosette - - - - -	2 Gals.		Turpentine - - - - -
20 Lin.Ft.		Wall Rail - - - - -	20 Lbs.		Putty - - - - -
5		Wall Rail Brackets - - - - -			
4		Stair Rail Acorn Ends - - - - -			
Miscellaneous					
60 Lin.Ft.		Stair Cove Moulding - - - - -			
Cabinets					
1 Set		China Shelves, See Plan - - - - -			
1		Mantel Shelf & Trim, See Plan - - - - -			
1 Set		Dining Nook Seats & Table, See Plan - - - - -			
1		Medicine Cabinet - - - - -			
1		Kitchen Cabinet Over Ref. Space With Hdwe. See Plan - - - - -			
2		Kitchen Cabinets Over Worktable With Hdwe., See Plan - - - - -			
1		Combination Kitchen Cabinet and Worktable Top Cut & Grooved For Sink, Complete with Hardware See Pl. - - - - -			
1		Broom Closet with Hdwe., See Plan - - - - -			

MATERIAL LIST FOR THE SEPTEMBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
8 Pc.	2x6-16	Main Building & Garage	128	62 Ft.	1x8	Facias	62
8 Pc.	2x6-14	Main Building & Garage	112	44 Ft.	1x6	Plancier	44
8 Pc.	2x6-12	Main Building & Garage	96	2 Pc.	1x2-12	Porch Frieze	4
6 Pc.	2x6-10	Main Building & Garage	60	34 Ft.	1x10	Porch Lintle Frieze	34
2 Pc.	2x6-8	Main Building & Garage	16	2 Po.	1x4-10	Porch Lintle Soffit & Frieze	7
4 Pc.	2x10-16	Main Building Box Sills	107	72 Ft.1-1/4x6"		Gable Frieze	72
2 Pc.	2x10-12	Main Building Box Sills	40	25 Ft.1x4 to 1x10		Miscellaneous O.F.Finish	25
Girders and Lintles				Inside Finish Lumber			
1 Pc.	6x8-20	Main Building	80	4 Pc.	1x12-10	Shelving	40
1 Po.	6x8-14	Main Building	56	4 Po.1-1/4x10-14		Cellar Stair Treads	58
2 Pc.	2x10-12	Rear Porch Roof Beam	40	4 Pc.	1x8-14	Cellar Stair Risers	37
1 Pc.	2x12-14	Front Porch Roof Beam Cut to Curve	28	1 Pc.	1x10-12	Cellar Stair Stringers In Entry	10
1 Pc.	2x10-6	Front Porch Roof Beam	10	1 Pc.	2x4-12	Cellar Stair Rails & Newel	8
Girder Posts				1 Pc.	1x4-8	Cellar Stair Rails	3
5 Pc.	6x6-7	Main Building	105	INSULATION			
3 Pc.	4x4-7	Stair Posts	28	2500 Sq.Ft.		Insulating Material	
Floor Joists, Headers and Trimmers				MASONRY MATERIAL			
26 Pc.	2x10-14	First Floor Main Building	607	Concrete Foundation 1-3-5 Mixture - 1158 Cu.Ft.			
54 Pc.	2x10-12	First Floor Main Building	1080	34 Cu.Yds.		Crushed Stone or Gravel	
8 Pc.	2x10-8	First Floor Main Building	107	20-1/2 Cu.Yds.		Coarse Sand	
4 Pc.	2x10-16	Headers	107	48-1/2 Bbls.		Portland Cement	
1 Pc.	2x4-10	Hearth Supports	7	Cement Floor and Steps 4" One Course 1310 Sq.Ft.			
2 Pc.	2x10-10	Garage Door Beams	33	13-1/4 Cu.Yds.		Crushed Stone or Gravel	
Ceiling Joists				8-3/4 Cu.Yds.		Coarse Sand	
27 Pc.	2x6-14	Main Building	378	20 Bbls.		Portland Cement	
29 Pc.	2x6-12	Main Building	348	Chimneys and Fireplace			
10 Pc.	2x6-10	Main Building	100	4150		Common Brick	
11 Pc.	2x6-8	Main Building	88	50		Face Brick For Fireplace	
8 Pc.	2x6-16	Garage	128	120		Fire Clay Brick	
9 Pc.	2x4-14	Front Porch	84	4 Cu.Yds.		Sand	
2 Pc.	2x6-9	Front Porch Headers	18	4 Bbls.		Lime	
9 Pc.	2x4-6	Rear Porch Headers	36	1 Bbl.		Portland Cement	
Outside Studs				50 Lbs.		Fire Clay	
193 Pc.	2x4-8	Main Building	1029	40 Lin.Ft. 8x12"		Flue Lining	
27 Pc.	2x4-8	Garage	144	15 Sq.Ft. 1/2"		Wire Mesh For Hearth Reinforcing	
20 Pc.	2x4-6	Garage	80	1		Damper	
2 Pc.	2x4-10	Garage	13	1		Ash Dump	
36 Pc.	2x4-9	Gables	216	1		Cleanout Door	
8 Pc.	2x4-8	GarageGables	43	1	4x4x1/4"	Angle Iron 3'8" Long	
1 Pc.	2x4-18	Porch Gables (Cut)	12	Plastering			
8 Pc.	2x6-6	Door Headers	48	415 Yds.		Plastering, Including Plaster Base, Nails, Metal Lath Corner Strips, and Metal Corner Beads	
Inside Studs				70 Yds.		Cement Plaster, Including Metal Lath & Staples For Garage & Over Boiler Space	
140 Pc.	2x4-8	First Floor	747	MILLWORK			
7 Pc.	2x6-8	First Floor	56	Outside Millwork and Mouldings			
Stud and Partition Plates				210 Lin.Ft.		Bed Moulding	
40 Pc.	2x4-14	Outside Walls	373	100 Lin.Ft.		Cove Moulding	
35 Pc.	2x4-12	Inside Partitions	280	50 Lin.Ft.		1/4 Round Moulding	
3 Pc.	2x6-8	Inside Partitions	24	4	4x4 7/6	Porch Columns See Plan	
Rafters				2		Pilasters (Angle) See Plan	
55 Pc.	2x6-20	Main Building	1100	1		Hood, Including Brackets, See Plan	
8 Pc.	2x6-10	Garage	80	Outside Door Frames			
8 Po.	2x6-16	Garage	128	2	4/0x6/8x1-3/4	Door Frames D.C.	
14 Po.	1x6-12	Collar Beams	84	1	2/8x6/8x1-3/4	Grade Door Frame D.C.	
8 Pc.	2x6-8	Front Porch	64	1	3/0x6/8x1-3/4	Front Door Frame With Spl.Head Trim See Plan	
2 Pc.	1x8-18	Ridge Boards	24	1	2/6x6/8x1-3/8	Garage Door Frame D.C.	
1 Pc.	1x8-10	Ridge Boards	7	1	8/0x7/0	Overhead Garage Door Frame	
1 Pc.	1x6-10	Ridge Boards	5	Window and Sash Frames			
2 Pc.	2x8-12	Valley Rafters	32	5	8x10x1-1/8	3 Lt.Cellar Sash Frames Plank	
8 Pc.	2x4-18	Knee Brace Plates	96	9	9x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C.	
16 Pc.	2x4-10	Knee Brace Studs	107	4	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C.	
Step and Stair Carriages				1	3/4x3/0x1-3/8	0.S.Sash Frame D.C.	
2 Pc.	2x10-18	Cellar Stairs	60	Louvres			
2 Po.	2x6-16	Stairs Platform	32	1	10"x1'8"	0.S.Gable Louvre, See Plan	
Sheathing, Boards, Sub-flooring, Furring				Windows and Sash			
1650 Ft.	1x4	Roof Sheathing S.2.S.4-1/2" O.C.	1650	5	8x10x1-1/8	3 Lt.Cellar Sash Glz.	
1240 Ft.	1x6	Sub-flooring, S.2.S.Laid Diagonally	1240	9	9x12x1-3/8	12 Lt.Ck.Rail Window Glz.	
2450 Ft.	1x8	Box Sheathing 0.S.Walls Shiplap Laid Diagonally	2450	4	8x10x1-3/8	12 Lt.Ck.Rail Window Glz.	
150 Ft.	1x6	Backing & Furring	150	1	Pr. 3/4x3/0x1-3/8	0.S.Casement Sash Glz. 6 Lt.Each	
5 Pc.	1x2-8	Furring Inside Walls Chimney Breast	7	Blinds			
900 Lin.Ft. 1x1		Ground (Around Inside Openings)	75	1	Pr. 3/0x6/8	0.S.Door Blinds See Plan	
70 Ft.	1x4	Bridging	70	3	Pr. 9x12	12 Lt.Window Blinds	
20 Ft.	1x4	Lookouts	20	4	Pr. 8x10	12 Lt.Window Blinds	
Siding For Outside Walls				Doors and Jamb's For Main Rooms First Floor			
2160 Ft. 3/4x10"		Bev.Siding 1" Lap	2160	1	3/0x6/8x1-3/4	Front Door Glz. See Plan	
60 Ft.	1x8	Shiplap Siding	60	1	2/0x6/8x1-3/8	Inside Door Panelled	
Flooring and Ceiling				1	2/6x6/8x1-3/8	Inside Door Panelled	
500 Ft. 3/4x3-1/4		Flooring, Main Rooms First Floor	500	2	Pr. 4/0x6/8x1-3/4	0.S.French Doors, Glz. 10 Lts.Each	
555 Ft. 3/4x3-1/4		Flooring, Balance First Floor	555	2	Sets 7/8x5-5/8	Door Jamb's For 2/0x6/8 Door	
220 Ft. 5/8x3-1/4		Ceiling Porches	220				
Shingles							
18 Squares 16"		Shingles For Roof Certigrade Red Cedar 4-1/2" Exposure					

MATERIAL LIST FOR THE SEPTEMBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			HARDWARE (CONTINUED)		
For Balance - First Floor					
1	2/8x6/8x1-3/4	Grade Door Glz. - - - - -	2		Double French Door Lock Sets Rab't.Face - - -
1	2/8x6/8x1-3/8	Inside Door Panelled - - - - -	1 Set	1-3/8"	Floor Double Acting Hinge - - - - -
2	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	2		Push Plates - - - - -
1	2/4x6/8x1-3/8	Inside Door Panelled - - - - -	1 Set		Casement Sash Fasteners, Double - - - - -
2	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	12		Sash Locks - - - - -
1	1/6x6/8x1-3/8	Inside Door Panelled - - - - -	24		Sash Lifts - - - - -
1	1/4x6/8x1-3/8	Inside Door Panelled - - - - -	2		Sash Lifts, Bathroom - - - - -
7 Sets	7/8x5-5/8	Door Jambs For 2/8x6/8 Doors & Smaller - - - - -	1		Sash Lock, Bathroom - - - - -
1 Set	7/8x3-5/8	Door Jambs For 1/4x6/8 Doors - - - - -	4		Flush Bolts - - - - -
1	2/6x6/8x1-3/8	Garage Doors Glz. - - - - -	1		Cupboard Turn - - - - -
1 Set	12x16x7/8	Pipe Door, Jambs & Trim - - - - -	1		Cupboard Turn, Med.Case - - - - -
1 Set	8/0x7/0x1-3/4	Overhead Type Garage Door Glz. Top Panels (See Plan) Complete with Hdwe.& Equipment - - - - -	12		Metal Base Knobs - - - - -
Interior Finish: Main Rooms, First Floor			1		Metal Base Knob, Bathroom - - - - -
2		Sides of Trim For 4/0x6/8 Doors - - - - -	3 Doz.		Coat and Hat Hooks - - - - -
1		Sides of Trim For 3/0x6/8 Doors - - - - -	8 Sets		Window Blinds Hangers - - - - -
1		Sides of Trim For 2/0x6/8 Doors - - - - -	Rough Hardware		
1		Sides of Trim For 2/0x6/8 Closet Doors - - - - -	3 Hanks		Sash Cord - - - - -
1		Sides of Trim For 2/6x6/8 Door - - - - -	36	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
5		Sides of Trim For 9x12 - 12 Lt.Windows - - - - -	5 Sets	6"	C.I.Post Caps & Sockets With Lag Screws - - - - -
15 Lin.Ft.		Closet Base - - - - -	325 Lbs.		Sash Weights - - - - -
104 Lin.Ft.		Base - - - - -			
119 Lin.Ft.		Base Shoe - - - - -	BUILDING PAPER		
90 Lin.Ft.		Picture Mould - - - - -	6 Rolls	50#	Building Paper (500 Ft.Rolls) - - - - -
15 Lin.Ft.		Hook Strips - - - - -			
10 Lin.Ft.		Shelf Cleats - - - - -	SHEET METAL MATERIAL		
13 Lin.Ft.		Thresholds - - - - -	15 Sq.Ft.		Metal Roofing with Nails - - - - -
Interior Finish: Balance of Rooms, First Floor			50 Lin.Ft.	14"	Valley Tin Flashing - - - - -
3		Sides of Trim For 2/8x6/8 Doors - - - - -	30	10x12"	Tin Shingles - - - - -
5		Sides of Trim For 2/6x6/8 Doors - - - - -	90 Lin.Ft.		Gutter Crown Mould - - - - -
2		Sides of Trim For 2/4x6/8 Doors - - - - -	21		Hangers Crown Mould - - - - -
2		Sides of Trim For 2/0x6/8 Door - - - - -	12		End Caps Crown Mould - - - - -
1		Sides of Trim For 1/6x6/8 Doors - - - - -	8		Drop Outlets Crown Mould - - - - -
1		Sides of Trim For 1/4x6/8 Doors - - - - -	60 Lin.Ft.	3"	Conductor Pipe - - - - -
1		Sides of Trim For 1/4x6/8 Closet Door - - - - -	16		Elbows - - - - -
1		Sides of Trim For 1/6x6/8 Closet Door - - - - -	18	3"	Conductor Pipe, Hooks - - - - -
2		Sides of Trim For 2/0x6/8 Closet Door - - - - -	2		Funnels, See Plan - - - - -
1		Sides of Trim For 2/6x6/8 Garage Door - - - - -	8	3"	Strainers - - - - -
4		Sides of Trim For 9x12 - 12 Lt.Window - - - - -	2		Conductor Baskets - - - - -
1		Sides of Trim For 8x10 - 12 Lt.Window - - - - -			
1		Sides of Trim For 8x10 - 12 Lt.Window Garage - - - - -			
1		Sides of Trim For 3/4x3/0 O.S.Sash - - - - -			
8 Lin.Ft.		Window Stool Attic - - - - -			
32 Lin.Ft.		Window Stop Attic - - - - -			
163 Lin.Ft.		Base - - - - -			
200 Lin.Ft.		Base Shoe - - - - -			
165 Lin.Ft.		Picture Mould - - - - -			
55 Lin.Ft.		Chair Rail - - - - -			
40 Lin.Ft.		Hook Strips - - - - -			
30 Lin.Ft.		Shelf Cleats - - - - -			
1	3/0	Thresholds - - - - -			
35 Lin.Ft.		Closet Base - - - - -			
1 Set	24x24"	Scuttle Trim, Door & Jambs - - - - -			
2		Landing Treads - - - - -			
Cabinets					
2 Sets		Open Book Shelves with Cabinet Below Complete With Hardware See Plan - - - - -			
1		Mantel Shelf & Trim, See Plan - - - - -			
1		Medicine Cabinet - - - - -			
1		Kitchen Cabinet Over Ref.Space With Hdwe. See Plan - - - - -			
2		Combination Kitchen Cabinets and Worktable Complete with Hdwe.,See Plan-			
FINISH HARDWARE					
5		Cellar Sash Sets - - - - -	9 Gals.		Outside Body Paint - - - - -
1 Pr.	3-1/2x3-1/2	Garage Door Butts - - - - -	3-1/2 Gals.		Outside Trim Paint - - - - -
9 Pr.	4x4	Door Butts - - - - -	1 Gals.		Porch Ceiling Paint - - - - -
8 Pr.	3-1/2x3-1/2	Door Butts - - - - -	1 Gals.		Blind or Shutter Paint - - - - -
2 Pr.	3x3	Casement Sash Butts - - - - -	1 Gals.		Sheet Metal Paint (Mineral) - - - - -
1 Pr.	2-1/2	Cupboard Door Butts, Narrow - - - - -	6 Gals.		Inside Varnish - - - - -
1 Pr.	3-1/2x3-1/2	Bathroom Door Butts - - - - -	5 Gals.		Floor Varnish - - - - -
1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow - - - - -	1/2 Gals.		Spar Varnish - - - - -
1		Front Door Lock Set - - - - -	1/4 Gals.		Shellac - - - - -
1		Garage Door Lock Set - - - - -	3 Gals.		Liquid Wood Filler - - - - -
1		Grade Door Lock Set - - - - -	1/2 Gals.		Flat White - - - - -
8		Inside Door Lock Sets - - - - -	1 Gals.		White Enamel - - - - -
1		Bathroom Door Lock Set - - - - -	2 Gals.		Boiled Linseed Oil - - - - -
			2 Gals.		Turpentine - - - - -
			25 Lbs.		Putty - - - - -

MATERIAL LIST FOR THE OCTOBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION		Feetage	Quantity	Size	ARTICLE AND DESCRIPTION		Feetage
LUMBER					LUMBER (CONTINUED)				
Wall Plates or Sills for Foundation					Outside Finish Lumber				
6 Pc.	2x6-14	Main Building & Garage	- - - - -	84	42 Ft.	1x8	Frieze	- - - - -	42
2 Pc.	2x6-12	Main Building & Garage	- - - - -	24	60 Ft.	1-1/4x6"	Frieze	- - - - -	60
12 Pc.	2x6-10	Main Building & Garage	- - - - -	120	1 Pc.	1-1/4x10-12	Frieze, Cut to Curve	- - - - -	13
6 Pc.	2x6-8	Main Building	- - - - -	48	35 Ft.	1x8	Porch Facia	- - - - -	35
Girders and Lintles					25 Ft.	1x10	Porch Lintle Frieze	- - - - -	25
1 Pc.	6x8-16	Main Building	- - - - -	64	10 Ft.	1x4	Porch Lintle Frieze	- - - - -	10
1 Pc.	6x8-14	Main Building	- - - - -	56	10 Ft.	1x4	Porch Lintle Soffit	- - - - -	10
2 Pc.	2x10-20	Front Porch Roof Beam	- - - - -	67	1 Pc.	1x10-14	Porch Lintle Frieze - Cut to Design	- - - - -	12
1 Pc.	2x10-12	Front Porch Roof Beam	- - - - -	20	See Plan-				
Girder Posts					125 Lin.Ft.	1x2	Porch Lattice	- - - - -	11
2 Pc.	6x6-7	Main Building	- - - - -	42	20 Ft.	1x4 to 1x10	Miscellaneous O.S.Finish	- - - - -	20
Floor Joists, Headers and Trimmers					Inside Finish Lumber				
27 Pc.	2x10-14	First Floor Main Building	- - - - -	630	5 Pc.	1x12-10	Shelving	- - - - -	50
9 Pc.	2x10-18	First Floor Main Building	- - - - -	270	3 Pc.	1-1/4x10-14	Cellar Stair Treads	- - - - -	44
8 Pc.	2x10-10	First Floor Headers	- - - - -	133	3 Pc.	1x8-14	Cellar Stair Risers	- - - - -	28
1 Pc.	2x10-12	First Floor Box Sills	- - - - -	20	1 Pc.	2x4-12	Cellar Stair Rails & Newel	- - - - -	8
2 Pc.	2x10-8	First Floor Box Sills	- - - - -	27	20 Ft.	1x4	Garage Trim (Inside)	- - - - -	20
12 Pc.	2x10-18	Second Floor Main Building	- - - - -	360					
26 Pc.	2x10-14	Second Floor Main Building	- - - - -	607					
6 Pc.	2x10-12	Second Floor Main Building	- - - - -	120					
3 Pc.	2x10-10	Second Floor Headers	- - - - -	50					
Ceiling Joists									
17 Pc.	2x6-16	Main Building	- - - - -	272					
6 Pc.	2x6-9	Main Building	- - - - -	54					
8 Pc.	2x4-6	Garage Ceil.Joists	- - - - -	32					
16 Pc.	2x4-6	Front Porch	- - - - -	64					
2 Pc.	2x10-12	Garage Door Beams	- - - - -	40					
Outside Studs									
106 Pc.	2x4-10	Main Building	- - - - -	707					
22 Pc.	2x4-10	Gables	- - - - -	147					
3 Pc.	2x4-10	Garage	- - - - -	20					
14 Pc.	2x4-8	Garage	- - - - -	75					
1 Pc.	2x4-8	Porch Gables	- - - - -	5					
44 Pc.	2x4-6	Dormers	- - - - -	176					
12 Pc.	2x6-6	Window Lintles	- - - - -	72					
2 Pc.	2x6-10	Bay Window Lintles	- - - - -	20					
Inside Studs									
72 Pc.	2x4-8	First Floor	- - - - -	384					
2 Pc.	2x6-8	First Floor	- - - - -	16					
4 Pc.	2x6-6	First Floor C.O.Headers	- - - - -	24					
58 Pc.	2x4-8	Second Floor	- - - - -	309					
12 Pc.	2x4-10	Second Floor Cut	- - - - -	80					
2 Pc;	2x6-8	Second Floor	- - - - -	16					
Stud and Partition Plates									
35 Pc.	2x4-14	Outside Walls	- - - - -	327					
42 Pc.	2x4-12	Inside Partitions	- - - - -	336					
1 Pc.	2x6-8	Inside Partitions	- - - - -	8					
8 Pc.	2x4-12	Fire Stops	- - - - -	64					
Rafters									
24 Pc.	2x6-20	Main Building	- - - - -	480					
8 Pc.	2x6-16	Main Building	- - - - -	128					
18 Pc.	2x6-8	Main Building	- - - - -	144					
5 Pc.	2x4-8	Bays	- - - - -	27					
24 Pc.	2x6-8	Front Porch	- - - - -	192					
11 Pc.	1x10-10	Front Porch Cut to Curve	- - - - -	92					
18 Pc.	2x6-14	Dormers	- - - - -	252					
4 Pc.	2x6-6	Valley Rafters	- - - - -	24					
2 Pc.	1x8-16	Ridge Boards	- - - - -	21					
2 Pc.	1x6-8	Ridge Boards	- - - - -	8					
Step and Stair Carriages									
2 Pc.	2x10-14	Cellar Stairs	- - - - -	47					
2 Pc.	2x10-16	Main Stairs	- - - - -	53					
1 Pc.	2x6-16	Stairs Platform	- - - - -	16					
Sheathing, Boards, Sub-flooring, Furring, Etc.,									
800 Ft.	1x4	Roof Sheathing S.2.S.Laid 4-1/2" O.C.	- - - - -	800					
450 Ft.	1x6	Roof Sheathing D&M Over Rooms & Dormers	- - - - -	450					
1310 Ft.	1x6	Sub-flooring D&M Laid Diagonally	- - - - -	1310					
1900 Ft.	1x8	Box Sheathing O.S.Walls Shiplap Laid Diagonally	- - - - -	1900					
175 Ft.	1x6	Ribbons, Backing & Furring	- - - - -	175					
12 Pc.	1x2-8	Furring Inside Walls At Chimney & Porch	- - - - -	16					
1000 Lin.Ft.	1x1	Ground (Around Inside Openings)	- - - - -	83					
95 Ft.	1x4	Bridging	- - - - -	95					
70 Ft.	1x2	Floor Stripping On 2nd Floor Only	- - - - -	70					
Siding For Outside Walls									
1450 Ft.	3/4x10"	Bev.Siding 1" Lap.	- - - - -	1450					
450 Ft.		"V" Vertical Siding Random Widths 8/0 Long - Under Porch & Living Room Wall	- - - - -	450					
25 Ft.	1x8	Shiplap Siding	- - - - -	25					
Flooring and Ceiling									
450 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor	- - - - -	450					
140 Ft.	3/4x3-1/4	Flooring, Balance First Floor	- - - - -	140					
650 Ft.	3/4x3-1/4	Flooring, Second Floor	- - - - -	650					
140 Ft.	5/8x3-1/4	Ceiling Porches	- - - - -	140					
Shingles									
11 Squares	5/2 16"	Shingles For Roof Certigrade Red Cedar 4-1/2" Exposure	- - - - -						
Lath									
50	48"	Lath For Furring	- - - - -						

INSULATION				
2100 Sq.Ft.	Insulating Material - - - - -			
MASONRY MATERIAL				
Concrete Foundation 1-3-5 Mixture - 771 Cu.Ft.				
23 Cu.Yds.	Crushed Stone or Gravel - - - - -			
13-1/2 Cu.Yds.	Coarse Sand - - - - -			
31-1/2 Bbls.	Portland Cement - - - - -			
Cement Floor and Steps 1-3-5 Mixture - 815 Sq.Ft.				
8 Cu.Yds.	Crushed Stone or Gravel - - - - -			
5-1/2 Cu.Yds.	Coarse Sand - - - - -			
12-1/2 Bbls.	Portland Cement - - - - -			
Chimneys and Fireplace				
6000	Common Brick - - - - -			
60	Face Brick For Fireplace - - - - -			
120	Fire Clay Brick - - - - -			
5-1/2 Cu.Yds.	Sand - - - - -			
5-1/2 Bbls.	Lime - - - - -			
1 Bbl.	Portland Cement - - - - -			
50 Lbs.	Fire Clay - - - - -			
28 Lin.Ft. 8x12"	Flue Lining - - - - -			
20 Lin.Ft. 12x12	Flue Lining - - - - -			
15 Sq.Ft. 1/2"	Wire Mesh Reinforcing For Hearth - - - - -			
1	Damper - - - - -			
1	Ash Dump - - - - -			
1	Cleanout Door - - - - -			
1	4x4x1/4"	Angle Iron 4'2" Long - - - - -		
Plastering				
445 Yds.	Plaster, Including Plaster Base, Nails, Metal Lath Corner Strips, and Metal Corner Beads - - - - -			
80 Yds.	Cement Plaster, Including Metal Lath & Staples for Garage & Over Boiler Space - - - - -			
MILLWORK				
Outside Millwork and Mouldings				
225 Lin.Ft.	Bed Moulding - - - - -			
60 Lin.Ft.	Cove Moulding - - - - -			
40 Lin.Ft.	1/4 Round Moulding - - - - -			
3 5-1/2x5-1/2 7	Porch Columns See Plan - - - - -			
2 5-1/2x5-1/2x2-3/4 7	Pilasters, Corner, See Plan - - - - -			
Outside Door Frames				
1 3/0x6/8x1-3/4	Front Door Frame D.C. - - - - -			
1 2/8x6/8x1-3/4	Rear Door Frame D.C. - - - - -			
1 2/6x6/8x1-3/4	Garage Door Frame D.C. - - - - -			
1 8/0x8/0	Garage Door Frame, No Headcasing - - - - -			
Window and Sash Frames				
4 10x12x1-1/8	3 Lt.Cellar Sash Frames Plank - - - - -			
4 8x12x1-3/8	20 Lt.Ck.Rail Window Frames P&P D.C. - - - - -			
1 8x10x1-3/8	16 Lt.Ck.Rail Window Frames P&P D.C. - - - - -			
2 8x10x1-3/8	16 Lt.Ck.Rail Window Frames P&P No Casings - - - - -			
3 8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -			
1 34x16x1-3/8	2 Lt.Ck.Rail Window Frames P&P D.C. - - - - -			
2 8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P No Headcasing - - - - -			
1 Triple	Bay Window Frame, Center 9x12 - 12 Lt.Ck.Rl. Sides 12x24" - 2 Lt.Ck.Rail P&P D.C.See Plan-			
Windows and Sash				
4 10x12x1-1/8	3 Lt.Cellar Sash Glz. - - - - -			
4 8x12x1-3/8	20 Lt.Ck.Rail Window Glz. Top Sash Div. 8 Lt. Bottom Sash Div. 12 Lt. - - - - -			
3 8x10x1-3/8	16 Lt.Ck.Rail Window Glz. - - - - -			
5 8x10x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -			
1 9x12x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -			
2 12x24x1-3/8	2 Lt.Ck.Rail Window Glz. Div. 8 Lt. - - - - -			
1 34x16x1-3/8	2 Lt.Ck.Rail Window Glz. Div. 16 Lt. - - - - -			
Blinds				
3 Pr.	Blinds For 8x12 - 20 Lt.Windows - - - - -			
2 Single	Blinds For 8x10 - 12 Lt.Windows - - - - -			
1 Pr.	Blinds For 8x10 - 16 Lt.Windows - - - - -			
1 Pr.	Blinds For 8x10 - 12 Lt.Windows - - - - -			

MATERIAL LIST FOR THE OCTOBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)					
Doors and Jambs For Main Rooms First Floor			FINISH HARDWARE		
1	3/0x6/8x1-3/4	Front Door Glz. See Plan - - - - -	4	Pr.	4x4
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	9	Pr.	3-1/2x3-1/2
1 Set	7/8x5-5/8	Door Jambs For 2/0x6/8 Door - - - - -	1	Pr.	2-1/2
2 Sets	7/8x5-5/8	Door Jambs For 4/0x6/8 C.O. - - - - -	1	Pr.	3-1/2x3-1/2
For Balance - First Floor			1	Pr.	2-1/2
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	1		
2	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	1		
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	1		
1	2/4x6/8x1-3/8	Inside Door 1 Side Panelled & 1 Side Metal Clad - - - - -	9		
1	2/6x6/8x1-3/4	Garage Door Glz. - - - - -	1		
4 Sets	7/8x5-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	1 Set	1-3/8"	
1 Set	8/0x8/0x1-3/4	Garage Doors, Overhead Type, Complete with Hardware & Equipment - Glz., See Plan - - - - -	2		
Doors and Jambs For Second Floor			15		
2	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	30		
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	2		
3	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	1		
6 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	1		
1 Set	12x16x7/8	Pipe Door, Jambs & Trim - - - - -	12		
Interior Finish, Main Rooms, First Floor			1		
1		Sides of Trim For 3/0x6/8 Door - - - - -	4 Doz.		
1		Sides of Trim For 2/0x6/8 Door - - - - -	4 Sets		
3		Sides of Trim For 4/0x6/8 C.O. - - - - -	Rough Hardware		
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	4	Hanks	
4		Sides of Trim For 8x12 - 20 Lt.Windows - - - - -	36	1/2x16"	
14 Lin.Ft.		Closet Base - - - - -	2	Sets 6"	
72 Lin.Ft.		Base - - - - -	400	Lbs.	
86 Lin.Ft.		Base Shoe - - - - -	Sash Cord - - - - -		
80 Lin.Ft.		Picture Mould - - - - -	Anchor Bolts With Nuts & Washers - - - - -		
14 Lin.Ft.		Hook Strips - - - - -	C.I.Post Caps & Sockets With Lag Screws - - - - -		
1 Pc.	3/6	Thresholds - - - - -	Sash Weights - - - - -		
Interior Finish: Balance of Rooms, First Floor			BUILDING PAPER		
1		Sides of Trim For 2/8x6/8 Door - - - - -	6	Rolls 50 Lb.	Building Paper (500 Ft.Rolls) For O.S. Walls and Floors - - - - -
3		Sides of Trim For 2/6x6/8 Door - - - - -	SHEET METAL MATERIAL		
1		Sides of Trim For 2/0x6/8 Door - - - - -	200	Sq.Ft.	Metal Roofing with Nails - - - - -
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	25	Lin.Ft. 14"	Valley Tin Flashing - - - - -
1		Sides of Trim For 2/6x6/8 Cellar Door - - - - -	150	10x12	Tin Shingles - - - - -
1		Sides of Trim For 2/4x6/8 Garage Door - - - - -	70	Pc. 5"	Gutter Eaves Trough - - - - -
1		Sides of Trim For Triple Bay Window, Center 9x12 - 12 Lt.Window, Sides 12x24 - 2 Lt. Windows, See Plan - - - - -	21	5"	Hangers - - - - -
1		Sides of Trim For 34x16 - 2 Lt.Windows - - - - -	8	Pc. 5"	End Caps - - - - -
4 Lin.Ft.		Window Stool Garage - - - - -	4	Pc. 5x3"	Drop Outlets - - - - -
16 Lin.Ft.		Window Stop Garage - - - - -	40	Lin.Ft. 3"	Conductor Pipe - - - - -
60 Lin.Ft.		Base - - - - -	10	Pc. 3"	Elbows - - - - -
78 Lin.Ft.		Base Shoe - - - - -	1	Doz. 3"	Conductor Pipe, Hooks - - - - -
35 Lin.Ft.		Picture Mould - - - - -	1	Pc. 3"	Funnel - - - - -
40 Lin.Ft.		Chair Rail - - - - -	4	Pc. 3"	Strainers - - - - -
14 Lin.Ft.		Hook Strips - - - - -	16	Lin.Ft.	Vents For Gas Flue - - - - -
6 Lin.Ft.		Thresholds - - - - -	NAILS		
18 Lin.Ft.		Closet Base - - - - -	85	Lbs. 20d	Common Nails - - - - -
Interior Finish: Second Floor			85	Lbs. 16d	Common Nails - - - - -
4		Sides of Trim For 2/6x6/6 Doors - - - - -	25	Lbs. 10d	Common Nails - - - - -
2		Sides of Trim For 2/4x6/6 Doors - - - - -	170	Lbs. 8d	Common Nails - - - - -
3		Sides of Trim For 2/0x6/6 Doors - - - - -	10	Lbs. 6d	Common Nails - - - - -
3		Sides of Trim For 2/0x6/6 Closet Doors - - - - -	5	Lbs. 10d	Casing Nails - - - - -
3		Sides of Trim For 8x10 - 16 Lt.Window - - - - -	45	Lbs. 8d	Casing Nails - - - - -
4		Sides of Trim For 8x10 - 12 Lt.Window - - - - -	5	Lbs. 6d	Casing Nails - - - - -
155 Lin.Ft.		Base - - - - -	10	Lbs. 10d	Finish Nails - - - - -
200 Lin.Ft.		Base Shoe - - - - -	15	Lbs. 8d	Finish Nails - - - - -
45 Lin.Ft.		Closet Base - - - - -	5	Lbs. 6d	Finish Nails - - - - -
122 Lin.Ft.		Picture Mould - - - - -	2	Lbs. 4d	Finish Nails - - - - -
26 Lin.Ft.		Chair Rail - - - - -	1	Lb. 7/8"	Finish Brads (16 Gauge) - - - - -
40 Lin.Ft.		Hook Strips - - - - -	55	Lbs. 3d	Shingle Nails Hot Dipped Zinc Coated - - - - -
Main Stairs			40	Lbs. 8d	Cement Coated Nails For Siding - - - - -
2		Circle End Tread & Riser, See Plan - - - - -	2	Lbs. 3d	Fine Lath Nails - - - - -
11		Treads - - - - -	5	Lbs. 20d	Cut Nails For Furring - - - - -
12		Risers - - - - -	PAINT		
3		Landing Treads - - - - -	7	Gals.	Outside Body Paint - - - - -
28 Lin.Ft.		Wall String (2 Mem.) - - - - -	3	Gals.	Outside Trim Paint - - - - -
14 Lin.Ft.		Wall Rail - - - - -	1	Gals.	Porch Ceiling Paint - - - - -
3		Wall Rail Brackets - - - - -	1/2	Gals.	Blind or Shutter Paint - - - - -
2		Stair Rail Acorn Ends - - - - -	1	Gals.	Sheet Metal Paint (Mineral) - - - - -
Miscellaneous			1	Gals.	Paint For Brick Work Undercoat - - - - -
60 Lin.Ft.		Stair Cove Moulding - - - - -	6	Gals.	Floor Varnish - - - - -
Cabinets			5	Gals.	Inside Varnish - - - - -
1		Mantel Shelf & Trim - - - - -	1/2	Gals.	Spar Varnish - - - - -
1		Medicine Cabinet - - - - -	1/4	Gals.	Shellac - - - - -
2		Kitchen Cabinets Over Worktable With Hdwe., See Plan - - - - -	2-1/2	Gals.	Liquid Wood Filler - - - - -
2		Kitchen Worktables Complete with Hdwe., See Pl	1/2	Gals.	Flat White - - - - -
			1	Gals.	White Enamel - - - - -
			1	Gals.	Paint For Brick Work - Top Coat - - - - -
			2	Gals.	Boiled Linseed Oil - - - - -
			2	Gals.	Turpentine - - - - -
			25	Lbs.	Putty - - - - -

MATERIAL LIST FOR THE OCTOBER 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills For Foundation				Lath			
2 Pc.	2x6-16	Garage - - - - -	32	50	48"	Lath For Exterior Furrings - - - - -	
4 Pc.	2x6-14	Main Building & Garage - - - - -	56	Outside Finish Lumber			
2 Pc.	2x6-12	Main Building & Garage - - - - -	24	42 Ft.	1x8	Frieze - - - - -	42
12 Pc.	2x6-10	Main Building - - - - -	120	50 Ft.	1x6	Frieze - - - - -	50
6 Pc.	2x6-8	Main Building - - - - -	48	1 Pc.	1x10-8	Frieze, Cut To Curve - - - - -	7
Girders and Lintels				9 Pc.	1x6-12	V.Siding For Blinds - - - - -	54
1 Pc.	6x8-16	Main Building - - - - -	64	2 Pc.	1x6-8	V.Siding For Blinds - - - - -	8
1 Pc.	6x8-14	Main Building - - - - -	56	2 Pc.	1x4-12	Blind Cleats - - - - -	8
2 Pc.	2x10-20	Front Porch Roof Beam - - - - -	67	48 Ft.	1x10	Porch Lintle Frieze - - - - -	48
1 Pc.	2x10-12	Front Porch Roof Beam Cut - - - - -	20	15 Ft.	1x6	Porch Lintle Frieze - - - - -	15
Girder Posts				10 Ft.	1x4	Porch Lintle Soffit - - - - -	10
2 Pc.	6x6-7	Main Building - - - - -	42	1 Pc.	1x3-8	Water Table - - - - -	2
Floor Joists, Headers and Trimmers				7 Pc.	6x6-7	Porch Columns - - - - -	147
27 Pc.	2x10-14	First Floor Main Building - - - - -	630	20 Ft.1x4 to 1x10	Miscellaneous - - - - -		20
9 Pc.	2x10-18	First Floor Main Building - - - - -	270	Inside Finish Lumber			
8 Pc.	2x10-10	First Floor Headers - - - - -	133	5 Pc.	1x12-10	Shelving - - - - -	50
1 Pc.	2x10-12	First Floor Box Sills - - - - -	20	3 Pc.1-1/4x10-14	Cellar Stair Treads - - - - -		44
2 Pc.	2x10-8	First Floor Box Sills - - - - -	27	3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
12 Pc.	2x10-18	Second Floor Main Building - - - - -	360	1 Pc.	2x4-12	Cellar Stair Rails & Newel - - - - -	8
26 Pc.	2x10-14	Second Floor Main Building - - - - -	607	20 Ft.	1x4	Garage Trim (Inside) - - - - -	20
7 Pc.	2x10-12	Second Floor Main Building - - - - -	140				
3 Pc.	2x10-10	Second Floor Headers - - - - -	50	Quantity	Size	ARTICLE AND DESCRIPTION	
Ceiling Joists				INSULATION			
17 Pc.	2x6-16	Main Building - - - - -	272	2150 Sq.Ft.		Insulating Material - - - - -	
6 Pc.	2x6-9	Main Building - - - - -	54	MASONRY MATERIAL			
4 Pc.	2x4-14	Garage Ceiling Joists Cut - - - - -	37	Concrete Foundation 1-3-5 Mixture - 780 Cu.Ft.			
16 Pc.	2x4-6	Front Porch - - - - -	64	23-1/4 Cu.Yds.		Crushed Stone or Gravel - - - - -	
2 Pc.	2x10-12	Garage Door Beams - - - - -	40	14 Cu.Yds.		Coarse Sand - - - - -	
Outside Studs				33 Bbls.		Portland Cement - - - - -	
110 Pc.	2x4-10	Main Building & Garage - - - - -	733	Stone Work			
14 Pc.	2x4-8	Garage - - - - -	75	170 Sq.Ft. 4"		Flagstone - - - - -	
22 Pc.	2x4-10	Gables Main - - - - -	147	Cement Floor and Steps 1-3-5 Mixture - 825 Sq.Ft.			
8 Pc.	2x4-6	Gables Garage - - - - -	32	8-1/4 Cu.Yds.		Crushed Stone or Gravel - - - - -	
1 Pc.	2x4-8	Porch Gables - - - - -	5	5-1/2 Cu.Yds.		Coarse Sand - - - - -	
40 Pc.	2x4-6	Dormers - - - - -	160	12-1/2 Bbls.		Portland Cement - - - - -	
14 Pc.	2x6-6	Window Lintels - - - - -	84	Chimneys and Fireplace			
2 Pc.	2x6-10	Bay Window Lintels - - - - -	20	6000		Common Brick - - - - -	
Inside Studs				60		Faces Brick For Fireplace - - - - -	
72 Pc.	2x4-8	First Floor - - - - -	384	120		Fire Clay Brick - - - - -	
2 Pc.	2x6-8	First Floor - - - - -	16	5-1/2 Cu.Yds.		Sand - - - - -	
4 Pc.	2x6-6	First Floor C.O.Headers - - - - -	24	5-1/2 Bbls.		Lime - - - - -	
2 Pc.	2x6-8	Second Floor - - - - -	16	1 Bbl.		Portland Cement - - - - -	
58 Pc.	2x4-8	Second Floor - - - - -	309	50 Lbs.		Fire Clay - - - - -	
12 Pc.	2x4-10	Second Floor Cut - - - - -	80	28 Lin.Ft. 8x12"		Flus Lining - - - - -	
Stud and Partition Plates				20 Lin.Ft. 12x12"		Flus Lining - - - - -	
35 Pc.	2x4-14	Outside Walls - - - - -	327	15 Sq.Ft. 1/2"		Wire Mesh Reinforcing For Hearth - - - - -	
42 Pc.	2x4-12	Inside Partitions - - - - -	336	1		Damper - - - - -	
1 Pc.	2x6-8	Inside Partitions - - - - -	8	1		Ash Dump - - - - -	
8 Pc.	2x4-12	Fire Stops - - - - -	64	1		Cleanout Door - - - - -	
Rafters				1	4x4x1/4"	Angle Iron 4'2" Long - - - - -	
9 Pc.	2x6-22	Main Building - - - - -	198	Plastering			
16 Pc.	2x6-20	Main Building - - - - -	320	445 Yds.		Plaster, Including Plaster Base, Nails, Metal Lath Corner Strips and Metal Corner Beads - - - - -	
8 Pc.	2x6-16	Main Building - - - - -	128	82 Yds.		Cement Plaster, Including Metal Lath & Staples For Garage & Over Boiler Space - - - - -	
26 Pc.	2x6-8	Main Building & Garage - - - - -	208	MILLWORK			
5 Pc.	2x4-8	Bays - - - - -	27	Outside Millwork and Mouldings			
16 Pc.	2x6-8	Front Porch - - - - -	128	20 Lin.Ft.		Crown Moulding - - - - -	
11 Pc.	1x10-10	Front Porch Cut to Curve - - - - -	92	200 Lin.Ft.		Bed Moulding - - - - -	
18 Pc.	2x6-14	Dormers - - - - -	252	60 Lin.Ft.		Cove Moulding - - - - -	
2 Pc.	2x8-10	Valley Rafters Garage - - - - -	27	40 Lin.Ft.		1/4 Round Moulding - - - - -	
2 Pc.	2x6-10	Valley Rafters & Hip Rafters - - - - -	20	12		Porch Brackets, See Plan - - - - -	
2 Pc.	1x8-16	Ridge Boards - - - - -	21	Outside Door Frames			
1 Pc.	1x8-10	Ridge Boards - - - - -	7	1	3/0x6/8x1-3/4	Front Door Frame D.C. - - - - -	
1 Pc.	1x6-8	Ridge Boards - - - - -	4	1	2/8x6/8x1-3/4	Rear Door Frame D.C. - - - - -	
Step and Stair Carriages				1	2/6x6/8x1-3/4	Garage Door Frame D.C. - - - - -	
2 Pc.	2x10-14	Cellar Stairs - - - - -	47	1	8/0x8/0	Garage Door Frame, No Head Casing - - - - -	
2 Pc.	2x10-16	Main Stairs - - - - -	53	Window and Sash Frames			
2 Pc.	2x6-16	Main Stairs Platform - - - - -	32	4	10x12x1-1/8	3 Lt.Cellar Sash Frames - - - - -	
Sheathing, Boards, Sub-flooring, Furring, Etc.,				4	8x12x1-3/8	20 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
840 Ft.	1x4	Roof Sheathing S.2.S; Laid 4-1/2" O.C. 840		3	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
450 Ft.	1x6	Roof Sheathing D&M Over Rooms & Dormers - - - - -	450	2	34x16x1-3/8	2 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	
1300 Ft.	1x6	Sub-flooring D&M Laid Diagonally - - - - -	1300	1	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P No Headcasing - - - - -	
1950 Ft.	1x8	Box Sheathin O.S.Walls Shiplap Laid Diagonally - - - - -	1950	1	8x10x1-3/8	12 Lt.Ck.Rail Mull Frame D.C. - - - - -	
175 Ft.	1x6	Ribbons, Backing & Furring - - - - -	175	1	8x10x1-3/8	16 Lt.Ck.Rail Single Frame P&P Special Casing See Plan - - - - -	
12 Pc.	1x2-8	Furring Inside Walls At Chimney - - - - -	12	1	Triple	Bay Window Frame, Center 9x12 - 12 Lt.Ck.Rail Sides 12x24" - 2 Lt. Ck.Rail P&P D.C. See Plan - - - - -	
1000 Lin.Ft.	1x1	Ground 'Around Inside Openings) - - - - -	83	Windows and Sash			
95 Ft.	1x4	Bridging - - - - -	95	4	10x12x1-1/8	3 Lt.Cellar Sash Glz. - - - - -	
70 Ft.	1x2	Floor Stripping On 2nd Floor Only - - - - -	70	4	8x12x1-3/8	20 Lt.Ck.Rail Window Glz. Top Sash Div. 8 Lt. Bottom Div. 12 Lt. - - - - -	
Siding For Outside Walls				1	8x10x1-3/8	16 Lt.Ck.Rail Window Glz. - - - - -	
50 Ft. 3/4x8"		Bev.Siding Rough Cut - - - - -	50	7	8x10x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
200 Ft.		"V" Vertical Siding - Random Widths - 8'0" Long for Living Room Wall - - - - -	200	1	34x16x1-3/8	2 Lt.Ck.Rail Window Glz. Div.16 Lt. - - - - -	
13-1/2 Squares 24"		Wall Shingles Certigrade Red Cedar (Double Course) Stained Laid 11" Exp. - - - - -		2	12x24x1-3/8	2 Lt.Ck.Rail Window Glz. 8 Lt. - - - - -	
Flooring and Ceiling				1	9x12x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	
450 Ft. 3/4x3-1/4		Flooring, Main Rooms First Floor - - - - -	450				
140 Ft. 3/4x3-1/4		Flooring, Balance First Floor - - - - -	140				
650 Ft. 3/4x3-1/4		Flooring, Second Floor - - - - -	650				
140 Ft. 5/8x3-1/4		Ceiling Porches - - - - -	140				
Shingles							
11-1/2 Squares 5/2		16" Shingles For Roof Certigrade Red Cedar 4-1/2" Exposure - - - - -					

MATERIAL LIST FOR THE OCTOBER 1938 CITY CALENDAR (ALTERNATE)

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)					
Doors and Jambs For Main Rooms First Floor			FINISH HARDWARE		
1	3/0x6/8x1-3/4	Front Door "V" Joint Glz. See Plan - - - - -	4		Cellar Sash Sets - - - - -
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	4	Pr. 4x4	Door Butts - - - - -
1	Set 7/8x5-5/8	Door Jambs For 2/0x6/8 Door - - - - -	9	Pr. 3-1/2x3-1/2	Door Butts - - - - -
2	Sets 7/8x5-5/8	Door Jambs For 4/0x6/8 C.O. - - - - -	1	Pr. 2-1/2	Cupboard Door Butts, Narrow - - - - -
For Balance - First Floor			1	Pr. 3-1/2x3-1/2	Bathroom Door Butts - - - - -
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	1	Pr. 2-1/2	Medicine Cabinet Butts, Narrow - - - - -
2	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	1		Front Door Lock Set - - - - -
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	1		Rear Door Lock Set - - - - -
1	2/4x6/8x1-3/8	Inside Door, 1 Side Panelled & 1 Side Metal Clad - - - - -	9		Garage Door Lock Set - - - - -
1	2/6x6/8x1-3/4	Garage Door Glz. - - - - -	1		Inside Door Lock Sets - - - - -
4	Sets 7/8x5-5/8	Door Jambs For 2/6x6/8 & Smaller Doors - - - - -	1	Set 1-3/8"	Bathroom Door Lock Set - - - - -
1	Set 8/0x8/0x1-3/4	Garage Doors, Overhead Type, Glazed Complete with Hdwe., & Equipment, See Plan - - - - -	2		Floor Double Acting Hinge - - - - -
Doors and Jambs For Second Floor			15		Push Plates - - - - -
2	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	30		Sash Locks - - - - -
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	2		Sash Lifts - - - - -
3	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	1		Sash Lifts, Bathroom - - - - -
6	Sets 7/8x5-5/8	Door Jambs For 2/6x6/6 & Smaller Doors - - - - -	1		Sash Lock, Bathroom - - - - -
1	12x16x7/8	Pipe Door, Jamb & Trim - - - - -	12		Cupboard, Turn - - - - -
Interior Finish: Main Rooms, First Floor			1		Cupboard Turn, Med. Case - - - - -
1		Sides of Trim For 3/0x6/8 Door - - - - -	12		Metal Base Knobs - - - - -
1		Sides of Trim For 2/0x6/8 Door - - - - -	1		Metal Base Knobs, Bathroom - - - - -
3		Sides of Trim For 4/0x6/8 C.O. - - - - -	1		Coat and Hat Hooks - - - - -
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	4	Doz.	W.I. Hinge Plates - - - - -
4		Sides of Trim For 8x12 - 20 Lt. Windows - - - - -	3		Window Blinds Hangers With Fasteners - - - - -
14	Lin. Ft.	Closet Base - - - - -	4		
72	Lin. Ft.	Base - - - - -	Rough Hardware		
86	Lin. Ft.	Base Shoe - - - - -	4	Hanks	Sash Cord - - - - -
80	Lin. Ft.	Picture Mould - - - - -	36	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
14	Lin. Ft.	Hook Strips - - - - -	2	Sets 6"	C.I. Post Caps & Sockets, With Lag Screws - - - - -
1	Pc. 3/6	Thresholds - - - - -	400	Lbs.	Sash Weights - - - - -
Interior Finish: Balance of Rooms, First Floor			BUILDING PAPER		
1		Sides of Trim For 2/8x6/8 Door - - - - -	6	Rolls 50	Lbs. Building Paper (500 Ft. Rolls) For Walls and Ceilings - - - - -
3		Sides of Trim For 2/6x6/8 Door - - - - -	SHEET METAL MATERIAL		
1		Sides of Trim For 2/0x6/8 Door - - - - -	200	Sq. Ft.	Metal Roofing with Nails - - - - -
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	50	Lin. Ft. 14"	Valley Tin Flashing - - - - -
1		Sides of Trim For 2/6x6/8 Cellar Door - - - - -	100	10x12"	Tin Shingles - - - - -
1		Sides of Trim For 2/4x6/8 Garage Door - - - - -	60	Ft. 5"	Gutter Eaves Trough - - - - -
1		Sides of Trim For 34x16 - 2 Lt. Window - - - - -	18	Pc. 5"	Hangers - - - - -
1		Sides of Trim For Triple Bay Window, Center 9x12 - 12 Lt. Window - Sides 12x24 - 2 Lt. Windows, See Plan - - - - -	11	Pc. 5"	End Caps - - - - -
4	Lin. Ft.	Window Stool - Garage - - - - -	6	Pc. 5x3"	Drop Outlets - - - - -
16	Lin. Ft.	Window Stop Garage - - - - -	50	Ft. 3"	Conductor Pipe, - - - - -
60	Lin. Ft.	Base - - - - -	12	Pc. 3"	Elbows - - - - -
78	Lin. Ft.	Base Shoe - - - - -	15	Pc. 3"	Conductor Pipe, Hooks - - - - -
35	Lin. Ft.	Picture Mould - - - - -	1	Pc. 3"	Funnel - - - - -
Interior Finish: Balance of Rooms, First Floor			6	Pc. 3"	Strainers - - - - -
40	Lin. Ft.	Chair Rail - - - - -	16	Lin. Ft.	Vents For Gas Flue - - - - -
14	Lin. Ft.	Hook Strips - - - - -	NAILS		
6	Lin. Ft.	Thresholds - - - - -	85	Lbs. 20d	Common Nails - - - - -
18	Lin. Ft.	Closet Base - - - - -	85	Lbs. 16d	Common Nails - - - - -
Interior Finish: Second Floor			25	Lbs. 10d	Common Nails - - - - -
4		Sides of Trim For 2/6x6/6 Doors - - - - -	170	Lbs. 8d	Common Nails - - - - -
2		Sides of Trim For 2/4x6/6 Doors - - - - -	10	Lbs. 6d	Common Nails - - - - -
3		Sides of Trim For 2/0x6/6 Doors - - - - -	5	Lbs. 10d	Casing Nails - - - - -
3		Sides of Trim For 2/0x6/6 Closet Doors - - - - -	45	Lbs. 8d	Casing Nails - - - - -
4		Sides of Trim For 8x10 - 12 Lt. Windows - - - - -	5	Lbs. 6d	Casing Nails - - - - -
1		Sides of Trim For 8x10 - 16 Lt. Windows - - - - -	10	Lbs. 10d	Finish Nails - - - - -
1		Sides of Trim For 8x10 - 12 Lt. Mull Windows - - - - -	15	Lbs. 8d	Finish Nails - - - - -
150	Lin. Ft.	Base - - - - -	5	Lbs. 6d	Finish Nails - - - - -
200	Lin. Ft.	Base Shoe - - - - -	2	Lbs. 4d	Finish Nails - - - - -
45	Lin. Ft.	Closet Base - - - - -	1	Lb. 7/8"	Finish Brads (16 Gauge) - - - - -
120	Lin. Ft.	Picture Mould - - - - -	55	Lbs. 3d	Shingle Nails Hot Dipped Zinc Coated - - - - -
26	Lin. Ft.	Chair Rail - - - - -	5	Lbs. 8d	Cement Coated Nails For Siding - - - - -
40	Lin. Ft.	Hook Strips - - - - -	2	Lbs. 3d	Fine Lath Nails - - - - -
Main Stair			70	Lbs. 5d	Shingle Nails - Hot Dipped Zinc Coated - - - - -
2		Circle End Treads & Risers, See Plan - - - - -	5	Lbs. 20d	Cut Nails For Furring - - - - -
11		Treads - - - - -	PAINT		
12		Risers - - - - -	1/2	Gals.	Outside Body Paint - - - - -
3		Landing Treads - - - - -	3	Gals.	Outside Trim Paint - - - - -
20	Lin. Ft.	Wall String (2 Mem.) - - - - -	1	Gals.	Porch Ceiling Paint - - - - -
14	Lin. Ft.	Wall Rail - - - - -	1/2	Gals.	Blind or Shutter Paint - - - - -
3		Wall Rail Brackets - - - - -	1	Gals.	Sheet Metal Paint (Mineral) - - - - -
2		Stair Rail Acorn Ends - - - - -	5	Gals.	Inside Varnish - - - - -
Miscellaneous			6	Gals.	Floor Varnish - - - - -
60	Lin. Ft.	Stair Cove Moulding - - - - -	1/2	Gals.	Spar Varnish - - - - -
Cabinets			1/4	Gals.	Shellac - - - - -
1		Mantel Shelf & Trim, See Plan - - - - -	2-1/2	Gals.	Liquid Wood Filler - - - - -
1		Medicine Cabinet - - - - -	1/2	Gals.	Flat White - - - - -
2		Kitchen Cabinets Over Worktable, With Hdwe., See Plan - - - - -	1	Gals.	White Enamel - - - - -
2		Kitchen Worktable, Complete with Hdwe., See Plan - - - - -	1	Gals.	Boiled Linseed Oil - - - - -
			2	Gals.	Turpentine - - - - -
			20	Lbs.	Putty - - - - -

MATERIAL LIST FOR THE NOVEMBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates or Sills for Foundation				Outside Finish Lumber			
2 Pc.	2x6-16	Main Building - - - - -	32	70 Ft.	1x6	Plancier & Frieze - - - - -	70
2 Pc.	2x6-14	Main Building - - - - -	28	1 Pc.	1-1/4x6-14	Belt Course - - - - -	8
10 Pc.	2x6-12	Main Building - - - - -	120	50 Ft.	1x6	For Blinds - - - - -	50
2 Pc.	2x6-10	Main Building - - - - -	20	2 Pc.	1x10-10	Porch Gable Frieze Cut to Curve - - -	17
Girdere and Lintlee				50 Ft.	1-1/4x8"	Stucco Panel Boards - - - - -	50
1 Pc.	6x8-20	Main Building - - - - -	80	90 Ft.	1-1/4x6"	Stucco Panel Boarde - - - - -	90
Girder Posts				1 Pc.	4x6-12	Entrance Beams - - - - -	24
2 Pc.	6x6-7	Main Building - - - - -	42	2 Pc.	4x8-7	Entrance Poete - - - - -	37
Floor Joists, Headers and Trimmere				1 Pc.	4x8-8	Entrance Poets - - - - -	21
31 Pc.	2x10-16	First Floor Main Building - - - - -	826	2 Pc.	4x6-8	Entrance Poets - - - - -	32
12 Pc.	2x10-9	First Floor Main Building - - - - -	180	20 Ft.	1x6	Porch Lintle Soffit - - - - -	20
8 Pc.	2x10-6	First Floor Main Building - - - - -	80	4 Pc.	6x6-8	Rear Porch Poete - - - - -	96
1 Pc.	2x10-14	Hearth Headere - - - - -	23	1 Pc.	6x8-12	Rear Porch Beams - - - - -	48
1 Pc.	2x4-10	Hearth Floor Support - - - - -	7	1 Pc.	6x8-14	Rear Porch Beams - - - - -	56
1 Pc.	2x10-18	First Floor Box Sills - - - - -	30	25 Ft.	1x4 to 1x10	Miscellaneous O.S.Finish - - - - -	25
1 Pc.	2x10-16	First Floor Box Sille - - - - -	27	Inside Finish Lumber			
2 Pc.	2x10-12	First Floor Box Sille - - - - -	40	3 Pc.	1x12-10	Shelving - - - - -	30
8 Pc.	2x4-14	Fire Stope - - - - -	75	3 Pc.	1-1/4x10-14	Cellar Stair Treads - - - - -	44
16 Pc.	2x10-16	Second Floor Main Building - - - - -	426	3 Pc.	1x8-14	Cellar Stair Riseere - - - - -	28
2 Pc.	2x10-14	Second Floor Main Building - - - - -	47	2 Pc.	2x4-12	Cellar Stair Raile & Newels - - - - -	16
20 Pc.	2x10-12	Second Floor Main Building - - - - -	400	2 Pc.	1x4-8	Cellar Stair Raile - - - - -	5
8 Pc.	2x10-6	Second Floor Main Building - - - - -	80				
Ceiling Joiets				Quantity	Size	ARTICLE AND DESCRIPTION	
24 Pc.	2x6-12	Main Building - - - - -	288	INSULATION			
9 Pc.	2x6-8	Main Building - - - - -	72	2100 Sq.Ft.		Insulating Material - - - - -	
7 Pc.	2x4-8	Rear Porch - - - - -	37	MASONRY MATERIAL			
Outside Studs				Concrete Foundation 1-3-5 Mixture - 624 Cu.Ft.			
112 Pc.	2x4-14	Main Building - - - - -	1047	25 Cu.Yde.		Crushed Stone or Gravel - - - - -	
36 Pc.	2x4-8	Main Building Front - - - - -	192	15 Cu.Yds.		Coarse Sand - - - - -	
12 Pc.	2x4-14	Gablee - - - - -	112	36 Bbls.		Portland Cement - - - - -	
6 Pc.	2x4-6	Gablee - - - - -	24	Stone Work			
4 Pc.	2x4-10	Gables, Blocking - - - - -	27	110 Sq.Ft.	4"	Flagstone - - - - -	
8 Pc.	2x4-6	Porch Gables - - - - -	32	30 Sq.Ft.	8"	Flagetone - - - - -	
20 Pc.	2x4-6	Dormers - - - - -	80	Cement Floor and Steps 1-3-5 Mixture - 651 Sq.Ft.			
6 Pc.	2x6-14	Window & Door Lintlee - - - - -	84	6-3/4 Cu.Yds.		Crushed Stone or Gravel - - - - -	
Inside Stude				4-1/2 Cu.Yds.		Coarse Sand - - - - -	
54 Pc.	2x4-8	First Floor - - - - -	288	10 Bble.		Portland Cement - - - - -	
4 Pc.	2x6-8	First Floor - - - - -	32	Brick Work			
2 Pc.	2x6-10	Arch Headers - - - - -	20	4350		Common Brick - - - - -	
50 Pc.	2x4-8	Second Floor - - - - -	267	2050		Face Brick - - - - -	
6 Pc.	2x6-8	Second Floor - - - - -	48	6-1/2 Bbls.		Lime - - - - -	
Stud and Partition Plates				6-1/2 Cu.Yds.		Sand - - - - -	
23 Pc.	2x4-14	Outside Walls - - - - -	215	1 Bbl.		Portland Cement - - - - -	
26 Pc.	2x4-12	Inside Partitions - - - - -	208	Cut Stone			
3 Pc.	2x6-10	Inside Partitions - - - - -	30	1 Set		Rough Cut Stone Work For Lower Chimney Ledger	
1 Pc.	2x6-12	Porch Platee - - - - -	12	1 Set		Rough Cut Stone Work For Center Chimney Ledger	
1 Pc.	2x4-12	Porch Platee - - - - -	8	1 Set		Rough Cut Stone Work For Top Chimney Ledger -	
Rafters				1 Set		Rough Cut Stone Work For Chimney Cap, See Pl.	
12 Pc.	2x6-22	Main Building - - - - -	264	Fireplace			
40 Pc.	2x6-14	Main Building - - - - -	560	55		Face Brick - - - - -	
18 Pc.	2x6-10	Main Building - - - - -	180	120		Fire Clay Brick - - - - -	
6 Pc.	2x4-6	Front Entrance - - - - -	24	50 Lbs.		Fire Clay - - - - -	
6 Pc.	1x8-6	Front Entrance Cut to Curve - - - - -	24	54 Lin.Ft.	8x12"	Flue Lining - - - - -	
10 Pc.	2x8-6	Rear Porch Cut to Curve - - - - -	80	15 Sq.Ft.	1/2"	Wire Mesh Reinforcing For Hearth - - -	
12 Pc.	2x4-6	Dormers - - - - -	48	1		Damper - - - - -	
1 Pc.	2x6-8	Hip Rafters - - - - -	8	1		Ash Dump - - - - -	
2 Pc.	2x8-12	Valley Raftere - - - - -	32	1		Cleanout Door - - - - -	
1 Pc.	2x6-8	Valley Rafters - - - - -	8	1		Angle Iron 3'8" Long - - - - -	
2 Pc.	1x8-16	Ridge Boards - - - - -	21	Plastering			
1 Pc.	1x8-14	Ridge Boards - - - - -	9	450 Yds.		Plaster, Including Plaster Bacee, Naile, Metal	
10 Pc.	2x4-9	Partition Truee - - - - -	60	12 yds.		Lath Corner Strips, and Metal Corner Beads -	
Step and Stair Carriages						Cement Plaeter, Including Metal Lath &	
2 Pc.	2x10-14	Cellar Staire -, - - - -	47			Staples For Over Boiler Space - - -	
2 Pc.	2x10-16	Main Staire - - - - -	53	Exterior Stucco			
2 Pc.	2x6-12	Main Staire Platform - - - - -	24	17 Sq.Yds.		Stucco, Including Metal Lath & Staples - - -	
Sheathing, Boarde, Sub-flooring, Furring, Etc.,				ORNAMENTAL IRON			
780 Ft.	1x4	Roof Sheathing S.2.S.4-1/2"O.C. - - -	780	1		Ornamental Chimney Anchor, See Plan - - - -	
540 Ft.	1x6	Roof Sheathing D&M - - - - -	540	MILLWORK			
1510 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally - 1510		Outside Millwork and Mouldings			
2000 Ft.	1x8	Box Sheathing O.S.Walle Shiplap		225 Lin.Ft.		Bed Moulding - - - - -	
		Laid Diagonally - 2000		50 Lin.Ft.		Cove Moulding - - - - -	
175 Ft.	1x6	Ribbone, Backing & Furring - - - - -	175	20 Lin.Ft.		1/4 Round Moulding - - - - -	
10 Pc.	1x2-10	Furring Outside Walls For Stucco - - -	17	30 Lin.Ft.		Drip Cap - - - - -	
14 Pc.	1x2-8	Furring Inside Walls For Brick Walle -	19	6		Porch Brackets, See Plan - - - - -	
900 Lin.Ft.	1x1	Ground (Around Inside Opening) - - -	75	6		Cornice Brackets, See Plan - - - - -	
80 Ft.	1x4	Bridging - - - - -	80	5		Dormer Brackets, See Plan - - - - -	
70 Ft.	1x2	Floor Stripping On 2nd Floor Only - -	70	Outside Door Frames			
Siding For Outside Walls				1 3/0x6/8x1-3/4		Front Door Frame For 9" Brick Wall - - - -	
90 Ft.	3/4x10"	Bev.Siding Rustic, 1-1/2" Lap. - - -	90	1 2/8x6/8x1-3/4		Rear Door Frame D.C. - - - - -	
12 Squares	24"	Stained Wall Shingles Certigrade Red		1 4/0x6/8x1-3/4		French Door Frame D.C. - - - - -	
		Cedar 10" Exposure, Double Couree - -					
Flooring and Ceiling							
475 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor - -	475				
170 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - -	170				
650 Ft.	3/4x3-1/4	Flooring, Second Floor - - - - -	650				
100 Ft.	5/8x3-1/4	Ceiling Porches - - - - -	100				
Shingles							
12 Squares	16"	Shinglee For Roof Certigrade Red Cedar					
		4-1/2" Exp. - - - - -					
Lath							
50	48"	Exterior Lath For Gable Furring - - -					

MATERIAL LIST FOR THE NOVEMBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			MILLWORK (CONTINUED)		
Window and Sash Frames			Miscellaneous		
4	10x18x1-1/8	3 Lt.Cellar Sash Frames Plank - - - - -	70	Lin.Ft.	Stair Cove Moulding - - - - -
1	8x12x1-3/8	12 Lt.Ck.Rail Window Frames P&P No Headcasing - - - - -	Cabinets		
3	8x10x1-3/8	12 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	1		Mantel Shelf With Trim & Brackets, See Plan -
1	32x16x1-3/8	2 Lt.Ck.Rail Window Frames P&P D.C. - - - - -	1		Medicine Cabinet - - - - -
			1		Linen Cabinet, See Plan - - - - -
1	3/4x4/3x1-3/8	0.S.Dormer Sash Frame See Plan - - - - -	1		Kitchen Cabinet Over Ref.Space With Hdwe., See Plan - - -
2	2/0x4/3x1-3/8	0.S.Sash Frame Stucco Wall, No Casing - - - - -	1		Combination Kitchen Cabinet and Worktable, Complete with Hdwe.,
1	2/6x2/3x1-3/8	0.S.Sash Frame No Casing, See Plan - - - - -	1		Broom Closet - - - - -
1	3/4x4/6x1-3/8	0.S.Sash Frame D.C. - - - - -	FINISH HARDWARE		
2	1/10x4/6x1-3/8	0.S.Sash Frame D.C. - - - - -	4		Cellar Sash Sets - - - - -
3	1/6x4/6x1-3/8	0.S.Triple Sash Frame D.C. - - - - -	6	Pr. 4x4	Door Butts - - - - -
Windows and Sash			7	Pr. 3-1/2x3-1/2	Door Butts - - - - -
4	10x18x1-1/8	3 Lt.Cellar Sash Glz. - - - - -	18	Pr. 3x3	Casement Sash Butts - - - - -
1	8x12x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	1	Pr. 2-1/2	Cupboard Door Butts, Narrow - - - - -
3	8x10x1-3/8	12 Lt.Ck.Rail Window Glz. - - - - -	1	Pr. 3-1/2x3-1/2	Bathroom Door Butts - - - - -
1	32x16x1-3/8	2 Lt.Ck.Rail Window Glz. - - - - -	1	Pr. 2-1/2	Medicine Cabinet Butts, Narrow - - - - -
9	1/6x4/6x1-3/8	Sash Glz. Div. 8 Lt. - - - - -	1		Front Door Lock Set - - - - -
2	1/10x4/6x1-3/8	Sash Glz. Div. 8 Lt. - - - - -	1		Rear Door Lock Set - - - - -
1	Pr. 3/4x4/6x1-3/8	0.S.Sash Glz. Div. 8 Lt.Each - - - - -	8		Inside Door Lock Sets - - - - -
1	Pr. 3/4x4/3x1-3/8	0.S.Sash Glz. Leaded, See Plan - - - - -	1		Bathroom Door Lock Set - - - - -
2	2/0x4/3x1-3/8	Sash Glz. Leaded, See Plan - - - - -	1	Double	French Door Lock Set Rab't.Face - - - - -
1	2/6x2/3x1-3/8	0.S.Sash Glz. Leaded, See Plan - - - - -	1	Set 1-3/8"	Floor Double Acting Hinge - - - - -
Doors and Jambs For Main Rooms First Floor			2		Push Plates - - - - -
1	3/0x6/8x1-3/4	Front Door V Joint Glz. See Plan - - - - -	14	Sets	Casement Sash Fasteners, Single - - - - -
2	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	2	Sets	Casement Sash Fasteners, Double - - - - -
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	4		Sash Locks - - - - -
1	Pr. 4/0x6/8x1-3/4	French Doors, Glz. 10 Lt.Each - - - - -	8		Sash Lifts - - - - -
2	Sets 7/8x5-5/8	Door Jambs For 2/6x6/8 Doors - - - - -	2		Sash Lifts, Bathroom - - - - -
1	Set 7/8x3-5/8	Door Jambs For 2/0x6/8 Doors - - - - -	1		Sash Lock, Bathroom - - - - -
For Balance - First Floor			2		Flush Bolts - - - - -
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	1		Cupboard Turn - - - - -
1	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	1		Cupboard Turn, Med.Case - - - - -
1	Set 7/8x5-5/8	Door Jambs For 2/6x6/8 Door - - - - -	9		Metal Base Knobs - - - - -
Doors and Jambs For Second Floor			1		Metal Base Knobs, Bathroom - - - - -
2	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	3	Doz.	Coat and Hat Hooks - - - - -
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	3		W.I.Hinge Plates - - - - -
2	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	5	Sets	Window Blinds Hangers - - - - -
1	2/6x4/6x1-3/8	Inside Door Panelled - - - - -	Rough Hardware		
6	Sets 7/8x5-5/8	Door Jambs For 2/6x6/6 Doors & Smaller - - - - -	1	Hanks	Sash Cord - - - - -
1	Set 12x16x7/8	Pipe Door, Jambs & Trim - - - - -	28	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
Interior Finish: Main Rooms, First Floor			2	Sets 6"	C.I.Post Caps & Sockets With Lag Screws - - - - -
1		Sides of Trim For 3/0x6/8 Door - - - - -	125	Lbs.	Sash Weights - - - - -
1		Sides of Trim For 4/0x6/8 Door - - - - -	BUILDING PAPER		
2		Sides of Trim For 2/6x6/8 Door - - - - -	6	Rolls 50 Lb.	Building Paper (500 Ft.Rolls) - - - - -
1		Sides of Trim For 2/0x6/8 Door - - - - -	SHEET METAL MATERIAL		
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	100	Sq.Ft.	Metal Roofing With Nails - - - - -
2		Sides of Trim For 1/10x4/6 0.S.Sash - - - - -	50	Lin.Ft. 14"	Valley Tin - - - - -
3	Triple	Sides of Trim For 1/6x4/6 0.S.Sash - - - - -	40	5x7	Tin Shingles - - - - -
10	Lin.Ft.	Closet Base - - - - -	80	Lin.Ft. 5"	Gutter Eaves Trough - - - - -
110	Lin.Ft.	Base - - - - -	24	5"	Hangers - - - - -
120	Lin.Ft.	Base Shoe - - - - -	1	5"	O.S.Mitres - - - - -
140	Lin.Ft.	Picture Mould - - - - -	1	5"	I.S.Mitres - - - - -
10	Lin.Ft.	Hook Strips - - - - -	16	5"	End Caps - - - - -
10	Lin.Ft.	Shelf Cleats - - - - -	8	5x3"	Drop Outlets - - - - -
8	Lin.Ft.	Thresholds - - - - -	110	Lin.Ft. 3"	Conductor Pipe - - - - -
Interior Finish: Balance of Rooms, First Floor			18	3"	Elbows - - - - -
1		Sides of Trim For 2/8x6/8 Door - - - - -	2-1/2	Doz. 3"	Conductor Pipe, Hooks - - - - -
4		Sides of Trim For 2/6x6/8 Door - - - - -	1	3"	Funnels - - - - -
1		Sides of Trim For 8x10 - 12 Lt.Window - - - - -	7	3"	Strainers - - - - -
1		Sides of Trim For 32x16 - 2 Lt.Window - - - - -	12	Lin.Ft.	Vents For Gas Flue - - - - -
50	Lin.Ft.	Base - - - - -	NAILS		
50	Lin.Ft.	Base Shoe - - - - -	85	Lbs. 20d	Common Nails - - - - -
40	Lin.Ft.	Chair Rail - - - - -	85	Lbs. 16d	Common Nails - - - - -
1	3/0	Thresholds - - - - -	35	Lbs. 10d	Common Nails - - - - -
Interior Finish: Second Floor			170	Lbs. 8d	Common Nails - - - - -
4		Sides of Trim For 2/6x6/6 Doors - - - - -	10	Lbs. 6d	Common Nails - - - - -
2		Sides of Trim For 2/4x6/6 Doors - - - - -	5	Lbs. 10d	Casing Nails - - - - -
2		Sides of Trim For 2/0x6/6 Doors - - - - -	50	Lbs. 8d	Casing Nails - - - - -
2		Sides of Trim For 2/0x6/6 Closet Doors - - - - -	10	Lbs. 6d	Casing Nails - - - - -
1		Sides of Trim For 2/6x4/6 Door - - - - -	5	Lbs. 10d	Finish Nails - - - - -
1		Sides of Trim For 8x12 - 12 Lt.Window - - - - -	15	Lbs. 8d	Finish Nails - - - - -
2		Sides of Trim For 8x10 - 12 Lt.Window - - - - -	5	Lbs. 6d	Finish Nails - - - - -
2		Sides of Trim For 2/0x4/3 0.S.Sash - - - - -	2	Lbs. 4d	Finish Nails - - - - -
1		Sides of Trim For 3/4x4/8 0.S.Sash - - - - -	1	Lb. 7/8"	Finish Brads (16 Gauge) - - - - -
1		Sides of Trim For 3/4x4/3 0.S.Sash With Wide Stool, See Plan - - - - -	60	Lbs. 3d	Shingle Nails Hot Dipped Zinc Coated - - - - -
1		Sides of Trim For 2/6x2/3 0.S.Sash - Closet - - - - -	10	Lbs. 8d	Cement Coated Nails For Siding - - - - -
150	Lin.Ft.	Base - - - - -	5	Lbs. 3d	Fine Lath Nails - - - - -
180	Lin.Ft.	Base Shoe - - - - -	60	Lbs. 5d	Galv.Hot Dipped Zinc Coated - - - - -
30	Lin.Ft.	Closet Base - - - - -	PAINT		
150	Lin.Ft.	Picture Mould - - - - -	1/2	Gals.	Outside Body Paint - - - - -
20	Lin.Ft.	Chair Rail - - - - -	3	Gals.	Outside Trim Paint - - - - -
26	Lin.Ft.	Hook Strips - - - - -	1/2	Gals.	Porch Ceiling Paint - - - - -
20	Lin.Ft.	Shelf Cleats - - - - -	1/2	Gals.	Blind or Shutter Paint - - - - -
Main Stair			1	Gals.	Sheet Metal Paint (Mineral) - - - - -
1		Angle Newel - - - - -	5	Gals.	Inside Varnish - - - - -
1		Landing Newel - - - - -	6	Gals.	Floor Varnish - - - - -
10		Treads - - - - -	1/2	Gals.	Spar Varnish - - - - -
13		Risers - - - - -	1/4	Gals.	Shellac - - - - -
4		Landing Treads - - - - -	2-1/2	Gals.	Liquid Wood Filler - - - - -
10		Rail - - - - -	1/2	Gals.	Flat White - - - - -
30	32"	Balusters - - - - -	3/4	Gals.	White Enamel - - - - -
8	Lin.Ft.	Nosing - - - - -	1	Gals.	Boiled Linseed - - - - -
8	Lin.Ft.	Face Mould - - - - -	2	Gals.	Turpentine - - - - -
26	Lin.Ft.	Wall String (2 Mem.) - - - - -	20	Lbs.	Putty - - - - -
8	Lin.Ft.	Face String - - - - -			
1	Set	Winders 2 Risers & 3 Treads - See Plan - - - - -			
1		Wall Rosette - - - - -			
14	Lin.Ft.	Wall Rail - - - - -			
5		Wall Rail Brackets - - - - -			
4		Stair Rail Acorn Ends - - - - -			


MATERIAL LIST FOR THE DECEMBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Feetage	Quantity	Size	ARTICLE AND DESCRIPTION	Feetage
LUMBER				LUMBER (CONTINUED)			
Wall Plates for Foundation				Inside Finish Lumber			
2 Pc.	2x6-20	Main Building Wall Plates - - - - -	40	5 Pc.	1x12-10	Shelving - - - - -	50
2 Pc.	2x6-18	Main Building Wall Plates - - - - -	36	3 Pc.1-1/4x10-14	Cellar Stair Treads - - - - -		44
8 Pc.	2x6-16	Main Building Wall Plates - - - - -	128	3 Pc.	1x8-14	Cellar Stair Risers - - - - -	28
4 Pc.	2x6-14	Main Building Wall Plates - - - - -	56	2 Pc.	2x4-10	Cellar Stair Rails - - - - -	13
Girders and Lintles				2 Pc.	1x4-8	Cellar Stair Rails - - - - -	5
1 Pc.	6x8-16	Main Building - - - - -	64	10 Pc.	4x6-10	Ceiling Beams - - - - -	200
2 Pc.	6x8-12	Main Building - - - - -	96	1 Pc.	1x12-14	Ceiling Beams Cut to Curve - - - - -	14
Girder Posts				500 Ft.	1x6	Wall Panelling - - - - -	500
4 Pc.	6x6-7	Main Building - - - - -	84	10 Ft.	1x4	Wall Panelling - - - - -	10
1 Pc.	6x10-7	Main Building - - - - -	35	2 Pc.	1x12-16	Studio Frieze - - - - -	32
Floor Joists, Headers, and Trimmers				INSULATION			
17 Pc.	2x10-20	First Floor Main Building - - - - -	567	2050 Sq.Ft.	Insulating Material - - - - -		
13 Pc.	2x10-18	First Floor Main Building - - - - -	390	MASONRY MATERIAL			
27 Pc.	2x10-16	First Floor Main Building - - - - -	720	Concrete Foundation 1-3-5 Mixture - 1234 Cu.Ft.			
1 Pc.	2x10-18	First Floor Box Sill - - - - -	30	37 Cu.Yds.	Crushed Stone or Gravel - - - - -		
4 Pc.	2x10-16	First Floor Box Sill - - - - -	107	22 Cu.Yds.	Coarse Sand - - - - -		
1 Pc.	2x4-8	Hearth Support - - - - -	5	52 Bbls.	Portland Cement - - - - -		
3 Pc.	2x10-22	Second Floor Main Building - - - - -	110	Stone Work			
17 Pc.	2x10-20	Second Floor Main Building - - - - -	567	50 Cu.Ft.	Stone Trim - - - - -		
3 Pc.	2x10-16	Second Floor Main Building & Headers - - - - -	80	80 Sq.Ft.4"	Stone Facing - - - - -		
9 Pc.	2x10-14	Second Floor Main Building - - - - -	210	80 Sq.Ft.4"	Flagstone - - - - -		
2 Pc.	2x10-12	Second Floor Main Building - - - - -	40	Cement Floor and Steps - 833 Sq.Ft.			
3 Pc.	1x10-14	Fire Stop - - - - -	35	8-1/4 Cu.Yds.	Crushed Stone or Gravel - - - - -		
Ceiling Joists				5-1/2 Cu.Yds.	Coarse Sand - - - - -		
18 Pc.	2x6-12	Main Building - - - - -	216	12-3/4 Bbls.	Portland Cement - - - - -		
8 Pc.	2x6-8	Main Building - - - - -	64	Brickwork			
1 Pc.	2x6-16	Joist Headers - - - - -	16	3100	Common Brick - - - - -		
9 Pc.	2x4-6	Main Building Over Studio - - - - -	36	9000	Face Brick - - - - -		
6 Pc.	2x4-9	Front Porch - - - - -	36	12 Bbls.	Lime - - - - -		
1 Pc.	2x2-12	Porch Ceiling Ledger - - - - -	4	12 Cu.Yds.	Sand - - - - -		
Outside Studs				1 Bbl.	Portland Cement - - - - -		
114 Pc.	2x4-8	Main Building - - - - -	608	1800	Ties For Brick Veneer - - - - -		
45 Pc.	2x4-9	Main Building - - - - -	270	Cut Stone			
6 Pc.	2x4-12	Gables (Main) - - - - -	48	1	Stone Door Sill 3'4" Long - - - - -		
12 Pc.	2x4-10	Gables (Main) - - - - -	80	1	Stone Door Sill 3'6" Long - - - - -		
11 Pc.	2x4-8	Gables (Main) - - - - -	59	Iron and Steel			
4 Pc.	2x4-6	Porch Gables - - - - -	16	1	4x6x3/8"	Angle Iron 6'8" Long - - - - -	
46 Pc.	2x4-8	Dormers - - - - -	245	1	4x6x3/8"	Angle Iron 5'6" Long - - - - -	
8 Pc.	2x6-8	Window Lintles - - - - -	64	4	4x4x1/4"	Angle Iron 2'8" Long - - - - -	
Inside Studs				1	4x4x1/4"	Angle Iron 2'6" Long - - - - -	
90 Pc.	2x4-8	First Floor - - - - -	480	1	4x4x1/4"	Angle Iron 2'2" Long - - - - -	
12 Pc.	2x6-8	First Floor - - - - -	96	2	4x4x1/4"	Angle Iron 4'4" Long - - - - -	
3 Pc.	2x6-16	First Floor Part. Headers - - - - -	48	1	4x4x1/4"	Angle Iron 3'8" Long - - - - -	
63 Pc.	2x4-8	Second Floor - - - - -	336	7	4x4x1/4"	Angle Iron 3'10" Long - - - - -	
24 Pc.	2x4-9	Second Floor Cut - - - - -	144	Fireplace			
4 Pc.	2x6-8	Second Floor - - - - -	32	1 Set	Stone Fireplace Blocks, See Plan - - - - -		
Stud and Partition Plates				40	Face Brick - - - - -		
38 Pc.	2x4-14	Outside Walls - - - - -	355	130	Fire Clay Brick - - - - -		
50 Pc.	2x4-12	Inside Partitions - - - - -	400	15 Sq.Ft. 2"	Flagstone - - - - -		
4 Pc.	2x6-12	Inside Partitions - - - - -	48	50 Lbs.	Fire Clay - - - - -		
Rafters				26 Lin Ft. 8x12"	Flue Lining - - - - -		
30 Pc.	2x6-18	Main Building & Porch - - - - -	540	14 Sq.Ft. 1/2"	Wire Mesh Reinforcing For Hearth - - - - -		
26 Pc.	2x6-16	Main Building - - - - -	416	1	Damper - - - - -		
5 Pc.	2x6-20	Main Building - - - - -	100	1	Ash Dump - - - - -		
19 Pc.	2x6-12	Dormers - - - - -	228	1	Cleanout Door - - - - -		
10 Pc.	2x6-14	Dormers (Cut) - - - - -	140	1	Angle Iron 3'8" Long - - - - -		
2 Pc.	1x8-16	Ridge Boards - - - - -	21	2	Chimney Pots, See Plan - - - - -		
2 Pc.	1x8-12	Ridge Boards - - - - -	16	20 Lin.Ft. 12"x12"	Flue Lining - - - - -		
2 Pc.	2x8-18	Valley Rafters - - - - -	48	Plastering			
Step and Stair Carriages				530 Yds.	Plaster, Including Metal Lath Corner Strips, Plaster, Base, Nails, and Metal Corner Beads - - - - -		
2 Pc.	2x10-14	Cellar Stairs - - - - -	47	12 Yds.	Cement Plaster, Including Metal Lath & Staples (For Over Boiler Space) - - - - -		
2 Pc.	2x10-16	Main Stairs - - - - -	53	Exterior Stucco			
4 Pc.	2x6-16	Main Stairs Platform Framing - - - - -	64	20 Sq.Yds.	Stucco For Gables, Including Metal Lath and Staples - - - - -		
Sheathing, Boards, Sub-flooring, Furring, Etc.,				ORNAMENTAL IRON			
910 Ft.	1x4	Roof Sheathing S.2.S.Laid 4-1/2"O.C. - - - - -	910	1	W.I.Chimney Anchor, See Plan - - - - -		
680 Ft.	1x6	Roof Sheathing D&M Over Rooms Only - - - - -	680	MILLWORK			
1650 Ft.	1x6	Sub-flooring S.2.S.Laid Diagonally - - - - -	1650	Outside Millwork and Mouldings			
2200 Ft.	1x8	Box Sheathing O.S.Walls Shiplap - - - - -	2200	340 Lin.Ft.	Bed Moulding - - - - -		
		Laid Diagonally - - - - -		40 Lin.Ft.	Cove Moulding - - - - -		
175 Ft.	1x6	Ribbons, Backing & Furring - - - - -	175	20 Lin.Ft.	1/4 Round Moulding - - - - -		
22 Pc.	1x2-10	Furring Outside Walls (Stucco Gables) - - - - -	37	4	6x12x2/0 Porch Fillets, See Plan - - - - -		
8 Pc.	1x2-8	Furring Inside Walls (Chimney Breast) - - - - -	11	Outside Door Frames			
1000 Lin.Ft.	1x1	Ground (Around Inside Openings) - - - - -	83	1	2/10x6/8x1-3/4	Front Door Frame For Brick Veneer - - - - -	
110 Ft.	1x4	Bridging - - - - -	110	1	2/8x6/8x1-3/4	Rear Door Frame For Brick Veneer - - - - -	
35 Ft.	1x4	Lookouts - - - - -	35	Window and Sash Frames			
80 Ft.	1x2	Floor Stripping 2nd Floor Only - - - - -	80	6	10x12x1-1/8	3 Lt.Cellar Sash Frames Plank - - - - -	
Siding For Outside Walls				1	Mullion 20x16x1-3/8	2 Lt.Ok.Rail Window Frames P&P For Brick Veneer - - - - -	
210 Ft.	3/4x10"	Bev.Siding 1" Lap. - - - - -	210	4	1'8"x4'6"x1-3/8	O.S.Sash Frames For Brick Veneer - - - - -	
40 Ft.	3/4x10"	Bev.Siding Rough Cut - 1-1/2" Lap. (Porch Gable & Blinds) - - - - -	40	1	1'6"x3'6"x1-3/8	O.S.Sash Frames For Brick Veneer - - - - -	
Flooring and Ceiling				1	1'2"x2'6"x1-3/8	O.S.Sash Frames For Brick Veneer - - - - -	
585 Ft.	3/4x3-1/4	Flooring, Main Rooms First Floor - - - - -	585	1	3'4"x4'6"x1-3/8	O.S.Sash Frames For Brick Veneer - - - - -	
240 Ft.	3/4x3-1/4	Flooring, Balance First Floor - - - - -	240	1	3'4"x4'0"x1-3/8	O.S.Sash Frames For Brick Veneer - - - - -	
574 Ft.	3/4x3-1/4	Flooring, Second Floor - - - - -	574	3	1'8"x4'6"x1-3/8	O.S.Triples Sash Frames For Brick Veneer - - - - -	
60 Ft.	5/8x3-1/4	Ceiling Porches 6 Ft.Lengths - - - - -	60	2	3'4"x4'6"x1-3/8	O.S.Sash Frames For Stucco Wall No Casings - - - - -	
Shingles				2	3'4"x4'6"x1-3/8	O.S.Sash Frames For 2x4" Wall No Headcasings - - - - -	
17 Squares 5/2		Shingles For Roof Certigrade Red Cedar 4-1/2" Exposure - - - - -		1	1'10"x4'0"x1-3/8	O.S.Sash Frames For 2x4" Wall No Headcasings - - - - -	
Lath							
200	48"	Exterior Lath (For Brick Veneer Wall Furring) - - - - -					
Outside Finish Lumber							
120 Ft.	1x8	Facias & Plancier - - - - -	120				
45 Ft.	1x6	Frieze - - - - -	45				
140 Ft.	1-1/4x6"	Stucco Panel Boards - - - - -	140				
56 Ft.1-1/4x8"		Stucco Panel Boards - - - - -	56				
3 Pc.	8x8 8/0	Porch Columns - - - - -	128				
1 Pc.	6x8 18	Porch Beams - - - - -	72				
25 Ft.1x4 to 1x10		Miscellaneous O.S.Finish - - - - -	25				


MATERIAL LIST FOR THE DECEMBER 1938 CITY CALENDAR

Quantity	Size	ARTICLE AND DESCRIPTION	Quantity	Size	ARTICLE AND DESCRIPTION
MILLWORK (CONTINUED)			MILLWORK (CONTINUED)		
Louvers			Cabinets		
2	3'0"x1'10"	Triangle Louvers, See Plan - - - - -	1 Set		Open Book Shelves, See Plan - - - - -
Windows and Sash			1		Mantel Shelf & Trim, Including Brackets, See Plan - -
6	10x12x1-1/8	3 Lt.Cellar Sash Glz. S.S. - - - - -	1		Telephone Cabinet - - - - -
2	20x16x1-3/8	2 Lt.Ck.Rail Window Glz. Glz. Div. 6 Lt. - -	1		Medicine Cabinet - - - - -
13	1'8"x4'6"x1-3/8	O.S.Sash Glz. Div. 8 Lt.Each Sash - - - - -	1		Cabinet For Breakfast Room, Complete with (See Plan) Hardware - - -
1	1'10"x4'0"x1-3/8	O.S.Sash Glz. Div. 8 Lt.Each Sash - - - - -	2	3'4"	Combination Kitchen Cabinets and Worktables Complete with Hardware, See Plan - -
1	1'6"x3'6"x1-3/8	O.S.Sash Glz. Div. 6 Lt.Each Sash - - - - -			
1	1'2"x2'6"x1-3/8	O.S.Sash Glz. Leaded See Plan - - - - -			
5 Pr.	3'4"x4'6"x1-3/8	O.S.Sash Glz. Div. 8 Lt.Each Sash - - - - -			
1 Pr.	3'4"x4'0"x1-3/8	O.S.Sash Glz. Div. 8 Lt.Each Sash - - - - -			
Blinds					FINISH HARDWARE
1 Pr.		Blinds For 3/4x4/6 Opg.Size Sash - - - - -	6		Cellar Sash Sets - - - - -
4 Single		Blinds For 1/8x4/6 Opg.Size Sash See Plan - -	3 Pr.	4x4	Door Butts - - - - -
Doors and Jambs For			8 Pr.	3-1/2x3-1/2	Door Butts - - - - -
1	2/10x6/8x1-3/4	Main Rooms First Floor	26 Pr.	3x3	Casement Sash Butts, - - - - -
1	2/6x6/8x1-3/8	Front Door "V" Joint Glz. See Plan - - - -	1 Pr.	2-1/2	Cupboard Door Butts, Narrow - - - - -
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	2 Pr.	3-1/2x3-1/2	Bathroom Door Butts - - - - -
2 Sets	7/8x5-5/8	Inside Door Panelled - - - - -	1 Pr.	2-1/2	Medicine Cabinet Butts, Narrow - - - - -
		Door Jambs For 2/6x6/8 Doors or Smaller - - -	2 Pr.	3x3	Casement Sash Butts, Bathroom - - - - -
For Balance - First Floor					Front Door Lock Set - - - - -
1	2/8x6/8x1-3/4	Rear Door Glz. - - - - -	1		Rear Door Lock Set - - - - -
1	2/8x6/8x1-3/8	Inside Door Panelled - - - - -	8		Inside Door Lock Sets - - - - -
1	2/6x6/8x1-3/8	Inside Door Panelled - - - - -	2		Bathroom Door Lock Sets - - - - -
1	2/0x6/8x1-3/8	Inside Door Panelled - - - - -	3		W.I.Ornamental Hinge Plates, See Plan - - -
1	1/8x6/8x1-3/8	Inside Door Panelled - - - - -	2 Sets	1-3/8"	Floor Double Acting Hinge - - - - -
2 Sets	7/8x5-5/8	Door Jambs For 2/8x6/8 Doors or Smaller - - -	4		Push Plates - - - - -
1 Set	7/8x7-5/8	Door Jambs For 2/6x6/8 Doors - - - - -	14 Sets		Casement Sash Fasteners, Single - - - - -
1 Set	7/8x3-5/8	Door Jambs For 2/0x6/8 Doors - - - - -	6 Sets		Casement Sash Fasteners, Double - - - - -
		Door Jambs For 2/0x6/8 Doors - - - - -	2 Sets		Casement Sash Fasteners, Single Bath & Lav. -
Doors and Jambs For			2		Sash Locks - - - - -
		Second Floor	4		Sash Lifts - - - - -
2	2/6x6/6x1-3/8	Inside Door Panelled - - - - -	1		Cupboard Turn - - - - -
1	2/4x6/6x1-3/8	Inside Door Panelled - - - - -	1		Cupboard Turn, Med.Case - - - - -
2	2/0x6/6x1-3/8	Inside Door Panelled - - - - -	9		Metal Base Knobs - - - - -
1	1/0x6/6x1-3/8	Inside Door Panelled - - - - -	1		Metal Base Knobs, Bathroom - - - - -
2 Sets	7/8x5-5/8	Door Jambs For 2/6x6/6 Doors - - - - -	4 Doz.		Coat and Hat Hooks - - - - -
4 Sets	7/8x3-5/8	Door Jambs For 2/4x6/6 Doors or Smaller - - -	3 Sets		Gravity Blinds Hangers - - - - -
1 Set	12x16x7/8"	Pipe Door, Jambs & Trim - - - - -			
Interior Finish, Main Rooms, First Floor			Rough Hardware		
1		Sides of Trim For 2/10x6/8 Door - - - - -	1 Hank		Sash Cord - - - - -
1		Sides of Trim For 2/6x6/8 Door - - - - -	26	1/2x16"	Anchor Bolts With Nuts & Washers - - - - -
1		Sides of Trim For 2/0x6/8 Door - - - - -	4 Sets	6"	C.I.Post Caps & Sockets, With Lag Screws - -
1		Sides of Trim For 2/0x6/8 Closet Door - - - - -	1 Set		Special C.I. Post Cap & Socket With Lag Screws See Pl.
4		Sides of Trim For 1/8x4/6 O.S.Sash - - - - -	40 Lbs.		Sash Weights - - - - -
1		Sides of Trim For 1/2x2/6 O.S.Sash - - - - -			
3 Triple		Sides of Trim For 1/8x4/6 O.S.Sash - - - - -			
120 Lin.Ft.		Base - - - - -			BUILDING PAPER
130 Lin.Ft.		Base Shoe - - - - -	6 Rolls	50 Lb.	Building Paper (500 Ft.Rolls) - - - - -
150 Lin.Ft.		Picture Mould - - - - -			
10 Lin.Ft.		Closet Base - - - - -			SHEET METAL MATERIAL
10 Lin.Ft.		Hook Strips - - - - -	100 Lin.Ft.	14"	Valley Tin Flashing - - - - -
10 Lin.Ft.		Shelf Cleats - - - - -	100 Pc.	10x12"	Tin Shingles - - - - -
1 Pc.	3/6	Thresholds - - - - -	90 Lin.Ft.	5"	Gutter Eaves Trough - - - - -
Interior Finish: Balance of Rooms, First Floor			24 Pc.	5"	Hangers - - - - -
2		Sides of Trim For 2/8x6/8 Doors - - - - -	1	5"	I.S.Mitres - - - - -
3		Sides of Trim For 2/6x6/8 Doors - - - - -	9	5"	End Caps - - - - -
1		Sides of Trim For 1/8x6/8 Doors - - - - -	5	5x3"	Drop Outlets - - - - -
2		Sides of Trim For 2/0x6/8 Doors - - - - -	50 Lin.Ft.	3"	Conductor Pipe - - - - -
1		Sides of Trim For 1/8x6/8 Closet Door - - - - -	10	3"	Elbows - - - - -
1		Sides of Trim For 20x16 - 2 Lt.Mull Window - -	1 Doz.	3"	Conductor Pipe, Hooks - - - - -
1		Sides of Trim For 3/4x4/6 O.S.Sash - - - - -	1	3"	Funnel - - - - -
1		Sides of Trim For 3/4x4/0 O.S.Sash - - - - -	5	3"	Strainers - - - - -
1		Sides of Trim For 1/6x3/6 O.S.Sash - - - - -	16 Ft.		Vents For Gas Flue - - - - -
1		Sides of Trim For 2/8x6/8 Cellar & Stair Door -			
75 Lin.Ft.		Base - - - - -			NAILS
90 Lin.Ft.		Base Shoe - - - - -	80 Lbs.	20d	Common Nails - - - - -
65 Lin.Ft.		Chair Rail - - - - -	80 Lbs.	16d	Common Nails - - - - -
15 Lin.Ft.		Hook Strips - - - - -	25 Lbs.	10d	Common Nails - - - - -
10 Lin.Ft.		Shelf Cleats - - - - -	175 Lbs.	8d	Common Nails - - - - -
1 Pc.	3/0	Thresholds - - - - -	15 Lbs.	6d	Common Nails - - - - -
15 Lin.Ft.		Closet Base - - - - -	10 Lbs.	10d	Casing Nails - - - - -
Interior Finish: Second Floor			60 Lbs.	8d	Casing Nails - - - - -
4		Sides of Trim For 2/6x6/6 Doors - - - - -	5 Lbs.	6d	Casing Nails - - - - -
2		Sides of Trim For 2/4x6/6 Doors - - - - -	5 Lbs.	10d	Finish Nails - - - - -
2		Sides of Trim For 2/0x6/6 Doors - - - - -	15 Lbs.	8d	Finish Nails - - - - -
1		Sides of Trim For 1/0x6/6 Doors - - - - -	10 Lbs.	6d	Finish Nails - - - - -
1		Sides of Trim For 1/0x6/6 Closet Doors - - - - -	2 Lbs.	4d	Finish Nails - - - - -
2		Sides of Trim For 2/0x6/6 Closet Doors - - - - -	1 Lb.	7/8"	Finish Brads (16 Gauge) - - - - -
4		Sides of Trim For 3/4x4/6 O.S.Sash - - - - -	75 Lbs.	3d	Galv.Shingle Nails - Hot Dipped Zinc Coated -
1		Sides of Trim For 1/10x4/0 O.S.Sash - - - - -	10 Lbs.	8d	Cement Coated Nails For Siding - - - - -
135 Lin.Ft.		Base - - - - -	2 Lbs.	3d	Fine Lath Nails - - - - -
165 Lin.Ft.		Base Shoe - - - - -	2 Lbs.	20d	Cut Nails For Furring - - - - -
30 Lin.Ft.		Closet Base - - - - -			
115 Lin.Ft.		Picture Mould - - - - -			PAINT
25 Lin.Ft.		Chair Rail - - - - -	1-1/4 Gals.		Outside Body Paint - - - - -
24 Lin.Ft.		Hook Strips - - - - -	2-1/2 Gals.		Outside Trim Paint - - - - -
30 Lin.Ft.		Shelf Cleats - - - - -	1/4 Gals.		Porch Ceiling Paint - - - - -
Main Stair			1/2 Gals.		Blind or Shutter Paint - - - - -
1		Starting Angle Newel - - - - -	1/2 Gals.		Sheet Metal Paint (Mineral) - - - - -
1		Angle Newel - - - - -	5 Gals.		Insids Varnish - - - - -
2		Landing Newels - - - - -	6 Gals.		Floor Varnish - - - - -
1		Pilaster Newel - - - - -	1/2 Gals.		Spar Varnish - - - - -
1		Circle End Tread & Riser, See Plan - - - - -	1/4 Gals.		Shellac - - - - -
7		Treads - - - - -	2-1/2 Gals.		Liquid Wood Filler - - - - -
10		Risers - - - - -	3/4 Gals.		Flat White - - - - -
4		Landing Treads - - - - -	1 Gals.		White Enamel - - - - -
22 Lin.Ft.		Rail - - - - -	2 Gals.		Boiled Linseed Oil - - - - -
60 Pc.	32"	Balusters - - - - -	2 Gals.		Turpentine - - - - -
24 Lin.Ft.		Nosing - - - - -	15 Lbs.		Putty - - - - -
80 Lin.Ft.		Cove - - - - -			
8 Lin.Ft.		Face Mould - - - - -			
22 Lin.Ft.		Wall String (2 Mem.) - - - - -			
8 Lin.Ft.		Face String - - - - -			
1 Set		Winders - - - - -			
12 Lin.Ft.		Wall Rail - - - - -			
4		Wall Rail Brackets - - - - -			
4		Stair Rail Acorn Ends - - - - -			

FLOOR PLANS




SECOND FLOOR PLAN




FIRST FLOOR PLAN

JANUARY




SECOND FLOOR PLAN




FIRST FLOOR PLAN


FEBRUARY



MARCH




SECOND FLOOR PLAN




FIRST FLOOR PLAN

APRIL

FLOOR PLANS




SECOND FLOOR PLAN




FIRST FLOOR PLAN


MAY



JUNE




SECOND FLOOR PLAN




FIRST FLOOR PLAN

JULY




SECOND FLOOR PLAN




FIRST FLOOR PLAN

AUGUST


FLOOR PLANS



SEPTEMBER




SECOND FLOOR PLAN




FIRST FLOOR PLAN

OCTOBER




SECOND FLOOR PLAN




FIRST FLOOR PLAN

NOVEMBER



SECOND FLOOR PLAN



FIRST FLOOR PLAN

DECEMBER

EVERY
LIBRARY

EVERY
LIBRARY

EVERY
LIBRARY

